

STAR 18 JUL 10 1985

(NASA-TM-86673) PROCEEDINGS OF THE SEMINAR  
ON SPACE STATION HUMAN PRODUCTIVITY (NASA)  
747 p HC A99/MF E63 CSCI 05H

N85-29539

THEU

N85-29573

Unclass

21530

G3/54

---

# Proceedings of the Seminar on Space Station Human Productivity

---

Compiled by Marc M. Cohen and Erika Rosenberg

---

March 1985



National Aeronautics and  
Space Administration

---

# **Proceedings of the Seminar on Space Station Human Productivity**

---

Marc M. Cohen, Ames Research Center, Moffett Field, California  
Erika Rosenberg, San Jose State University, San Jose, California



National Aeronautics and  
Space Administration

**Ames Research Center**  
Moffett Field, California 94035



# TABLE OF CONTENTS

		Page
MONDAY		
Introduction	J. E. Queller	1-1
Introduction	M. K. Junge	1-3
CREW SAFETY ALTERNATIVES STUDY		
Space Station Crew Safety	M. M. Cohen	1-4 to 1-15
Third Quarter Status Briefing	B. Peercy L. Rockoff	1-16 to 1-82
TUESDAY		
INTERNAL CONTAMINATION	J. Queller W. Hoffler	2-1 to 2-3
Statement of Contamination Problem	W. Hoffler	2-4 to 2-13
Shuttle Experiences:		
Internal Contamination Issues	L. Rockoff	2-14 to 2-29
Materials and Processes Control for Space Application	G. A. Blackburn	2-30 to 2-39
Ventilation Flow--Submerged	D. Hutchinson	2-40 to 2-69
Contamination Control Experiences:		
Toxicity and the Smoke Problem	H. Kaplan	2-70
Industrial Atmospheric Monitoring: Ambient Air Contamination-- Characterization and Detection Techniques	C. Nulton	2-71 to 2-79

#### Atmospheric Contamination:

Extended Mission Life Support Systems	P. Quattrone	2-80 to 2-98
Space Shuttle Air Revitalization System	P. Quattrone	2-99 to 2-128
Internal Contamination in the Space Station	C. Poythress	2-129 to 2-153
Space Station Trace Contaminant Control	T. Olcott	2-154 to 2-169

#### WEDNESDAY

##### Detection and Control

Gas Chromatography: Possible Application of Advanced Instrumentation Developed for Solar System Exploration to Space Station Cabin Atmospheres	G. Carle	3-1 to 3-15
Mass Spectrometry at the Jet Propulsion Lab	C. Griffin	3-16 to 3-32
Trace Gas Analyzer and NASA Experience: Atmosphere Monitoring Requirements	M. Ruecker	3-33 to 3-61
Some Problems Associated with Trace Contaminant Removal Systems for Spacecabins	T. Wydeven	3-62 to 3-76
Contamination Control for Increased Crew Productivity	D. Heppner	3-77 to 3-105
Human Productivity Program Definition	D. Cramer	3-106 to 3-131
The Human Role in Space (THURIS)	H. Wolbers	3-132 to 3-175

#### THURSDAY

Overview	M. Cohen	4-1 to 4-27
----------	----------	----------------

A Preliminary Human Factors Planning and Design Outline of Parameters Related to Space Station Windows and CCTV Monitoring	R. Haines	4-28 to 4-40
View graphs re SS Windows	R. Haines	4-41 to 4-59
Johnson Space Center Configurations	J. Lewis	4-60 to 4-72
Man Machine Trade-Off Study	A. Feinberg	4-73 to 4-82
Some Ideas and Questions Regarding Space Station Design	S. S. Kolnick	4-83 to 4-91
Underseas Habitat Design	T. Taylor and J. Spencer	4-92 to 4-107
Considerations for SS Interior Architecture	B. Griffin	4-108 to 4-170
ECLSS Module Concept	C. Poythress	4-171 to 4-184
Habitability Sleep Accommodations	H. Fisher	4-186 to 4-197
Design of Confined Environments	M. Kalil	4-198
Customer and Mission Influences on Space Station Architecture	F. Runge	4-199 to 4-215
FRIDAY		
Ames Mock-up Ideas	M. Cohen	5-1 to 5-3
Simulation for Human Factors Research	D. Nagel	5-4 to 5-7
EVA Orbital Servicing Equipment	H. Vykukal	5-8 to 5-10
SS Models, Mockups and Simulators	K. Miller	5-11 to 5-18

Mock-up and Human Productivity Studies	T. Fisher	5-19 to 5-38
Experiences with Neutral Buoyancy Testing Mockups	R. Dellacamera	5-39 to 5-47
Rockwell Experience Applications to Ames Space Station Mockup Habitability/Productivity Studies	J. Roebuck	5-48 to 5-64
Role of Mock-ups in the Development of Orbital Replaceable Units (ORU)	G. Johnson	5-65 to 5-90

**HUMAN FACTORS IN SPACE STATION ARCHITECTURE**

**Minutes of Seminar on Space Station Human Productivity**

**Space Station Human Productivity Working Group Meeting**

**at NASA-Ames Research Center**

**Hosted by the Space Human Factors Office**

**Aero-Space Human Factors Division**

**Ames Research Center**

**National Aeronautics and Space Administration**

**March 1, 1984**

**Opening Address Angelo Guastaferrro, ARC**

The seminar opened with a welcoming address by Angelo "Gus" Guastaferrro, Deputy Director of Ames Research Center. Gus affirmed Ames Center management support for Human Factors Research for the space station and for the Human Productivity Program.

**Overview: Human Factors in Space Station Architecture Marc Cohen, ARC**

Marc, the seminar chair, presented an overview of key issues for the day's session. A description of current program status covered the early program assumptions, the Concept Development Group's (CDG) Initial Operational Capability (IOC) model and the CDG Autonomy Baseline. Specific Human Factors topics were covered as follows:

- (1) Space Human Factors
- (2) Architecture
- (3) Volume
- (4) Reference Orientation
- (5) Circulation
- (6) Privacy
- (7) Group Gathering Places
- (8) Visual Systems
- (9) Vibroacoustics
- (10) Structures: Shells
- (11) Mechanisms
- (12) Utilities
- (13) Function

This presentation was essentially a synopsis of a work in progress entitled *Space Station Architecture: Human Factors Definition*.

**Space Station Windows and Visual Systems Richard Haines, ARC**

Dick presented a paper entitled "A Preliminary Human Factors Design Planning Outline Related to Space Station Windows and CCTV Monitoring." In this paper, he discussed issues of window size, shape and location. He compared the capabilities and limitations of direct human vision to indirect vision by closed circuit television (CCTV). Asking the question, "Where do we need outside surveillance?" he discussed several EVA, rendez-vous and docking situations. The key variables for observation windows are inter-module spacing, window orientation, module radius and the field of view half-angle. Dick concluded with the recommendation that the viewing distance from the eye to the window be kept as short as possible.

**JSC Configurations Jim Lewis, JSC**

Jim presented a discussion of "JSC Configurations." He showed some remarkable color computer graphic slides of the "Big T" and "Delta" configurations. Then he described his Crew Station Group's estimated volume and area requirements for crews of four, six and eight people. He presented plan and section-elevation views of proposed module arrangements based on these estimates and concluded with a "Conceptual 48-Hour Space Station Time Line," which attempts to breakdown crew resources and activities over a typical two day period or cycle of work and living.

**Man/Machine Interaction in Resources Module and MBA Abe Feinberg, JPL**

Abe presented a brief overview of the proposed JPL research program in "Space Station Automation Assessment," with a focus on Man-Machine Tradeoff Studies. In their preliminary investigations, Wayne Zimmerman and Abe have selected the Resources or Utility Module and the Multiple Berthing Adapter (MBA) for detailed analysis. They hope to arrive at an assessment of the impact of autonomy on reliability, among other goals.

**Design for Skylab Habitability at Raymond Loewy Sharon Skolnick**

Sharon began with an anecdotal history of the earliest space station habitability studies conducted at Raymond Loewy/Wm. Snaith Industrial Design, Inc. during 1969. Raymond Loewy was responsible for many design artifacts of the twentieth century including the Coca-Cola bottle, the standard desktop telephone, the Studebaker and streamlined locomotives. The Loewy involvement represented an attempt to achieve design excellence at the inception of NASA's first space station effort. Then Sharon presented a critique of the final Skylab design. She pointed out that in many respects, the interior spaces of both the Airlock and Multiple Docking Adapter (MDA) on Skylab were not designed. The engineers had taken a cylindrical form, packed the inside walls with equipment and any habitable volume was purely residual. She discussed the crew deck and made the novel observation that although the sleeping compartments were of differing sizes, the fact that they were different shapes, and that the wardroom and other walls were at varied angles probably created a more interesting and stimulating environment than if all areas had been uniform and regularized.

**Human Productivity Experience and Undersea Habitat Design Tom Taylor, TAI and John Spencer, SHDA**

This presentation was a joint effort by Tom Taylor and John Spencer, who have collaborated previously. Tom Taylor conceived of the Aft Cargo Carrier (ACC) on the STS External Tank (ET) and John was his subcontractor for habitability applications of both the ET and the ACC. Tom began the presentation with a description of his experience as a heavy construction engineer on the North Slope of Alaska, living for three years in remote, isolated, and confined habitats within a severe and hostile environment. He compared two different construction camps and observed that the most important factors in human productivity were food, privacy and group gathering places separate from sleeping quarters. John Spencer described the activities of SHDA in developing the ACC space station module concept. He described also a conceptual design for an undersea habitat in which a "Privacy Gradient" is created from the diver's entry hatch/wettest area to the sleeping quarters/driest area.

**Considerations for Space Station Interior Architecture Brand Griffin, Boeing**

Brand began with a detailed description of Zero Gravity "Neutral Body" anatomical changes, angular relationships, skeletal and muscular effects, vision and orientation and the work station envelope. He then covered shuttle cargo bay characteristics and limitations, addressing the implications for module shell and interior design. This analysis led to the description of a great variety of interior architectural options for a spectrum of crew sizes and mission requirements. He presented detailed cut-away drawings with a special emphasis on berthing accommodations for side to side berthing of reduced-diameter modules in the "Vertical Raft" configuration.

**The ECLSS Module Concept Chris Poythress, Hamilton Standard**

Chris presented a new Hamilton Standard concept for a special, dedicated Environmental Control and Life Support System Module as an alternative to the old debate between centralized and decentralized/distributed life support systems. In this concept, the ECLSS module would carry

the ECLS for one or more adjacent space station modules, the health and hygiene facility, including a shower and an airlock for EVA with EVA (EMU) suit support. All these functions would be packed into a one segment common module, half the size of the pressurized portion of the proposed logistics module, and would remove from the logistics module the burden of hauling the hygiene facility up and down every 90 days. However, because the life support and hygiene are in a module separate module from the rest of the station, it would be possible to return them to earth for maintenance or repairs, perhaps once every two years. Redundancy would be achieved by always having two or more ECLS modules operational on the station.

#### **Design of Confined Environments    Michael Kalil, Michael Kalil Designs**

Michael presented a slide show of two environmental mock-ups. The first mock-up was an apartment interior in New York City and the second was a 22 foot diameter room for the Armstrong Corporation in Lancaster, PA (the same diameter as Skylab). Michael presented an innovative approach to "building-in" all types of furniture and fixtures to be "deployed" from the floor and walls. Using this technique, he is able to achieve a high degree of flexibility in configuring the room interior both functionally and aesthetically. In a comment on the CDG Common Module Study Group approach of "Take this module and stuff it," Michael said: "Space is not made by 'stuffing' a form. Space is made by unfolding form to necessity" The modular, panelized walls and floors are "a continuous ribbon of matter that expands and contracts."

#### **Vertical Versus Horizontal Sleep Compartments    Tom Fisher, Lockheed**

Tom presented a very detailed discussion of "Habitability Sleep Accommodations." He showed slides of the Lockheed "revolver" concept for sleeping quarters as part of a living quarters module. This concept is characterized by great flexibility in accommodating from four to eight crew without requiring construction changes but by the adjustment of folding and sliding partitions. Tom concluded with a philosophical but rousing appeal for unity among the Crew Systems/Human Factors community. "We need values to respect and also to be open to new values." He pointed out that the smaller the environment, the more territorial people become, and the more problems we are likely to have. "The hardware people have beaten us every time before, but if we all

#### **Space Station Architecture    Fritz Runge, McDonnell-Douglas**

Fritz focused on "Customer and Mission Influences on Space Station Architecture," particularly the process of defining mission and operational requirements that become design drivers. These requirements led him to an emphasis on the "multiservice center" aspect of the station, an he explored various aspects of on-orbit servicing. Among the missions that received special attention were the laboratory modules and the Large Deployable Reflecting Telescope (LDR) that will be assembled by EVA on the "manned space platform" and then deployed on a free-flyer. Fritz illuminated the principle that different mission models will result in significantly different space station architectures.

#### **Critique of the Presentations    Maynard Dalton, JSC**

Maynard began by stating emphatically that he would not critique anyone's presentation, but would instead offer some general comments on the body of presentations as a whole:

- (1) Human Productivity studies will produce design drivers on a philosophical level only.
- (2) Only through the dimensions of habitation and habitability will the arrangement of modules be impacted by human productivity.



- (3) No matter how good the idea, if we cannot get it into space, it does not matter.
- (4) We must be prepared to make compromises. Let the development designers integrate pieces provided by conceptual ideas. It is not possible to make everybody happy, and ironically, if nobody is completely happy, the designer knows he has the best design.
- (5) We need a habitability/human productivity data base to draw upon. When opposing the hardware people, we strong quantitative and qualitative requirements. We need a data book that shows how people interact with the environment. Analog studies are educational, but not directly useful. We need space-specific standards. We need to show how people are affected by the environment, and through which modalities. Ultimately we must be able to prove and demonstrate a band of tolerance thresholds below which it is not acceptable to go.

### BRAINSTORMING

The day concluded with a brainstorming session. The results are listed below. Dr. B.J. Bluth commented that the session was useful in bringing forth many issues of new relevance to human productivity, to human productivity, but that there were no surprises overall, which provided a confirmation of the scope of earlier efforts at the Space Station Task Force, NASA H.Q.

#### Lighting

long term effects

task versus ambient interior environment

external lighting - overall level, pointing, shading

#### Food

grow on orbit

capability for bulk stores

#### Cost Savings

station self-replication

closed systems

#### Flight Experiments

simulation through "cheap mock-ups"

build a "National Mockup" for human productivity

peer review is essential for any form of "simulation" or "test bed"

#### EVA Coordination

payload servicing

communications during operations

radiation effects of Ku band radio

**Radiation - Consensus Needed**

model of radiation environment  
standard for human tolerance  
optimization of shielding  
integration trade study for the three items above

**Volume - Standard for Cubic Feet per Person**

sleep compartments/private cabins  
work areas  
How is volume defined?  
What is usable Volume?  
Allocation of Functions within volumes?

**Human Performance Measurement**

Great need for non-intrusive, reliable work-load metrics.

**Command Structure**

Crew selection  
Crew training  
Crew mix

**Crew Workspace**

small group dynamics  
psycho-social aspects  
windows, effects on crew performance  
disease transmission - biological contamination

**Exercise versus Workload**

schedule - rigor and flexibility  
location of exercise  
solitary or group activity  
stability of station - perturbations from crew motion  
quality of exercise

**Distributed Control - Social Impact**

alternatives to centralized, hierarchical control?  
democratic organization  
operational impacts?  
emergency situations?

**Station Autonomy**

data handling  
crew interaction with ground  
controlling groups for various functions  
Earth vs. on-orbit?

**Medical Facility**

health support systems  
scope of services  
location and proximities on station  
health information network

**Sensitive Issues**

sex  
death - handling a cadaver  
tolerance for deviant behavior

MONDAY

		Page
Introduction	J. E. Queller	1-1
Introduction	M. K. Junge	1-3
CREW SAFETY ALTERNATIVES STUDY		
Space Station Crew Safety	M. M. Cohen	1-4 to 1-15
Third Quarter Status Briefing	B. Peercy	1-16 to
	L. Rockoff	1-83

## INTRODUCTION

Judith E. Queller

The fourth meeting of the Human Productivity Working Group was held at the Ames Research Center from February 27 to March 2, 1984. It was attended by a total of 111 individuals over the course of a four day meeting. Attendees came from all of NASA, from private industry and from the academic community. The focus of the meeting was the exploration of the issues which surround some of the elements of the Human Productivity Program. Each of the elements was explored through presentations and these were followed by a general discussion and summary.

Five general topics were discussed: 1) crew safety, 2) internal contamination, 3) the definition of the Human Productivity Program, 4) aspects of architecture that affect productivity, 5) and the role of mock-ups in the Human Productivity Program.

The meeting was held at Ames in recognition of the creation of their new Aerospace Human Factors Research Division, and of the assertion by Ames' new Director, Dr. William Ballhaus, that Space Human Factors will be a principal thrust at Ames. This assertion was reaffirmed by Dr. Alan B. Chambers who opened the meeting on Monday, February 27, and welcomed the group.

The agenda for the Human Productivity Working Group meeting follows along with the proceedings of the meeting.

#### CREW SAFETY ALTERNATIVES

Space Station Crew Safety: Human Factors Model, Marc M. Cohen and Maria K. Junge, NASA-Ames Research Center.

Crew Safety Alternatives Study - Rockwell-Downey,  
3/4 Interim Briefing Review - Bob Peercy

- Overview
- Threats and Strategies
- Alternate Strategy

Human Factors Overview - Lisa Rockoff, Rockwell International Corp.

- Human Factors Issues
- Historical Background
- Question of Windows
- Personal Privacy and Space
- Safety Criteria Update
- Conclusions

## INTRODUCTION

Maria K. Junge

Videotape: EVA on STS-10 Lisa Rockoff, Rockwell-Downey

- Use of tools.
- Use of contingency procedures.
- Examples of poor quality communication between EVA astronauts, IVA astronauts and mission control.

### Speakers:

Bob Peercy- Manager, Systems Safety Group at Rockwell-Downey and a Program Manager on the Space Station Crew Safety Study.

Lisa Rockoff- Principal Engineer on the Space Station Crew Safety Study at Rockwell-Downey.

Dr. Steve Ellis- Staff Researcher in the Aerospace Human Factors Research Division at Ames Research Center and on the faculty at UC Berkeley.

# **SPACE STATION CREW SAFETY HUMAN FACTORS INTERACTION MODEL**

**MARC M. COHEN**

**FEB. 27, 1984**

**SPACE HUMAN FACTORS OFFICE,**

**LHS: 239-2**

**AERO-SPACE HUMAN FACTORS DIVISION**

**NASA—Ames Research Center**

**Moffett Field, CA 94035**

**NASA—Ames Research Center  
Space Human Factors Office**



SPACE STATION CREW SAFETY  
HUMAN FACTORS INTERACTION MODEL

Abstract by Marc M. Cohen and Maria K. Junge

Space Human Factors Office

NASA-Ames Research Center

Presented at NASA HQ, May 8, 1984

As NASA prepares plans to develop a space station, one of the major Human Factors study tasks is to develop an approach to Crew Safety. NASA has always been a paradigm of safety consciousness and recognizes that safety will be a key to reliability and human productivity on the space station.

In evaluating safety strategies, it is also necessary to recognize both qualitatively and quantitatively how this space station will be different from all other spacecraft. During the initial phase of this study, it was recognized that the major difference between space station and previous spacecraft is the role of human factors and extra-vehicular activity (EVA). In this project, a model of the various human factors issues and interactions that might affect crew safety is developed.


The first step addressed systematically the central question: How is this space station different from all other spacecraft? A wide range of possible issues was identified and researched. Five major topics of human factors issues that interacted with crew safety resulted: *Protocols, Critical Habitability, Work Related Issues, Crew Incapacitation and Personal Choice.*

Second, an interaction model was developed that would show some degree of cause and effect between objective environmental or operational conditions and the creation of potential safety hazards. The intermediary steps between these two extremes of causality were the effects on human performance and the results of degraded performance. The model contains three milestones: stressor, human performance (degraded) and safety hazard threshold. Between these milestones are two countermeasure intervention points. The first opportunity for intervention is the countermeasure against stress. If this countermeasure fails, performance degrades. The second opportunity for intervention is the countermeasure against error. If this second countermeasure fails, the threshold of a potential safety hazard may be crossed.

An example of how this interaction model works can be demonstrated. Under *Critical Habitability*, the primary environmental stressors include confinement, isolation and separation from earth. There are two subgroups of within the first countermeasure against these stressors, social and architectural interventions. The social factors are communication with family and friends, visitors to the station and recreation. The architectural factors are design, station geometry and "local vertical" reference orientations and windows. When these social and architectural design level countermeasures against stress are not effective, crew performance may degrade in the form of morale deterioration, impaired

judgement or faulty perceptions. The second set of countermeasures, against errors are operational or group social activities plus personal existential actions. These social subset countermeasures include group activities, hobbies and time for personal interests. The design/physical countermeasure subgroup includes color coding on interior functions, lighting and video systems. To the extent that this second defense of countermeasures is not successful, the threshold of potential safety hazards may be crossed. In this instance, potential safety hazards include a breakdown in group process and teamwork, and mistakes occurring in judgement, perception or action.

The third step, which is now in progress, is to apply a system of weighting to the various stressors and countermeasures in order to be able to evaluate their relative importance. This weighting will also require an element of time duration to identify which stressors or countermeasures are relevant at the beginning, middle or end of missions, and which are short-lived or chronic in nature.



# SPACE STATION CREW SAFETY HUMAN FACTORS CONCERNS

## 1. PROTOCOLS

- AUTONOMY FROM GROUND

## 2. WORK RELATED ISSUES

- TASK ASSIGNMENT
- ROLE DEFINITION

## 3. CRITICAL HABITABILITY


## 4. CREW INCAPACITATION

## 5. PERSONAL CHOICE

- INDIVIDUAL SCHEDULE CHANGES
- OPERATIONAL CHANGES
- WORK PROCEDURE CHANGES

NASA—Ames Research Center  
Space Human Factors Office


**SPACE STATION CREW SAFETY  
HUMAN FACTORS INTERACTION MODEL**



1-9

SPACE STATION CREW SAFETY  
HUMAN FACTORS INTERACTION MODEL


# 1. PROTOCOLS



NASA—Ames Research Center  
Space Human Factors Office

SPACE STATION CREW SAFETY  
HUMAN FACTORS INTERACTION MODEL


## 2. CRITICAL HABITABILITY I



NASA—Ames Research Center  
Space Human Factors Office

SPACE STATION CREW SAFETY  
HUMAN FACTORS INTERACTION MODEL

# CRITICAL HABITABILITY II




NASA-Ames Research Center  
Space Human Factors Office



SPACE STATION CREW SAFETY  
HUMAN FACTORS INTERACTION MODEL

### 3. TASK RELATED ISSUES



SPACE STATION CREW SAFETY  
HUMAN FACTORS INTERACTION MODEL

## 4. CREW INCAPACITATION

STRESSORS		DEGRADED PERFORMANCE		SAFETY HAZARD
	COUNTER-MEASURES AGAINST STRESS		COUNTER-MEASURES AGAINST ERRORS	
SPACE SICKNESS GAS BUBBLES IN WATER	SELECTION/ ADJUSTMENT MAINTAIN/CHECK FUEL CELLS	RELIABILITY GAS PAINS	TREATMENT SLING WATER TO SEPARATE GAS	CREW FAILURE TO RESPOND
ILLNESS	EXAMINATIONS AND HEALTH MAINTENANCE PROGRAM	SHORT TERM INCAPACITATION	TREATMENT	CONTAGION?
INJURY	SPACE INDUSTRIAL SAFETY	LONG TERM INCAPACITATION	RETURN TO EARTH? STABILIZE ON ORBIT?	DISTRACTION OF OTHER CREW MEMBERS
EMOTIONAL/ MENTAL PROBLEM	CREW SELECTION GROUP TRAINING	STRAIN ON OTHERS/ LACK OF TRUST	RELIEF FROM DUTY	SOCIALLY DEVIANT BEHAVIOR?
FAILURE IN LIFE SUPPORT SYSTEM	ABANDON, EVACUATE ONE MODULE	CONFINEMENT, TRAUMA	REPAIRS, REPLACE- MENT	LOSS OF ACCESS TO CRITICAL FUNCTIONS
DEATH	COUNSELING	TRAUMA TO CREW DISRUPTION OF TEAMWORK	COUNSELING	PRESERVATION OR DISPOSAL OF BODY LACK OF EXPERTISE ON BOARD

NASA—Ames Research Center  
Space Human Factors Office

SPACE STATION CREW SAFETY  
HUMAN FACTORS INTERACTION MODEL

## 5. PERSONAL CHOICE

STRESSORS	COUNTER-MEASURES AGAINST STRESS	DEGRADED PERFORMANCE	COUNTER-MEASURES AGAINST ERRORS	SAFETY HAZARD
COOKING/EATING HABITS	SHARED MEALS ACCOMMODATION FOR INDIVIDUAL CREW PREFERENCE	IRRITATION DEPRESSION	ADEQUATE TRAINING	FIRE SMELLS OUTGASSING
INDIVIDUAL PROPERTY	EDUCATION MONITORING AND CONTROL CREW TRAINING	PERSONAL AUTON- OMY DIMINISHED	MONITORING AND CONTROL	OUTGASSING CONTAMINATION FLAMMABILITY
BOREDOM, MONOTONY	ENTERTAINMENT CREW SELECTED ACTIVITIES	LACK OF VIGILANCE	ADEQUATE CREW ACTIVITIES PLANNING AND SCHEDULING	PRACTICAL JOES DISTRACTION ACCIDENTS
CLOTHING	VARIETY, LAUNDRY CREW PREFERENCE	IRRITATION, DISCOMFORT LESS PERSONAL FREEDOM	CLEAN FILTERS	LINT PROBLEM
INDIVIDUAL SCHEDULE CHANGES WORK PROCEDURE CHANGES OPERATIONAL CHANGES				
PERSONAL HABITS: SMOKING ALCOHOL DRUGS	CREW SELECTION CREW TRAINING	REASONS FOR CONCEALMENT WITHDRAWAL SYMPTOMS POOR HEALTH INTERFERENCE WITH DUTIES	COUNSELING? EVACUATION EARLY CREW CHANGEOUT	FIRE IMPAIRED JUDGMENT DESTRUCTION OF "TEAM"

**Space Station  
Crew Safety Alternatives Study**

**SSD84-0106**

---

**Third Quarter Status Briefing**

---

**CONTRACT NAS1-17242**

**27 FEBRUARY 1984**

**Space Station  
Crew Safety Alternatives Study**

**SSD84-0106**

---


**Third Quarter Status Briefing**

---

**CONTRACT NAS1-17242**

**27 FEBRUARY 1984**

1-18



## PURPOSE OF STUDY


---

- IDENTIFY THREATS THAT COULD CAUSE AN ESCAPE OR RESCUE DECISION
  - LOOK AT STRATEGIES WITHIN THE BASELINE TO ACCOMMODATE THESE THREATS - GENERATE CRITERIA
- IDENTIFY OPTIONS & PERFORM ROM COSTING FOR ESCAPE/RESCUE
- MAKE RECOMMENDATIONS FOR ADDITIONAL STUDY
  - SOFT AREAS
  - VOIDS

# CREW SAFETY STUDY

NAS1-17242

## • AREAS ADDRESSED OR BEING ADDRESSED




## • OBJECTIVE:

- IDENTIFY SAFETY ISSUES
- PROPOSE CONTROLLING CRITERIA

1-20



# STUDY SEGMENTS - HARDWARE





1-21

\* THURIS ISSUES?

# SCHEDULE SUMMARY

1-22






1-23

## STUDY APPROACH

1-24



SPACE STATION CREW SAFETY  
THREAT LIST

---

- ✓• FIRE
  - LEAKAGE
  - TUMBLING/LOSS OF CONTROL
- ✓• BIOLOGICAL OR TOXIC CONTAMINATION
- ✓• INJURY/ILLNESS
  - GRAZING/COLLISION
  - CORROSION
  - MECHANICAL DAMAGE
- ✓• EXPLOSION/IMPLOSION
- ✓• LOSS OF PRESSURIZATION
- ✓• RADIATION
  - OUT-OF-CONTROL IVA/EVA ASTRONAUT
  - INADVERTENT OPERATIONS
  - LACK OF CREW COORDINATION
  - ABANDONMENT OF SPACE STATION
- ✓• METEOROID PENETRATION
  - STORES/CONSUMABLES DEPLETION
  - STRUCTURAL EROSION
  - ORBIT DECAY
  - LOSS OF ACCESS TO A HATCH
  - TEMPERATURE EXTREMES
- ✓• DEBRIS
  - FREE ORBIT (EVA ASTRONAUT)

1-25

ORIGINAL PAGE IS  
OF POOR QUALITY

SPACE STATION SAFETY PHILOSOPHY PRECEDENCE  
(HOW MUCH SAFETY?)


1-26

CURRENT OPTIONS	COMMENTS
<ul style="list-style-type: none"> <li>• CAUSE NO DAMAGE WHATSOEVER TO SPACE STATION AND NO INJURY TO CREW</li> </ul>	DESIRABLE: COST TRADE
<ul style="list-style-type: none"> <li>• CAUSE NO DAMAGE TO SPACE STATION BEYOND ROUTINE MAINTENANCE CAPABILITY</li> </ul>	COST TRADE
<ul style="list-style-type: none"> <li>• CAUSE NO DAMAGE TO SPACE STATION OR INJURY TO CREW WHICH WILL RESULT IN A SUSPENSION OF OPERATIONS</li> </ul>	BASELINE PHILOSOPHY
<ul style="list-style-type: none"> <li>• SPACE STATION REPAIRABLE AND OPERATIONAL WITHIN A SPECIFIED PERIOD OF TIME</li> </ul>	MAY REQUIRE ESCAPE/RESCUE
<ul style="list-style-type: none"> <li>• CREW SURVIVAL AT EXPENSE OF THE SPACE STATION</li> </ul>	IMPLIES EVACUATION AND RESCUE. AS A MINIMUM

THREAT	CAUSATIVE FACTORS	STRATEGY(IES)
DEPRESSURIZATION	<u>UNPLANNED</u> <ul style="list-style-type: none"> <li>• PUNCTURE FROM DEBRIS</li> <li>• INADVERTENT CREW ACTION</li> <li>• INTERNAL/EXTERNAL LEAKAGE</li> </ul>	<ol style="list-style-type: none"> <li>1. CAPABILITY TO INSPECT/REPAIR INSIDE OF PRESSURE VESSEL</li> <li>2. STATION MINIMUM SURVIVAL FUNCTIONS (MANDATORY OPERATIONS AT ALL TIMES) SHOULD BE COLDPLATED</li> <li>3. HARDWARE FOR OTHER CRITICAL FUNCTIONS SHOULD BE CAPABLE OF BEING TURNED OFF</li> <li>4. NEED TO KNOW LOCATION OF ALL PERSONNEL IN ALL MODULES</li> <li>5. DISCRETE DEFINITION OF "TIME-TO-SURVIVE" NEEDED <ul style="list-style-type: none"> <li>• CONTAMINATION/TOXICITY</li> <li>• EXPLOSIVE DECOMPRESSION</li> <li>• INTERIM SURVIVAL DEVICES</li> </ul> </li> <li>6. INFLATABLE PRESSURE BULKHEAD</li> <li>7. PROVIDE SUBSYSTEM DESIGNERS WITH "MAXIMUM HOLE" TO SIZE LIFE SUPPORT SYSTEM WITH NUMBER OF CYCLES (PRESS/DEPRESS) STATED</li> </ol>
	<u>PLANNED</u> <ul style="list-style-type: none"> <li>• REMOVE CONTAMINATION</li> <li>• FIRE CONTROL - ALTERNATE</li> <li>• MAINTENANCE DEPRESSURIZATION</li> </ul>	<ol style="list-style-type: none"> <li>1. STATION SHOULD BE CAPABLE OF TBD PRESSURE VOLUME CHANGEOUTS (3 MINIMUM)</li> </ol>

1-27

## DEPRESSURIZATION ESCAPE/RESCUE OPTIONS





## EFFECTS OF A FIRE IN A MODULE IN SPACE

---

1-29

- REMOVAL OF OXYGEN FROM MODULE
  - PYROLIZE 4 TO 8 POUNDS OF SOLIDS
  - GENERATION OF HEAT
    - DISTORTION OF SOLIDS
    - CAN CAUSE FIRE TO BREAK OUT ON EXTERIOR OF MODULE WALL
  - REDUCED VISIBILITY
  - ADDITION OF CONTAMINANTS - MOST ARE TOXIC
    - SEVERAL THOUSAND COMPOUNDS WHEN PYROLYZED IN AIR
    - CARBON MONOXIDE MORE LIKELY TO BE PRESENT THAN IN ONE-G
  - OVERLOAD OF ATMOSPHERIC REVITALIZATION SYSTEM
    - ADDED STAGNATION IN ZERO-G
  - PRESSURE RISE MAY BE CATASTROPHIC
  - PYROLISIS PRODUCTS MAY BE FLAMMABLE
    - LEAKING CONTAINERS CAN SUPPLY FLAMMABLE BASES AFTER FIRE IS EXTINGUISHED
  - CORROSIVE RESIDUE
-

## VENTING AS A FIRE-MITIGATION STRATEGY

---

### PROS

- MAY PRECLUDE RUPTURE
- EXHAUSTS TOXIC CONTAMINANTS
- PRECLUDES EXPLOSIVE MIXTURES
- HELPS IN CLEAN-UP OPERATIONS - AVOIDS OVERLOADING ECLSS
- FOR PURE OXYGEN, FIRE SHOULD EXTINGUISH AT  $\sim .13$  PSIA, FOR 21% OXYGEN - FIRE SHOULD EXTINGUISH AT 2-OR 3 PSIA

### CONS

- IF FLAMMABLE LIQUIDS INVOLVED, MORE RAPID BURNING WITH POTENTIAL OF EXPLOSION AT LOWER PRESSURES.
  - WHAT IS PROPER RATE OF DEPRESSURIZING A VOLUME? IT VARIES WITH SITUATION.
    - CONVECTION OF VENTING
  - ALL CONNECTING PLUMBING MUST BE SEALED.
  - TOO RAPID A DEPRESSURIZATION WILL CONDENSE VAPORS, PRODUCE A FOG AND MAY INTENSIFY A FIRE BECAUSE OF HIGH TURBULANCE.
  - EXTERIOR DAMAGE - SUBLIMATION ON WINDOWS, RADIATORS, SENSORS, ETC.
  - PROPULSIVE VENTING MAY RESULT IN TUMBLING.
-

## THREAT IDENTIFICATION/STRATEGY DEVELOPMENT

---


### SUMMARY

- 23 THREAT CATEGORIES HAVE BEEN DEFINED
- 8 THREATS HAVE IMPACT TO PRELIMINARY DESIGN & CANDIDATE STRATEGIES WERE DEVELOPED DURING STUDY
- 22 OF THE 23 THREAT CATEGORIES CAN BE DEALT WITH BY PROPER DESIGN SOLUTIONS
- APPROXIMATELY 70 CRITERIA IDENTIFIED TO MITIGATE THREATS
  - 50 OF THESE CRITERIA WERE COLLECTED FROM LITERATURE SEARCH
  - 20 CRITERIA - SPACE STATION - UNIQUE
  - APPROXIMATELY 240 DESIGN GUIDELINES DEVELOPED TO AID IN IMPLEMENTING THE 70 CRITERIA
- MOST THREAT STRATEGIES NEED INCORPORATION AT EARLIEST POINT IN CONFIGURATION DEVELOPMENT TO MINIMIZE DOWNSTREAM HARDWARE/OPERATIONAL IMPACT

1-31

# INITIAL HUMAN FACTORS ASSESSMENTS SAFETY CRITERIA DEVELOPMENT


---



\*HOW IS THIS INCORPORATED INTO SPACE STATION DEVELOPMENT


---

1-33



## STUDY APPROACH

1-34



## ALTERNATE STRATEGY DEFINITIONS

---


ESCAPE: LEAVE AREA OF THREAT WITHOUT EXTERNAL AID

RESCUE: AID FROM EXTERNAL SOURCES (EXCLUDING BASELINE)\*

\*BASELINE: ROCKWELL CONFIGURATION AT BEGINNING OF STUDY  
AUGMENTED BY NORMAL SHUTTLE RESUPPLY MISSIONS

# ESCAPE AND RESCUE OPTIONS

1-36





# DISCRIMINATORS FOR ESCAPE/RESCUE SYSTEM OPTIONS

OPTION	COSTS		RESPONSE TIME	CREW SIZE	TECHNOLOGY RISK	TYPE OF CALAMITIES ACCOMMODATED
	MISSION CONTINUATION	SAFETY				
A EMERGENCY ESCAPE VEHICLES	** NONE	100% (2 VEHICLES MINIMUM) \$300 TO \$1500M	VARIES (10 min TO 1-1/2 hr)	1 TO 4 PER VEHICLE	MEDIUM TO VERY HIGH	<ul style="list-style-type: none"> <li>• FIRE*</li> <li>• TUMBLING*</li> <li>• MECHANICAL DAMAGE</li> <li>• EXPLOSION*</li> <li>• DEPRESSURIZATION*</li> <li>• METEROID PENETRATION*</li> <li>• DEBRIS</li> </ul> *SELECTED
B GO TO A SECOND STATION VIA A MANNED OTV	** NONE	NO COST	VARIES (15 min TO 1-1/2 hr)	TBD	MEDIUM	ALL OF ABOVE
C SAFE HAVEN EXTERNAL	** NONE	TOTAL COST \$300 TO \$500M	<1 hr	8	VERY HIGH	ALL OF ABOVE
D SAFE HAVEN INTERNAL	TOTAL COST	NO COST	<10 min	8	LOW	ALL OF ABOVE
E ORBITER VEHICLE	NONE	<\$1.0M/DAY	<15 min	10	VERY LOW	ALL OF ABOVE PLUS INJURY/ILLNESS

\*\*POTENTIAL LOSS OF MISSION

1-37

# WHAT WOULD CAUSE ESCAPE OF LESS THAN FULL CREW

1-38

1 MAN?	2 MEN?	3 MEN?
<ul style="list-style-type: none"> <li>• SOLE SURVIVOR</li> <li>• PHYSICAL MEDICAL ISSUE (CUT, SOME BURNS)</li> <li>• PSYCHOLOGICAL ISSUE</li> <li>• DECEASED</li> </ul>	<ul style="list-style-type: none"> <li>• TWO SOLE SURVIVORS</li> <li>• INDIVIDUAL CREWMAN MEDICAL ISSUE REQUIRING CONSTANT AID BY MEDIC               <ul style="list-style-type: none"> <li>• PHYSICAL</li> <li>• PSYCHOLOGICAL</li> </ul> </li> <li>• DECEASED</li> </ul>	<ul style="list-style-type: none"> <li>• THREE SURVIVORS (REMOTE PROBABILITY) ESCAPING IMPENDING DISASTER</li> <li>• DECEASED</li> </ul>

# PARAMETRIC EVALUATION ESCAPE, RESCUE, AND SURVIVABILITY CONCEPTS

Concept	Crew Size	Shirt-Sleeve	Technology	Development Risk	Launch Vehicles	Recovery
Escape						
Airmat	2	No	New	High	No	Water
Rib stiffened	3	Yes	New	High	No	Water
Paracone	1	No	New	High	No	Water
Moose	1	No	New	High	No	Water
Moses	2-4	No	Current	Low	No	Water/air
Encap	1	No	New	High	No	Water
Egress	1	Yes	New	Medium	No	Water
Life raft	3	No	New	High	No	Water
Lifting body	3	Yes	New	Medium	No	Water
EEOD	3	Yes	New	Medium	No	Water
Spherical heat shield	2	Yes	New	Medium	No	Water
Apollo Escape CM	2-6	Yes	Old	Very low	No	Water
Saver	1	No	New	Very high	No	Water
Rescue						
Shuttle	12	Yes	None extra	Low	***	Land
Hermes	Unk	Yes	New	Medium	Yes	Land
Apollo Rescue CSM	2-4	Yes	Current	Low (S-IB) Med (Titan)	Yes	Water
Rescue Ball	1	Yes	Current	Low	No	
Survivability*						
Cocoon	1	No	New	High	Only if needed***	Shuttle
Sortie module	12	Yes	Current	Medium		Shuttle
Space Station Module	12	Yes	Current	Medium		Shuttle
Apollo Survivability CM	8	Yes	Current	Medium		Shuttle
Modular Survivability Vehicle (MSV)	12	Yes	Current	Medium		Shuttle

\*Assumes shuttle used for rescue (10 people nominal; greater than 10 in emergency)

\*\*Low = 2000 kg (4500 lb), high = 4000 kg (9000 lb)


\*\*\*Launch vehicles are used only if a rescue or survivability situation arises. Dedicated launch vehicles not required.

# SPACE STATION CREW SAFETY THREAT LIST


1-40

CONTROLLABLE (N/A)	IMMEDIATE NEED (IM)	DELAY ALLOWED (DEL)	
X	X		FIRE
	X		LEAKAGE
	X		TUMBLING/LOSS OF CONTROL
	X TO X		BIOLOGICAL OR TOXIC CONTAMINATION
	X TO X		INJURY/ILLNESS
		X	GRAZING/COLLISION
X			CORROSION
	X TO X		MECHANICAL DAMAGE
	X TO X		EXPLOSION
	X TO X		LOSS OF PRESSURIZATION
		X	RADIATION
X			OUT-OF-CONTROL IVA/EVA ASTRONAUT
X			INADVERTENT OPERATIONS
X			LACK OF CREW COORDINATION
	X TO X		ABANDONMENT OF SPACE STATION
	X		METEOROID PENETRATION
X		X	STORES/CONSUMABLES DEPLETION
		X	STRUCTURAL EROSION
		X	ORBIT DECAY
	X TO X		LOSS OF ACCESS TO A HATCH
X			TEMPERATURE EXTREMES
	X		DEBRIS
X			FREE ORBIT (EVA ASTRONAUT)

TIME  
TO  
ADVERSE  
IMPACT



## THREATS REQUIRING ESCAPE/RESCUE



CANDIDATES FOR ACCEPTED RISKS  
(CATASTROPHES OF A CERTAIN MAGNITUDE)

---

- FIRE RESULTING FROM FUEL CELL, RCS, HYDRAULIC LINE RUPTURE
- IGNITION IN OXYGEN SYSTEM
- RCS CHAMBER OR MANIFOLD EXPLOSION
- DISINTEGRATION OF ROTATING COMPONENTS
- GENERIC SOFTWARE ANOMALY (LOSS OF STABILIZATION & CONTROL)
- LOSS OF CABIN PRESSURE
- CONTAMINATION OF BREATHING ENVIRONMENT
- STRUCTURAL FAILURE OF TANKS
- CONTACT WITH DEBRIS
- LOSS OF STABILIZATION (TUMBLING)

1-42

## ALTERNATE STRATEGY - SUMMARY

---

- LIMITS ON USE OF BALLISTIC REENTRY ESCAPE VEHICLES
  - SIZE OF CREW ACCOMMODATED
    - IMPLICATIONS ON NUMBER OF VEHICLES REQUIRED
  - LIFE-IN-ORBIT LIMITATIONS
    - PARACHUTES
    - ORDNANCE SYSTEMS (BATTERIES)
    - OTHER DEGRADATION

(E.G., WOULD ONE TRUST AN ESCAPE POD THAT HAD NOT BEEN USED IN 6 TO 8 YEARS?)

- THREATS ACCOMMODATED BY BALLISTIC REENTRY ESCAPE POD
- LIMITS ON RESCUE SCENARIOS
  - WORST-CASE LIFE SUPPORT REQUIREMENTS
    - 21 DAYS
  - THREATS ACCOMMODATED
  - SIZE OF CREW ACCOMMODATED
  - SAFE HAVEN vs RESCUE
  - STORM CELLAR - MINIMUM SURVIVAL CONDITIONS FOR LIMITED PERIOD OF TIME

1-413

## MAJOR OPEN ISSUES CREW SAFETY

---

### TECHNICAL

- SAFE HAVEN *is a problem but a problem*
  - LIMITATIONS OF MULTIPLE SAFE HAVENS CONCEPT
- DEPRESSURIZATION
  - HOW MANY VOLUME CHANGE-OUTS?
- RESOURCE MODULE CONCEPTS
  - MAINTENANCE IN AN UNPRESSURIZED MODULE IS A HIGH-RISK SITUATION
  - SINGLE MODULE IS A CONCEPTUAL SINGLE-FAILURE POINT
- DUAL EGRESS REQUIREMENT


### PROGRAMMATIC

- MISSION DEFINITIZATION IS LIMITED
- TOTAL SYSTEM SAFETY vs INDUSTRIAL SAFETY
  - VARIABLE FACILITY SYNDROME *(by changing cargo)*
- TOTAL SYSTEM SAFETY INTEGRATION FUNCTION
- NO PROBLEM REPOSITORY FOR NON-DESIGN CRITERIA

ORIGINAL PAGE IS  
OF POOR QUALITY

1-44






1-45

# CREW SAFETY STUDY

NAS1-17242

## • AREAS ADDRESSED OR BEING ADDRESSED




## • OBJECTIVE:

- IDENTIFY SAFETY ISSUES
- PROPOSE CONTROLLING CRITERIA

1-4-6

SPACE STATION SAFETY  
HUMAN FACTORS STATUS


1-47




## HUMAN FACTORS SAFETY STUDY APPROACH

---

1-18



1-49



# HISTORICAL PRECEDENT HUMAN FACTORS ISSUES IMPACT SPACE STATION

1-50

SUBMARINE	SPACE STATION	ANTARCTIC
• CLOSED CYCLE ENVIRONMENT	•	• LONG PERIODS OF ISOLATION
• CROWDED QUARTERS	•	• NO COMMUNICATION
• NO "QUIET" PLACE	•	• RELIANCE ON MEDICAL CAPABILITY
• CLOSE CREW INTERACTION REQUIRED	•	• ESCAPE NOT POSSIBLE IMMEDIATELY
• OPERATIONS & TRAINING PRIME MISSION	•	• HOSTILE ENVIRONMENT CANNOT BE AVOIDED
	•	• SURVIVAL DEPENDS ON OUTSIDE FORCES
	•	• STATION MAINTENANCE PRIME MISSION

## NOTE:

MOST SEVERE ISSUES FROM EACH ENVIRONMENT DIRECTLY APPLY TO SPACE STATION

## SUBMARINE CREW EFFECTIVENESS DURING SUBMERGED MISSIONS (60 OR MORE DAYS)

---

### MAJOR STRESSORS:

- CONFINEMENT
- REVITALIZED AIR
- THREAT OF HYPERBARIC EXPOSURE
- FLATTENING OF CIRCADIAN RHYTHMS
- SLEEP DEPRIVATION

### MINOR STRESSORS:

- PERFORMANCE DECUREMENT
- DEBILITATING MORBIDITY
- DEPRESSED CREW MORALE

### BEHAVIOR PATTERNS:

- MOTIVATION vs PSYCHOLOGICAL
  - WW II - 56 OUT OF 126,160 PATROLS HAD PSYCHIATRIC CASUALTIES
  - IN 1963 - 20 PER 1,000

1-51

SUBMARINE CREW EFFECTIVENESS DURING SUBMERGED MISSIONS  
(60 OR MORE DAYS) (CONT)

---

SUMMARY COMMENTS:

- BIOLOGICAL ADAPTATION IS A COMPLEX FUNCTION OF:
  - NATURE & ENVIRONMENT SEVERITY
  - ADAPTIVE CAPACITY OF PERSONS INVOLVED
- PARAMETERS FOR SCREENING
  - EFFICIENT PERSONNEL SELECTION, SCREENING & TESTING
  - GROUP INTERACTION PROCESSES TEND TO PRODUCE COHESIVE CREWS
  - QUALITY OF LEADERSHIP INTRINSIC TO & ESSENTIAL FOR CREW INTEGRITY

REF: NAVAL SUBMARINE MEDICAL CENTER (95)



## HISTORY OF MILITARY PSYCHOLOGY (NAVAL SUBMARINE MEDICAL RESEARCH LAB)

---

- PSYCHOLOGY - WW II (1942-1945):
  - MAINLY MANDATED BY OPERATIONAL REQUIREMENTS OF DIESEL SUBS
  - RESEARCH IN AREAS OF HEARING, VISION & PERSONNEL SELECTION
    - PRIOR TO ESTABLISHED (NMRL) NAVY MEDICAL RESEARCH LAB
- NUCLEAR-POWERED SUBMARINES:
  - ADDITIONAL PSYCHOLOGICAL PROBLEMS IN CREW SIZE
    - INCREASED DURATION OF SUBMERGED PATROLS (FROM 3 TO 80 DAYS)
    - PSYCHOPATHOLOGICAL EFFECTS OF ISOLATION
    - INCREASED AUDITORY & VISUAL SKILLS
    - ADDED HUMAN FACTORS ASSOCIATED WITH NUCLEAR TECHNOLOGY
  - COLOR-CODED SWITCHES INCREASED COLOR PERCEPTUAL DEFICIENCY TESTS
  - EMPHASIS ON BETTER SCREENING OF PSYCHIATRIC PROBLEMS ASSOCIATED WITH MORALE DETERIORATION, PERFORMANCE DECREMENTS & DEBILITATIVE EFFECTS ON LONG-SUBMERGED MISSIONS
  - DETERMINE OPTIMAL STANDARDS FOR RED LIGHTING
  - POTENTIAL OF HEARING LOSS FROM LONGER EXPOSURE TO SOUND LEVELS
  - FIRST PROBLEMS (72-HOUR SUBMERGE)
    - HEADACHES
    - BLURRED VISION
    - DIZZINESS

HISTORY OF MILITARY PSYCHOLOGY  
(NAVAL SUBMARINE MEDICAL RESEARCH LAB) (CONT)

---

• FIRST PROBLEMS (72-HOUR SUBMERGE) (CONT)

- MALAISE
- PERFORMANCE DECREMENTS

• INCREASED INTERRUPTION OF DIURNAL PERIODICITY

- IN 60- TO 70-DAY RANGE, ALLOWED "PERISCOPE LIBERTY" AT 24-HOUR PERIODS TO  
ALL CREW (REASSURANCE TO REAL WORLD)

- QUESTION OF: OPTIMIZING "FIT" OF MAN TO ENVIRONMENT OR ORGANIZE ENVIRONMENT TO  
BEST "FIT" THE MAN?

1969-1972 (NSMRL):

• CONCERN IN FOUR CONCERNED AREAS

- HUMAN FACTORS IN SUBMARINE ESCAPE
- PSYCHO-PHYSIOLOGICAL EFFECTS OF LONG-DURATION EXPOSURE TO SONAR "BEEPS"  
AT HIGH INTENSITY
- CENTRAL NERVOUS SYSTEM INDICES OF THE NARCOTIZING EFFECTS OF EXPOSURE  
TO COMPRESSED GASES
- DRUG ABUSE IN SUBMARINE SERVICE

## HISTORY OF MILITARY PSYCHOLOGY (NAVAL SUBMARINE MEDICAL RESEARCH LAB) (CONT)

---

1969-1972 (NSMRL) (CONT)

LONG CONFINEMENT ADDED MORE ILLNESSES

- CARDIOVASCULAR
- RESPIRATORY
- NEOPLASTIC
- DUE TO ATMOSPHERIC TOXICANTS
- ABSENCE OF SUNLIGHT
- RESTRICTED SPACE

1-55  
• MOST ALL-PERVASIVE OF QUESTIONS HAD TO DO WITH ACCUMULATIVE PSYCHO-PHYSIOLOGICAL EFFECTS OF EXPOSURE TO CO<sub>2</sub> AT ABOUT 1.5%

• INTRODUCED DURING "OPERATION HIDEOUT" THAT THE CAPACITY OF CO<sub>2</sub> IN BLOOD GAVE CALCIUM DEFICIENCY

• COTTAGE CHEESE ADDED TO DIET & MANY TIMES WAS REQUESTED BY CREW AS AN "INSATIABLE DESIRE"

### SUMMARY & FUTURE PLANNING:

- IDENTIFICATION & CONTROL OF MAJOR TOXICANTS IN ATMOSPHERE
- DEVELOP & VALIDATE AN EFFECTIVE PSYCHOLOGICAL SCREENING PROGRAM
- APPLY CONCEPT OF "SIGNIFICANT ADAPTIVE DECREMENT"
  - LD-50 (LETHAL DOSE IN 50% OF EXPOSED POPULATION) & SAD-50 (STRESSOR CLASS LD-50) - LEVELS OF TOXIC GAS, LENGTH OF DUTY CYCLE, DURATION OF SLEEP DEPRIVATION

REF: U.S. NAVAL SUBMARINE MEDICAL RESEARCH LABORATORY (245)

---

## ANTARCTICA

---

- A FACTOR CONTRIBUTING TO THE IMPORTANCE OF INTERMEMBER ATTRACTION FOR GROUP EFFECTIVENESS IS THE NATURE OF THE SETTING
  - BESIDES SPACE, ANTARCTICA IS ONE OF THE MOST HOSTILE ENVIRONMENTS INHABITED BY MAN
  - DURING THE ISOLATION PERIOD, SURVIVAL DEPENDS ON EACH STATION GROUP'S ABILITY TO HANDLE ANY EMERGENCIES THAT MIGHT ARISE
  - THIS SETTING IS RELATIVELY STRESSFUL &, UNDER CONDITIONS OF STRESS, INDIVIDUALS MAY TEND TO BECOME MORE ANXIOUS, INTERDEPENDENT & AFFILIATIVE
- ANTARCTICA SYMPTOMS FOUND TO BE:
  - DEPRESSION
  - INSOMNIA
  - ANXIETY
  - HOSTILITY
- STRESS, UNCLEAR GOALS, & A COMBINATION OF TASK & SOCIAL-EMOTIONAL ORIENTATIONS HAVE BEEN FOUND TO BE PRESENT IN THE ANTARCTICA SETTING

REFERENCE: NAVAL HEALTH RESEARCH CENTER (256)

## SCREENING PROCEDURES FOR ANTARCTICA

---

- THREE MAJOR TYPES OF SCREENING INFORMATION USED
  - CLINICAL EVALUATION BY PSYCHOLOGISTS & PSYCHIATRISTS
  - BIOGRAPHICAL INFORMATION
  - ATTITUDE & PERSONALITY TESTS
- IN ANTARCTICA RESEARCH, BIOGRAPHICAL INFORMATION HAS BEEN USED FOR THREE PURPOSES:
  1. TO PREDICT INDIVIDUAL ADJUSTMENT OR PERFORMANCE
  2. TO DIFFERENTIATE OCCUPATIONAL SUBGROUPS IN TERMS OF EDUCATIONAL, FAMILIAL, SOCIAL & CULTURAL BACKGROUND CHARACTERISTICS
  3. TO PREDICT GROUP COHESIVENESS OR COMPATIBILITY ON THE BASIS OF DIVERSITY OR SIMILARITY IN BIOGRAPHICAL CHARACTERISTICS
- ATTITUDE QUESTIONNAIRE DESCRIBING MOTIVATION FOR THE ANTARCTIC ASSIGNMENT, CONFIDENCE IN EXPEDITION LEADERSHIP, SATISFACTION WITH DUTY & REACTIONS TO COLD WEATHER, FOOD & CLOTHING WAS ADMINISTERED IN THE SCREENING PROGRAMS
- PSYCHIATRIC EVALUATIONS WERE INTENDED ONLY TO IDENTIFY & DISQUALIFY POTENTIAL PSYCHOTIC OR SERIOUSLY DISTURBED INDIVIDUALS

REF: NAVY MEDICAL NEUROPSYCHIATRIC RESEARCH (255)

## LESSONS LEARNED - SKYLAB

---

- SKYLAB MISSIONS, AS WELL AS APOLLO/LEM, APOLLO/SOYUZ, & APOLLO/SKYLAB PROVIDED AN OPPORTUNITY TO EVALUATE THE DESIGN FEATURES & PROCEDURES THAT ARE REQUIRED TO ALLOW AN ASTRONAUT TO FUNCTION IN SPACE

### FINDINGS:

- NORMAL CREW MOVEMENTS DO NOT CAUSE UNWANTED PHYSICAL DISTURBANCES IN MOST EXPERIMENTS
  - SOME LIMITATIONS STILL MAY BE REQUIRED ON CREW MOVEMENTS DURING CRITICAL PHASES OF THE EXPERIMENT
- SUGGESTS THAT IN FUTURE FACILITIES, PERMANENT HARDWARE SHOULD HAVE NO NOOKS & CRANNIES THAT WOULD PRECLUDE THE RETRIEVAL OF LOOSE ITEMS THROUGH THE "AIR-RETURN" PHENOMENON
- FUTURE DESIGNS SHOULD ALLOW THE CREW ACCESS TO ANY POINT ON THE EXTERIOR OF THE SPACECRAFT FOR PURPOSES OF INSPECTION OR UNSCHEDULED MAINTENANCE & REPAIR
- ARCHITECTURAL LAYOUT OF THE SPACECRAFT'S INTERIOR SHOULD ENSURE THAT NORMAL TRAFFIC ROUTES DO NOT INTERFERE WITH THE ACTIVITIES OF OTHER CREWMEN
- IT WAS FOUND THAT A PRE-SLEEP PERIOD OF AT LEAST ONE HOUR OF MENTALLY NONDEMANDING ACTIVITY WAS REQUIRED
  - THIS ALLOWED THE CREW TO RELAX TO THE POINT WHERE THEY COULD FALL ASLEEP

## LESSONS LEARNED: SKYLAB (CONT)

---

1-59

- THERE WAS AN OCCASIONAL NEED FOR PRIVATE COMMUNICATIONS
  - A SECURE COMMUNICATION LINE SHOULD BE PROVIDED IN FUTURE SYSTEMS TO ELIMINATE POTENTIAL MISQUOTING OR MISUNDERSTANDING
- SLEEP COMPARTMENT VENTILATION SHOULD FLOW IN A HEAD-TO-FOOT PATTERN
- RIGID ADHERENCE TO A TWO-HOUR DAILY EXERCISE ROUTINE HAS BEEN CITED BY SOVIET AEROSPACE MEDICAL PERSONNEL AS THE PRIME FACTOR THAT ALLOWED A SALYUT-6 CREW TO RETURN TO EARTH IN STRONG PHYSICAL CONDITIONS
- THE SHOWER BATH FACILITY USES A PORTABLE SPRAY HEAD, BUT THE METHOD OF WATER REMOVAL AFTER USE WAS NOT CONVENIENT & CONSIDERABLE EFFORT & TIME WERE REQUIRED TO SET UP & TAKE DOWN THE SHOWER
- AN ENCLOSED HAND WASHER THAT WOULD ALLOW HAND INSERTION & ACTUAL "WORKING" DIRECTLY WITH THE WATER WOULD BE DESIRABLE
- CREW SHOULD BE PROVIDED WITH FAMILIAR "UP" & "DOWN" REFERENCES, PERMITTING EASY ORIENTATION, LOCATION RECOGNITION & EQUIPMENT IDENTIFICATION
- ILLUMINATION LEVELS MATCHING THOSE OF NORMAL EARTH WORKING CONDITIONS SHOULD BE PROVIDED

## STS-9 CREW DEBRIEFING

SPR:SLA B

### TWO-SHIFT OPERATIONS


- MULTIPROBLEMS ON FLIGHT DECK/MID DECK SATURATES QUICKLY
- BECOMES CLOCK-WATCHING ROUTINE
- AUTOMATE SOME OF THE MANEUVERS
  - SUGGESTIONS: 12-13 MANEUVERS PER SHIFT NORMAL  
20 MAXIMUM PER SHIFT
- ON TWO-SHIFT (12 & 12), A SECOND FLIGHT DECK CREWMAN NEEDED
- TREADMILL COULD NOT BE USED WHILE OTHER SHIFT ASLEEP
- B. SHAW - PRESENTED THE FOLLOWING COMMENTS:
  - HE THOUGHT IT WAS A LARGE STRAIN ON THE CREW, BUT CAN BE DONE IF REQUIRED
  - CMDR & PILOT TASKS - REQUESTED 3 PEOPLE FOR FLIGHT DECK OPERATIONS
    - THIS WOULD ENABLE THEM TO GO ON 8-HOUR DUTY CYCLES

### SAFETY IMPACT

- CONCERN HERE IS FOR CONTINGENCY OPERATIONS
  - WITH THREE FLIGHT DECK CREWMEN ON 8-HOUR SHIFTS:
    - THE PILOT WOULD NOT BE TIRED
    - WOULD NOT HAVE TO AWAKEN THE OTHER CREWMEN
    - THE OFF-DUTY CREWMAN WHO IS AWAKE CAN PROVIDE ASSISTANCE FOR ANY CONTINGENCY OPERATION



1-61



## MAN-MACHINE INTERFACES - ARCHITECTURE TERRITORIALISM

---

### ISSUE

- CLASSICAL ANTHROPOMETRICS MEASURES SCOPE OF EXPECTED BODY DIMENSIONS TO PROVIDE DESIGNERS WITH DISCRETE REQUIREMENTS FOR INTERFACING EQUIPMENT DESIGN. THE PSYCHOLOGICAL NEED FOR EACH INDIVIDUAL'S INTERACTIVE "SPHERE" IS NOT EASY TO DEFINE. VIOLATION OF ONE'S PERSONAL "SPHERE" GENERATES HOSTILITIES (REAL OR PERCEIVED) BETWEEN INDIVIDUALS. THIS ISSUE TENDS TO RESIST RESOLUTION

### SAFETY IMPACT

- VIOLATION OF CREWMAN'S VOLUME TENDS TO DEVELOP ANTAGONISMS THAT COULD ERUPT INTO EVENTUAL INTERCREW HOSTILITIES

### APPROACH

- DEVISE MENSURATION METHODS THAT CAN DEFINE THE LIMITS OF ONE'S "SPHERE":  
1. PROVIDE DESIGNERS WITH OPTIMUM DIMENSION, & 2. SCREEN OUT POTENTIAL STATION CREW PERSONNEL WHOSE SPHERE SIZE EXCEEDS THAT SELECTED FOR STATION DESIGN

## ANTHROPOMETRICS

---

### ISSUE

- PHYSICAL CAPABILITY TO HANDLE 5<sup>TH</sup> PERCENTILE FEMALE UP THROUGH 95<sup>TH</sup> PERCENTILE MALE IS DESIGN ISSUE
- SOME OF THESE ISSUES WERE NOT READILY RESOLVABLE - WORK STATIONS LARGE ENOUGH ON ONE END OF THE SPECTRUM, YET SMALL ENOUGH FOR A 5<sup>TH</sup> PERCENTILE FEMALE TO REACH ALL CONTROLS & DISPLAYS

### APPROACH

- ENSURE THAT CRITICAL & EMERGENCY CONTROLS & DISPLAYS ARE IN CORE REACH & SIGHT VOLUME

## CRISIS MANAGEMENT

---

### ISSUE

- ANNUNCIATING EVENTS FROM MANY STIMULI ARE COUNTERPRODUCTIVE
  - THE THREE MILE ISLAND INCIDENT MAY HAVE BEEN PRECIPITATED BY MULTIPLE ANNUNCIATIONS THAT CONFUSED THE OPERATORS
- SHUTTLE USES THREE-LEVEL SYSTEM
  - MASTER ALARM - HARDWIRED
  - C&W PANEL - HARDWIRED/REDUNDANCY MGT
  - BLUE LITE ALERT - SYSTEMS MANAGEMENT (SOFTWARE)
- B-1B USES ANNUNCIATION & A CENTRAL INTEGRATED TESTING SUBSYSTEM

1-64

### SAFETY IMPACT

- SENSORY OVERLOAD IS PRECURSOR TO DISASTER

### APPROACH

- CONTROLS & DISPLAYS SHOULD INCLUDE CONTINGENCY LEVEL INDICATORS, EDIT FUNCTIONS & MAINTENANCE ACTION READOUTS
- SCREEN FOR "UNFLAPPABLE" CREW

## EMERGENCY PROCEDURES

---

### ISSUES

- COMPLETE LOSS OF EQUIPMENT FUNCTIONS AND/OR PARTIAL DISABILITY
- REDUNDANT SYSTEMS
- NUMBER/TYPE WARNING SYSTEMS
- FIRE OR OTHER CATASTROPHIC INCIDENT
- LOSS OF PERSONNEL (DEATH) & INJURY
- EGRESS ROUTE & SAFE HAVEN
- ESCAPE & RESCUE

### SAFETY IMPACT

- EMERGENCY PROCEDURE CUEING & IMPLEMENTING OVERLOAD IS RISK SITUATION

### APPROACH

- ASSESS MAJOR ENVIRONMENTAL MANAGEMENT & LIFE SUPPORT SYSTEMS
  - RECOMMEND REDUNDANCY WITHOUT "OVERKILL"
  - IDENTIFY WARNING SYSTEMS - VISUAL & AUDIBLE
  - DUAL EGRESS & SAFE HAVEN FOR EACH MODULE/CAPSULE
  - PROPER PROCEDURES FOR DOCKING, EVA & INTERVEHICULAR ACTIVITIES
  - ADEQUATE TRAINING OF PERSONNEL
  - PORTABLE EMERGENCY EQUIPMENT
-

## CLEANING/DISINFECTING

---

### ISSUES:

- IDENTIFY PRIMARY & SECONDARY AREAS OF CLEANING
- GROUP BY PRIORITY, HEALTH & HYGIENE, GENERAL HOUSEKEEPING, HARDWARE, CLEAN ROOMS, ETC.
- MATERIALS & METHODS TO BE UTILIZED WITHOUT CREATING ADDITIONAL PROBLEMS
- ESTABLISH MAINTENANCE ITEMS & REGULARLY SCHEDULED ACTIVITIES
- WILL ALL CREW MEMBERS ROTATE TASKS TO PREVENT BOREDOM & CLASS DISTINCTION?

### SAFETY IMPACT:

- PERSONNEL HEALTH EFFECTED BY REVITALIZED AIR SYSTEMS & CONTROL OF TOXICITY
- MORALE FACTORS DEPLETED BY ASSIGNMENTS TO SPECIFIED INDIVIDUALS
- CERTAIN LAB EXPERIMENTS MUST BE CONTROLLED TO PROTECT OTHER CREW MEMBERS
- PHYSICAL DEGRADATION DUE TO SLEEP DEPRIVATION BIOLOGICAL PROCESSES, WHICH ARE A RESULT OF ESTABLISHED ENVIRONMENTAL CONTROL METHODS
- GOOD DETERGENTS IMPACT ECLSS SYSTEM DESIGN (LiOH)

### APPROACH:

- DETERMINE CLEANLINESS/DISINFECTANT LEVELS FOR ISOLATED & CONFINED LIVING/WORKING AREAS
- INVESTIGATE HIGH-TECH FILTRATION SYSTEMS TO CONTROL REVITALIZED AIR SYSTEMS
- MANDATE NO INDIVIDUAL "GRUNT" WORK, BUT SHARED CLEANING/MAINTENANCE ACTIVITIES
- INVESTIGATE ADDITIONS TO DIET AND/OR VITAMIN/MINERAL INTAKE TO "OFFSET" LOSSES IN REVITALIZED AIR

## MISSION SCHEDULING

---

### ISSUE:

- SCHEDULING CRITERIA MAY BE FORCED BY ECONOMIC (NUMBER OF SHUTTLE FLIGHTS), POLITICAL (INTERNATIONAL PARTICIPANTS), COSMIC (WINDOWS FOR EXPERIMENTS), & PERSONNEL PHYSIOLOGICAL/PSYCHOLOGICAL/ *500-2000 H L* ENDURANCE

### SAFETY IMPACT:

- CREW FATIGUE, ILLNESS, IRRITABILITY & TIME PRESSURES DRIVE PEOPLE TO MAKE ERRORS OR FUNCTION OUTSIDE OF EXPECTED PARAMETERS


### APPROACH:

- SET UP INTEGRATED AIR-GROUND TEAMING
- CUT DOWN TOTAL PER-PERSON TIME ON ORBIT BUT APPLY EFFORT TO STATION MISSIONS
- MAKE RATIONAL ASSESSMENTS OF MAXIMUM ALLOWABLE TIME IN ORBIT RECOMMENDED PER YEAR (RADIATION, PHYSICAL DEBILITATION, PSYCHOLOGICAL ABERRATION)

1-67

## WORK GROUP/SHIFT DYNAMICS

- USE "AGGREGATE" TEAM CONCEPT.




- ONE THIRD OF TIME SPENT IN EACH MISSION SEGMENT

ORIGINAL PAGE IS  
OF POOR QUALITY



# SPACE HABITAT SCHEDULING - PERSONNEL

THREE CREWS WOULD HANDLE ALL ASPECTS OF SPACE HABITAT



1-69

## CREW CHANGEOVER

---

### ISSUE:

- SPACE STATION IS SIZED FOR ONE CREW (8-16 PEOPLE). WHEN CREWS CHANGE OVER, WHERE WILL THE SECOND CREW BE & HOW LONG ON STATION?

### SAFETY IMPACT:

- CONTINGENCY PLANNING MAY NOT BE ABLE TO HANDLE TWO CREWS

### APPROACH:

- BEGIN CHANGEOVER ON GROUND
- MAINTAIN ORBITER AT STATION DURING CHANGEOVER
- PREPARE DETAIL PLAN FOR STATION CONTINGENCY OPERATIONS DURING CHANGEOVER

1-70

## CROSS-TRAINING

---

### ISSUE:

- EIGHT-MAN CREW TO HANDLE ALL SPACE STATION MAINTENANCE, OPERATIONS, USER SET-UP, MAINTENANCE & OPERATIONS REQUIRES BROAD, OVERLAPPING CAPABILITIES AMONG CREW

*Required 5 crew members for EVA - 2/EVA; 1 pilot; 1/Rem; 1/Photo*

### SAFETY IMPACT:

- UNIQUE CRITICAL SKILLS ARE LIABILITIES IF CREWMEMBER BECOMES INCAPACITATED

### APPROACH:

- SCREEN TOWARD GENERALISTS vs SPECIALISTS
- AUTOMATE, USING REDUNDANCY & SIMPLE MAINTENANCE REQUIREMENTS EQUIPMENT, EXPERIMENTS OR PRODUCTION LINES REQUIRING UNIQUE SKILLS

NOTE: APPROXIMATELY 50% OF SKYLAB CREW TIME WAS SPENT IN STATION UPKEEP, HOUSEKEEPING & REPAIR.

## ACOUSTICAL IMPACTS

---

### ISSUES:

- NOISE LEVELS FROM SPACECRAFT SYSTEMS/COMPONENTS
- PERSONNEL PHYSICAL & MENTAL EFFECTS
- BACKGROUND NOISE
- UHF NOISE
- CONTROLS, REDUCTION AND/OR ELIMINATION


### SAFETY IMPACTS:

- CREW FATIGUE, IRRITABILITY & INABILITY TO COMMUNICATE ARE RISK GENERATORS


### APPROACH:

- MEASURE & ASSESS ALL NOISE SOURCES FOR dB LEVEL & FREQUENCY
- INCLUDE INDIVIDUAL & ACCUMULATED NOISE
- INVESTIGATE CRITICAL AREAS OF SLEEP STATIONS & WORK AREA COMMUNICATION
- UHF MAY REQUIRE DETERMINATION FOR PHYSICAL & PSYCHOLOGICAL EFFECTS
- SLEEP AREAS SHOULD NOT BE COMPLETELY SILENT
- ADEQUATE COMMUNICATIONS MAY REQUIRE LIGHTWEIGHT HEADSETS
- SCREEN CANDIDATES FOR LOW NOISE SENSITIVITY

# APOLLO ACOUSTICS



# SHUTTLE ACOUSTICS




## ON-ORBIT ACOUSTIC NOISE

---

- ALL ORBITAL VEHICLES HAVE EXPERIENCED SOME FORM OF ACOUSTIC NOISE PROBLEMS
- PREVIOUS VEHICLE NOISE PROBLEMS HAVE BEEN COMPLEX & USUALLY RESULTED IN "TRADE-OFFS" & COMPROMISES INVOLVING:
  - SPECIFICATION REQUIREMENTS RELAXATION
  - ADDED DEVELOPMENT COSTS
  - WEIGHT PENALTIES
  - SCHEDULE IMPACTS
- CONCLUSIONS/RECOMMENDATIONS
  - OPERATIONS SHOULD CONSIDER THE LIMITS NOTED IN CHARTS
  - ATTAIN A REASONABLY QUIET SPACE STATION
  - IMPOSE NECESSARY DESIGN REQUIREMENTS & SPECIFICATIONS DURING INITIAL PHASE OF PROGRAM FOR BOTH PRIMARY & SUBCONTRACTORS
  - INVESTIGATE & UTILIZE THE LATEST TECHNOLOGY IN ATTENUATION FOR ACOUSTIC DESIGN & MATERIALS


1-75

1-76





INITIAL HUMAN FACTORS ASSESSMENTS  
SAFETY CRITERIA DEVELOPMENT



\*HOW IS THIS INCORPORATED INTO SPACE STATION DEVELOPMENT

# CREW SAFETY CRITERIA SUMMARY

---

## CATEGORIES RELATING TO:

• DAMAGE TOLERANCE	12
• CREW PROTECTION	27
• STATION INTEGRITY	11
• CONTINGENCY CONTROL	8

## NEW CRITERIA

• STATION INTEGRITY	4
• SELECTION/INDOCTRINATION (NEW HUMAN FACTORS CATEGORY)	5

---

TOTAL	67
-------	----

---

1-78

## NEW CRITERIA

---

### STATION INTEGRITY

- C-13 PROVISIONS SHALL BE MADE FOR INFLIGHT SERVICING, ADJUSTING, CLEANING, REMOVAL & REPLACEMENT OF OFFENDING COMPONENTS, & TESTING & REPAIRING OF ALL CRITICAL SUBSYSTEMS
- C-14 WEAR ITEMS SHOULD BE LIFE-CYCLE TESTED IN A REALISTIC ENVIRONMENT
- C-15 ALL PERSONNEL ITEMS SHOULD BE SCREENED FOR FLAMMABILITY & TOXICITY
- C-12 SPACE STATION MODULES SHOULD BE TUMBLED TO RID THEM OF INTERNAL DEBRIS & CONTAMINANTS IMMEDIATELY PRIOR TO PREPARATION FOR LAUNCH

1-79


NEW CATEGORY OF CRITERIA  
SELECTION/INDOCTRINATION

---

- E-1 CREW SELECTION SHOULD BE BASED ON SELECTEES' CROSS-TRAINABILITY IN FIELDS OTHER THAN SPECIALTY
- E-2 ORBITAL CREW SHOULD BE AN INTEGRAL PART OF THE AIR/GROUND SYSTEM ACTIVE INTERFACE WITH ON-ORBIT CREWS
- E-3 STATION CREWS & TEAMING SHOULD ALLOW EQUAL THIRDS OF SCHEDULE FOR ON-ORBIT, GROUND INTERFACE OPERATIONS & RECYCLE OPERATIONS (POST-ORBIT REHABILITATION, LEAVE, ADDITIONAL TRAINING, PUBLIC RELATIONS, ETC.)
- E-4 ASSURANCE SHOULD BE PROVIDED THAT EACH MISSION SEGMENT CREW IS FAMILIAR WITH: 1. STATION OPERATIONS & MAINTENANCE AS CONCERNS CRITICAL SUBSYSTEMS, & 2. PROCEDURES NECESSARY TO RENDER "SAFE" ALL EXPERIMENTS AND/OR USER PROCESSES
- E-5 SCREENING CRITERIA SHOULD INCLUDE ASSESSMENT OF ATTITUDES, PHYSICAL NEEDS, PSYCHOLOGICAL NEEDS, PERSONALITY TRAITS, ABILITY TO FUNCTION UNDER STRESS, ABILITY TO ACCEPT DIRECTION, & TBD

1-80

1-81



## CONCLUSION - HUMAN FACTORS

---

- 48 AREAS OF IMPACT IDENTIFIED
- SAFETY CRITERIA THAT ARE NOT DESIGN CRITERIA MAY BE DIFFICULT TO INCORPORATE IN SPACE STATION PROGRAM
  - TERRITORIAL ISSUES
  - HUMAN FACTORS ISSUES THAT IMPACT MISSION OPERATIONS
  - CREW SELECTION AND SUPPORT
  - CREW TRAINING
- SPACE STATION HUMAN FACTORS AGGREGATES THE MOST SEVERE PERSONNEL STRESSORS OF ISOLATED, CONFINED ENVIRONMENTS, INCLUDING CURRENT SPACE ACTIVITIES
- EIGHT AREAS WILL BE REVIEWED IN THIS STUDY, BASED ON CONFIGURATION IMPACT IMPLICATIONS

1-82

TUESDAY

		Page
INTERNAL CONTAMINATION	J. Queller W. Hoffler	2-1 to 2-3
Statement of Contamination Problem	W. Hoffler	2-4 to 2-13
Shuttle Experiences:		
Internal Contamination Issues	L. Rockoff	2-14 to 2-29
Materials and Processes Control for Space Application	G. A. Blackburn	2-30 to 2-39
Ventilation Flow--Submerged	D. Hutchinson	2-40 to 2-69
Contamination Control Experiences:		
Toxicity and the Smoke Problem	H. Kaplan	2-70
Industrial Atmospheric Monitoring: Ambient Air Contamination-- Characterization and Detection Techniques	C. Nulton	2-71 to 2-79
Atmospheric Contamination:		
Extended Mission Life Support Systems	P. Quattrone	2-80 to 2-98
Space Shuttle Air Revitalization System	P. Quattrone	2-99 to 2-128
Internal Contamination in the Space Station	C. Poythress	2-129 to 2-153
Space Station Trace Contaminant Control	T. Olcott	2-154 to 2-169

## INTERNAL CONTAMINATION SESSION

by Judith Queller

### Introduction

Two days of the Human Productivity meeting were devoted to presentations on and discussions of internal contamination. Internal contamination had been identified by the Program Review Committee as a potential problem requiring careful attention. It was therefore given special attention so that the various options could be discerned. On the one hand, strict control of onboard materials would simplify the problem but would represent a significant burden to the customer, both in terms of time and money. On the other hand, a more liberal policy on materials would directly benefit the customer but would necessitate better contaminant detection and removal inside the Space Station. The various issues and trades therefore needed to be defined and explored. Presentations during the two days of the Internal Contamination meeting covered an overview of internal contamination issues and concerns, past experiences including Shuttle and nuclear submarines, approaches to contamination detection and control, and discussion of the more promising approaches we might pursue.

Space Station presents us with unique conditions which permit us to rely on analogs and experiences only in a limited fashion. This is because of three sets of special circumstances. First, crew members will be subject to



continuous 24-hour exposures. Therefore, 8-hour industrial threshold limit values may not be applicable. Second, the system will not be periodically refurbished (i.e. purged, ground processed). Third, we will have hazardous operations and materials which we have not previously encountered. These unique conditions require specific actions on our part. Therefore, there are basically five major areas in which we have task requirements.

1. Potential contaminants need to be identified i.e. both the sources and types of contaminants.
2. The scope and magnitude of contaminant effects need to be determined i.e. toxicological effects, microbacteriological effects and impurities.
3. Mathematical models for predictive methods need to be developed.
4. State-of-the-art and advanced technologies for monitoring contaminants and for methods of decontamination need to be identified.
5. Automated monitoring and control systems need to be designed.

Fulfilling these requirements helps us to formulate solutions for the potential internal contamination problems which face us. These solutions include the prevention of contamination, the monitoring of contaminants and the active control of contaminants.

The trace contaminant technology base is relatively

firm. Mass spectrometry can be used for compound identification and gas chromatography for quantification. The hardware and design tools are available and the previous design philosophy of a conservative load model which is refined as actual data become available, is still applicable. This is true for particulate, atmospheric and bacteriological contamination.



Kennedy  
Space  
Center

SPACE STATION  
HUMAN PRODUCTIVITY WORKING GROUP  
CONTAMINATION

BIOMEDICAL OFFICE  
FEBRUARY 28, 1984

**DEFINITION: CONTAMINANT → CONTAMINATE**

REFERS TO THAT WHICH ON COMING INTO CONTACT WITH SOMETHING WILL MAKE IT IMPURE, UNCLEAN, OR UNFIT FOR USE; TO POLLUTE, SOIL, DECAY, INFECT, OR CORRUPT; TO COMPROMISE OR ADVERSELY AFFECT BEING AND FUNCTION WITH UNDESIRABLE ELEMENTS.

THIS IMPLIES THAT AN ORIGINAL CONDITION PRECEDES CONTAMINATION -- APPLICABLE TO INTENDED SPACE STATION DESIGN.

**BASIC COMPONENTS IN CONTAMINATION:**

**A. THAT WHICH IS CONTAMINATED**

- HUMAN CREW - PREEMINENTLY
- OTHER LIFE FORMS
- EQUIPMENT AND SYSTEMS ONBOARD
- PROCESSES AND ACTIVITIES

**B. CONTAMINANTS (FACTORS)**

- TYPES AND SOURCES
- EFFECTS AND CONSEQUENCES
- ASSESSMENT AND QUANTIFICATION
- CONTROL AND DECONTAMINATION

**N.B.:** AS IN THE HUMAN CASE, MANY ELEMENTS CAN BE EITHER OBJECT OR SOURCE OF CONTAMINATION!

N85-29542

ORIGINAL PAGE  
OF POOR QUALITY

2-4



Kennedy  
Space  
Center

SPACE STATION  
HUMAN PRODUCTIVITY WORKING GROUP  
**CONTAMINATION**

BIOMEDICAL OFFICE  
FEBRUARY 28, 1984

THE PROBLEM

THE "NEW WORLD" REVISITED

- GROWING POPULATION IN ORIGINALLY PRISTINE ENVIRONMENT
- LIMITED BASIC RESOURCES
- INCREASING AMOUNTS OF WASTE/DEBRIS INTO A FINITE CONTAINMENT
- BYPRODUCTS AND EFFLUENTS OF INDUSTRIALIZATION
- MICROBIAL THEORY REASONABLY WELL UNDERSTOOD AND OPERATIVE
- EXOTIC AND UNEXPECTED INPUTS (E.G. NUCLEAR WASTES, BIZARRE REACTIONS)
- INCOMPATIBILITIES OF VARIED INTEREST GROUPS
- MENTAL AND PSYCHIC OVERLOAD

**N.B.:** PROGRESS OF THESE CONTAMINATING EVENTS IN A MICROCOSM WILL FOLLOW A GREATLY COMPRESSED TIME SCALE WITH **LIMITED BUFFER CAPACITY**



Kennedy  
Space  
Center

SPACE STATION  
HUMAN PRODUCTIVITY WORKING GROUP  
CONTAMINATION

BIOMEDICAL OFFICE  
FEBRUARY 28, 1984

PURPOSE - TASKS

- RECOGNIZE AND EVALUATE THE PROBLEM(S) -  
DESIGN SPACE STATION ACCORDINGLY
  - IDENTIFY POTENTIAL CONTAMINANTS - SOURCES AND TYPES
  - DETERMINE SCOPE AND MAGNITUDE OF CONTAMINATION EFFECTS:  
TOXICOLOGICAL, MICROBIOLOGICAL, IMPURITIES
  - DEVELOP MATHEMATICAL MODELS FOR PREDICTIVE METHODS
  - IDENTIFY STATE-OF-THE-ART AND ADVANCED TECHNOLOGIES  
NEEDED FOR MONITORING CONTAMINANTS AND FOR DECONTAMINATION
  - DESIGN AUTOMATED MONITORING AND CONTROL SYSTEMS - LINKED  
TO TOX DATABASE AND MATH MODELS
  - DETERMINE OPTIMAL MEANS FOR MANAGING CONTAMINATION AND  
DESIGN AS INDICATED - A GLOBAL ISSUE
  - ESTABLISH ESSENTIAL BACK-UP PROVISIONS AS AUXILIARY MEDICAL  
DATABASE TO ASSIST RAPID DELIVERY OF APPROPRIATE MEDICAL CARE.



Kennedy  
Space  
Center

SPACE STATION  
HUMAN PRODUCTIVITY WORKING GROUP  
CONTAMINATION

BIOMEDICAL OFFICE  
FEBRUARY 28, 1984

SOURCES AND TYPES OF CONTAMINANTS:

- FUELS AND MECHANICAL SYSTEMS
- PAYLOADS/EXPERIMENTS
- HUMAN CREWMEMBERS
- NON-HUMAN BIOLOGICALS
- MATERIALS
- ENERGIES
  
- CHEMICALS
- GASES
- PARTICULATES
- AEROSOLS
- MICROBIOLOGICALS
- ELECTROMAGNETIC RADIATION
- IONIZING RADIATION
- THERMAL ENERGY
- MECHANICAL ENERGY

2-7



Kennedy  
Space  
Center

SPACE STATION  
HUMAN PRODUCTIVITY WORKING GROUP  
CONTAMINATION

BIOMEDICAL OFFICE

FEBRUARY 28, 1984

HUMAN TOXICOLOGIC DATA BASE

- 0 MAJORITY OF CONCERNS FOR HUMAN CREWS
- 0 UNIQUE SPACE STATION CONDITIONS
  - CONTINUOUS 24-HOUR EXPOSURE (8-HOUR TLV'S NOT APPLICABLE)
  - SYSTEM NOT PERIODICALLY REFURBISHED (PURGED, GROUND PROCESSED)
  - HAZARDOUS OPERATIONS/MATERIALS NOT PREVIOUSLY ENCOUNTERED
- 0 LIKELIEST PROBLEMS, ORGAN SYSTEMS AFFECTED, CONSEQUENCES
- 0 INTERRELATION WITH MEDICAL CARE SYSTEM

MICROBIOLOGICAL POTENTIAL PATHOGENS

SYSTEMS MALFUNCTION

- 0 LIFE SUPPORT SYSTEM (ANOMALOUS, OVERLOAD)
- 0 OPTICAL SURFACES, ELECTRONICS
- 0 MATERIALS PROCESSING
- 0 HOUSEKEEPING

2-8



Kennedy  
Space  
Center

SPACE STATION  
HUMAN PRODUCTIVITY WORKING GROUP  
CONTAMINATION

BIOMEDICAL OFFICE  
FEBRUARY 28, 1984

QUANTIFICATION OF CONTAMINANTS

- KNOWN
  - HUMAN OUTPUTS
    - RESPIRATORY
    - SKIN
    - URINARY
    - GASTROINTESTINAL
  - OTHER LIVING COMPONENTS
  - FOOD PRODUCTS, PROCESSING BYPRODUCTS
  - ONBOARD MATERIALS
  - MICROBIOLOGICALS
- LESS WELL DOCUMENTED
  - MATERIALS PROCESSING
  - MICROBIOLOGICALS - MUTANTS, VARIANTS
  - EXOTIC PHYSICO-CHEMICAL REACTIONS
  - ONBOARD INCIDENTS (I.E., SPILL, FIRE)
- PREDICTIVE MODELLING
  - REQUIRES CONTINUOUSLY UPDATED DATABASE

2-9





Kennedy  
Space  
Center

SPACE STATION  
HUMAN PRODUCTIVITY WORKING GROUP  
CONTAMINATION

BIOMEDICAL OFFICE

FEBRUARY 28, 1984

SOLUTIONS:

- PREVENTION
- MONITORING
  - TECHNOLOGIES, SENSORS, ANALYZERS; DISTRIBUTION, FREQUENCY
  - DATA INTERPRETATION, DECISION
  - RESPONSE ACTUATORS
- ACTION/CONTROL
  - ALARMS
  - REDUCTION, ELIMINATION
  - DECREASE INPUT, INCREASE FILTRATION/SCRUBBING, PURGE
  - ISOLATION, SHIELDING, PROTECTIVE DEVICES
  - RETREAT (SAFE HAVEN)
  - MEDICAL TREATMENT (OR SYSTEMS' EQUIVALENT)
- AUTOMATION
  - MINIMIZE HUMAN REQUIREMENTS FOR CONTAMINATION CONTROL,  
DECONTAMINATION

2-10



Kennedy  
Space  
Center

SPACE STATION  
HUMAN PRODUCTIVITY WORKING GROUP  
CONTAMINATION

BIOMEDICAL OFFICE

FEBRUARY 28, 1984

HISTORICAL LESSONS

- ALL SPACE CRAFT EXPERIENCE TO DATE
  - EMPHASIS ON LONGER DURATION
  - ATTENTION TO MORE SERIOUS/POTENTIAL PROBLEMS (E.G., HYPERGOLS, WASTE MANAGEMENT)
- SUBMARINES
- MINING
- METALLURGICAL INDUSTRIES
- CLEAN ROOMS
- MEDICAL ISOLATION
- MICROBIOLOGICAL RESEARCH AND MANUFACTURING
- EXTREME ENVIRONMENTS (E.G., BAROMETRIC PRESSURE, TEMPERATURE, HUMIDITY)

2-11



Kennedy  
Space  
Center

SPACE STATION  
HUMAN PRODUCTIVITY WORKING GROUP  
CONTAMINATION

BIOMEDICAL OFFICE  
FEBRUARY 28, 1984

TECHNOLOGIES REQUIRED:

INTEGRAL TO ALL OF SPACE STATION; COMPELLING FOR ECLSS AND LOGISTICS MODULE

- DETERMINE BEST MEANS (OR OPTIONS) FOR HANDLING EACH CASE
- IDENTIFY STATE-OF-THE-ART AND NEW TECHNOLOGIES TO IMPLEMENT
- GROUND TEST/MATH MODEL TO OPTIMIZE CONTROL
- DESIGN CONTROL AND MONITORING SYSTEMS TO MAXIMIZE AUTOMATION
- FLIGHT TEST COMPONENTS/SUBSYSTEMS WHERE FEASIBLE
- DETERMINE DEGREE OF SYSTEM CENTRALIZATION VERSUS MODULAR INDEPENDENCE
- ASSURE CAPABILITY TO UPGRADE SPACE STATION SYSTEMS

N.B.: SIZE, MASS, SPACE, COST WILL NECESSARILY CONSTRAIN TECHNOLOGIES



Kennedy  
Space  
Center

SPACE STATION  
HUMAN PRODUCTIVITY WORKING GROUP  
**CONTAMINATION**

BIOMEDICAL OFFICE  
FEBRUARY 28, 1984

MAJOR AGENCY DECISIONS FOR THE **CONTAMINATION** ISSUE

- MISSIONS AND OBJECTIVES OF SPACE STATION
- CENTRAL VERSUS DISTRIBUTIVE/MODULAR SYSTEM
- ESTABLISHMENT OF APPLICABLE TOXIC EXPOSURE TOLERANCES
- LEVEL OF AUTOMATION VERSUS HUMAN RESPONSIBILITY
- ELEMENTS AND DEGREE OF SYSTEMS CLOSURE
- WHEN TO FREEZE TECHNOLOGIES

2-13

N85-29543

---

INTERNAL CONTAMINATION ISSUES

2-14

L. ROCKOFF  
2-28-84  
IL #294-400-84-078

---

## CONTAMINATION

---

### EXTERNAL ISSUES

- WINDOWS
- MATERIAL DEGRADATION DUE TO MOLECULAR OXYGEN EXPOSURE
- HYPERGOLICS AND OTHER REACTANTS

### INTERNAL ISSUES

- PARTICULATE
- ATMOSPHERIC
- BIOLOGICAL (BACTERIOLOGICAL)

✓ DISCUSSED IN THIS SESSION

---

---

2-16

## INTERNAL ATMOSPHERIC CONTAMINATION

---

## Contaminants Found in Shuttle Orbiter Atmospheric Samples

### Compound Identity

## STS MISSION NUMBER

Acetic Acid, n-Butyl Ester  
Acetic Acid, 2-Ethoxyethyl ester  
Acetic Acid, Ethyl Ester  
C<sub>4</sub> Alkene  
Benzaldehyde  
Benzene  
Bromotrifluoromethane  
1-Butanal  
1-Butanol  
2-Butanone  
Butene  
n-Butylbenzene  
Carbon Dioxide  
Carbon Disulfide  
Carbon Monoxide  
Cyclohexane  
Decane  
Dichlorodifluoromethane  
1,1-Dichloroethene  
Dichloromethane  
1,2-Dimethylbenzene  
1,3-Dimethylbenzene  
1,4-Dimethylbenzene  
1,1-Dimethylethanol  
Ethanal  
Ethanol  
Ethylbenzene  
2-Ethylhexanal  
Ethyl 2-Propenyl Ether  
1-Heptanal  
Heptane  
2-Heptanone  
3-Heptanone  
Hexamethylcyclopentane  
Hexamethylcyclotrisiloxane  
1-Hexanal  
Hexane

[illegible]

ORIGINAL PAGE IS  
OF POOR QUALITY





C<sub>8</sub>-Alkane (1)  
 C<sub>9</sub>-Alkane (5)  
 C<sub>10</sub>-Alkane (6)  
 C<sub>11</sub>-Alkane (5)  
 C<sub>12</sub>-Alkane (4)

C<sub>8</sub>-Olefinic Hydrocarbon (1)  
 C<sub>9</sub>-Olefinic Hydrocarbon (2)  
 Silocone MN = 236  
 Siloxane (3)  
 Octamethylcyclotetrasiloxane

C<sub>3</sub>-Substituted Benzene (11)  
 C<sub>4</sub>-Substituted Benzene (6)

Compound Identity

STS MISSION NUMBER

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
			X		X									
X		X												
X		X												
X		X												
	X													
	X													
				X				X						
					X			X						
X														
X														


## BACKGROUND

---

### PRESENT SYSTEM:

- o WHOLE GAS SAMPLES
  - o THREE TIMES DURING MISSION THE CYLINDER VALVE IS OPENED TO PERMIT THE INFLOW OF CABIN ATMOSPHERE INTO THE EVACUATED CYLINDER.
  - o THE SAMPLE IS TRAPPED UPON CLOSING THE CYLINDER VALVE.
  - o TOXICOLOGY LABORATORY PERFORMS ANALYSES AFTER THE FLIGHT.
- o GAS CHROMATOGRAPHY
  - o MASS SPECTROMETRY FOR COMPOUND IDENTIFICATION
  - o GAS CHROMATOGRAPHY FOR QUANTIFICATION.

2-21



ORIGINAL PAGE IS  
OF POOR QUALITY

---

**STS-2**

- o **SYSTEMIC POISONS EXCEEDED LIMIT BY 1.22 TIMES (MAJOR CONSTITUENT TOLUENE)**
- o **FOUR SAMPLE BOTTLE, TENAX ABSORBER, AND CHARCOAL SAMPLE ANALYSES USED FOR EVALUATION.**
- o **SOURCE OF TOLUENE INTRODUCED DURING GROUND OPS.**

PHYSIOLOGICAL EFFECTS GROUP	SPACECRAFT MAXIMUM ALLOWABLE CONCENTRATION (SMAC) PERCENT
IRRITANTS CNS DEPRESSANTS SYSTEMIC POISONS ASPHYXIANTS	11.3% 22.2% 122.3% * 6.6%

---

STS-3

- o ANALYSIS OF 4 BOTTLES AND CHARCOAL SAMPLES SHOWED METHANE AND HALON 1301.
- o FIRE SUPPRESSION HALON BOTTLE RELEASED BEFORE ENTRY PER FLIGHT RULE  
(SMOKE DETECTOR FAILURE).
- o LEVEL WOULD EXCEED SMAC - FLIGHT RULE CHANGE TO USE OXYGEN MASK  
EACH TIME BOTTLE FIRED.

---

**STS-4**

- o ONLY ONE BOTTLE - INADEQUATE FOR ASSESSMENT
  - o FIRST USE OF ATCO (AMBIENT TEMP CATALYTIC OXIDIZER)
  - o 100% CHARCOAL USED IN A CANISTER FOR SCRUBBING
  - o FREON 12 INTRODUCED WITH FIRST USE OF VPC (VAPOR PHASE COMPRESSION) FREEZER.
  - o BALLOONING OF INSULATION BLANKET OCCURRED.
  - o ODOR NOTED WHEN AIRLOCK OPENED. (UNKNOWN)
  - o ANALYSIS OF THE ONE SAMPLE BOTTLE SHOWED: FREON 12, HALON 1301, FREON 113 (TF), METHANE.
-

---

STS-5

- o INCREASE IN CREW SIZE TO 4
- o ODOR AGAIN NOTED WHEN AIRLOCK OPENED (UNKNOWN)
- o ODOR NOTICED NEAR ONE OF THE LOCKERS (UNKNOWN)



---

STS-6

- o CREW SIZE OF 4
  - o CREW REPORTED THAT THEY WERE SUBJECTED TO HEADACHES DURING THE FLIGHT
  - o AIR SAMPLES #3 AND #4 WERE COLLECTED AT THE SAME TIME
  - o CREW REPORTED AN ODOR NEAR THE MLR
    - o CREW TURNED OFF MLR EXPERIMENT
    - o POST LANDING, THE ODOR WAS TRACED TO A BURNT WIRE INSULATION FROM A SHORT IN A WIRE HARNESS IN THE HUMIDITY SEPARATOR.
  - o DUE TO BURNT WIRE, CHARCOAL "SCRUBBERS" ARE BEING ANALYZED FOR POSSIBLE DECOMPOSITION PRODUCTS.
-

---

STS-7

- o CABIN PRESSURE CHANGE FROM 14.7 TO 10.2 PSI AND OXYGEN CONTENT INCREASED FROM 20.9% TO 26 TO 28%. MATERIALS WERE NOT CERTIFIED AT THE HIGHER O2 CONTENT.
- o INCREASE IN CREW SIZE TO 5
- o NO SAMPLES TAKEN WHEN CABIN WAS AT 10.2 PSI.

---

CONCERNS:

- o INSUFFICIENT SAMPLE BOTTLES TO PROVIDE THE NECESSARY DATA TO MAKE AN ADEQUATE ASSESSMENT OF THE CABIN ATMOSPHERE THROUGHOUT THE MISSION.
  - o USE OF SAMPLE BOTTLES FOR QUALIFICATION/VERIFICATION FOR NEW EQUIPMENT OR CHANGES IN OPERATING CONDITIONS.
  - o IF THE CREW CAPABILITY WERE TO BE DEGRADED (PHYSICALLY OR MENTALLY DURING THE FLIGHT) ADEQUATE POST FLIGHT DATA WOULD NOT BE AVAILABLE TO MAKE AN ASSESSMENT OF THE CAUSE AND INITIATION OF CORRECTIVE ACTION WOULD BE DIFFICULT.
  - o NO CONTROL ON CARRY-ON ITEMS. FIRST EXPOSURE TO CABIN ENVIRONMENT IS DURING FLIGHT WITHOUT PRIOR EVALUATION OR REAL TIME MONITORING.
  - o HALON 1301 LEAK/DISCHARGE COULD EXCEED SMAC LEVEL UNRECOGNIZED.
  - o SYNERGISTIC EFFECTS OF CABIN CONTENTS IS UNKNOWN.
  - o ABUSE OF L10H CANNISTERS MAY CREATE A SINGLE POINT FAILURE, WHICH COULD RELEASE CORROSIVE/TOXIC MATERIAL.
  - o UNDER CURRENT SITUATIONS, MISSIONS MUST BE ABORTED IF THE DORNING OF MASKS IS REQUIRED.
-

---

CONCERNS: CONT'D

- o CABIN ATMOSPHERE CANNOT READILY BE ALTERED. CANNOT VENT TO VACUUM.
- o SPACELAB DATA - TBD




N85-29544

MATERIALS AND PROCESSES CONTROL  
FOR  
SPACE APPLICATIONS

2-30

G. A. BLACKBURN



- o CONTAMINATION CONTROL IS AN INTEGRAL PART OF GOOD MATERIALS AND PROCESSES CONTROL.
- o IT IS ESSENTIAL THAT MATERIALS AND PROCESSES ENGINEERING BE CONSIDERED A "TOTAL CONTROL" ELEMENT OF ANY MANNED AEROSPACE PROGRAM.
- o FUTURE AEROSPACE PROGRAMS WILL REQUIRE A "SYSTEMS" PERSPECTIVE.




## M&P CONTROL FOR SPACE APPLICATIONS

---

MATERIALS AND PROCESS CONTROL APPLIES TO THE PROPER SELECTION, USAGE EVALUATION, DOCUMENTATION AND THE TRACKING OF MATERIALS AND PROCESSES TO AVOID OR REDUCE THE RISKS OF SYSTEM PERFORMANCE FAILURES FROM FLAMMABILITY, TOXICITY, THERMAL/VACUUM STABILITY, CORROSION, FLUID INCOMPATIBILITIES, FATIGUE, OXYGEN IMPACT SENSITIVITIES, CONTAMINATION CONTROL, ETC.

2-32





## M&P CONTROL FOR SPACE APPLICATIONS

---

A TOTAL MATERIAL AND PROCESS CONTROL SYSTEM CONSISTS OF TWO ELEMENTS:


1. AN ENGINEERING REVIEW/EVALUATION SYSTEM
  - PROGRAM REQUIREMENTS
  - DESIGN REVIEW/APPROVAL
  - MATERIALS/CONTAMINATION TEST PROGRAMS
  - SPECIFICATIONS
  - HAZARD REMOVALS
  - FAILURE ANALYSIS
2. AN ENGINEERING DATA MANAGEMENT AND TRACKING SYSTEM
  - MATERIALS SELECTION LISTS
  - PROPERTIES MANUAL
  - MATERIAL/CONTAMINATION IDENTIFICATION & TRACKING
  - AS/BUILT CONTROLS
  - COMPLETENESS VERIFICATION






ORIGINAL PAGE IS  
OF POOR QUALITY

MATERIAL CONTROL PROGRAM LOGIC




# M&P CONTROL FOR SPACE APPLICATIONS

## MATERIALS & PROCESSES ENGINEERING A SYSTEMS APPROACH



ORIGINAL PAGE IS  
OF POOR QUALITY



### CONTAMINATION CONTROL ISSUES \*

ISSUES	CURRENT DATA BASE TO RESOLVE	CONTROL W/CURRENT TECHNOLOGY	NEW TECHNOLOGY
o INHERENT HARDWARE CONTAMINATION LEVELS	60%	X	
o ASCENT/LAUNCH DRAG ALONG/INDUCED	20%		X
o ORBITAL DEBRIS	?		X
o OPERATIONS/CROSS CONTAMINATION	?	X	X
o MATERIALS DEGRADATION	20%	X	X
o MAINTENANCE PROCEDURES	30%	X	X
o PROBLEM ANTICIPATION/TRACKING/MONITORING	30%		X

\* BASED ON APOLLO/SHUTTLE PROGRAM EXPERIENCE 1960 - 1984



---

MATERIALS AND PROCESSES  
ISSUES \*

ISSUE	CURRENT DATA BASE TO RESOLVE	CONTROL W/CURRENT TECHNOLOGY	NEW TECHNOLOGY
o ADVANCED ENGINEERING MATERIALS TRACKING DATA BASE SYSTEM	70%	X	—
o IMPROVED MATERIALS AGE LIFE DATA BASE	40%	X	X
o EFFECTS OF RADIATION ON MATERIAL PROPERTIES	30%	X	X
o INTEGRATED LOGISTICAL DATA BASES	?	X	—
o MATERIAL/CONFIGURATION MAPPING (LOCATOR)	?	X	X

\*. BASED ON APOLLO/SHUTTLE PROGRAM EXPERIENCE 1960 - 1984



### EXPERIENCE:

- o OUR INVESTMENT IN MATERIALS & PROCESSES CONTROL PROCEDURES/ SYSTEMS HAS BEEN REPAYED BY REDUCED RISK/HAZARDS AS WELL AS TIMELY FAILURE ANALYSIS WHEN NEEDED.
- o MATERIAL FAILURES AND CONTAMINATION ARE STILL A MAJOR CAUSE OF SYSTEM FAILURES.
- o THE FUTURE NON-RECOVERABLE SYSTEMS SUCH AS SPACE STATION WILL DEMAND EVEN GREATER RELIABILITY, MONITORING & CONTROL.
- o AT THIS TIME, WE DON'T HAVE SUFFICIENT EXPERIENCE WITH PERMANENT MANNED AEROSPACE SYSTEMS TO PROPERLY DETERMINE ALL OF THE CRITICAL USEABILITY FACTORS.

2-38




---

RECOMMENDATIONS:

- o THERE IS AN IMMEDIATE NEED TO DEVELOP A COMPREHENSIVE MATERIALS & PROCESSES DATA BASE TO SUPPORT PHASE 'B' SPACE STATION STUDIES.
- o DEVELOP A FLIGHT PROVEN "CONTAMINATION" REAL-TIME MONITORING SYSTEM.
- o DEVELOP AN INTEGRATED/OPERATIONAL DATA BASE FOR A MATERIALS/MAINTENANCE/INCIDENTS TRACKING SYSTEM.

2-39

N85-29545



VENTILATION FLOW — SUBMERGED

2-110

(D)  
I.

## VENTILATION SYSTEM

WHEN THE SUBMARINE IS SUBMERGED, THE VENTILATION SYSTEM PROVIDES A CONDITIONED ATMOSPHERE IN THE SHIP WITH COMPLETE ISOLATION FROM THE OUTSIDE. A CONDITIONED ATMOSPHERE INCLUDES NOT ONLY FILTRATION AND TEMPERATURE AND HUMIDITY CONTROL, BUT ALSO AIR PURIFICATION (REMOVAL OF POTENTIALLY HARMFUL QUANTITIES OF IMPURITIES AND CONTAMINANTS) AND REVITALIZATION (ADDITION OF VITAL LIFE SUPPORT OXYGEN). THIS IS THE NORMAL MODE OF OPERATION OF THE VENTILATION SYSTEM.

THE REMAINING MODES EXCHANGE AIR BETWEEN THE SHIP'S ATMOSPHERE AND THE OUTSIDE AIR.  
CARBON DIOXIDE REMOVAL SYSTEM

CARBON DIOXIDE REMOVAL PLANTS PREVENT CARBON DIOXIDE IN THE SHIP'S ATMOSPHERE FROM INCREASING TO AN UNSATISFACTORY LEVEL DURING SUBMERGED OPERATIONS. THIS IS NECESSARY SINCE THE SHIP'S PERSONNEL ARE CONTINUALLY EXPIRING CARBON DIOXIDE TO THE SHIP'S ATMOSPHERE.

BLOWERS SEND EXHAUST AIR TO THE INLETS OF THE CARBON DIOXIDE REMOVAL SYSTEM PLANTS WHEN THE SHIP IS SUBMERGED. THIS PLANT BATHES THE AIR IN A CHEMICAL SOLUTION WHICH HAS AN AFFINITY FOR CARBON DIOXIDE. MOST OF THE CARBON DIOXIDE REMAINS IN THE CHEMICAL SOLUTION, AND THE AIR IS RETURNED TO THE SPACE RELATIVELY FREE OF CARBON DIOXIDE. THE PURIFIED AIR FROM THE CARBON DIOXIDE REMOVAL PLANTS IS DISCHARGED INTO THE INLET OF A VENTILATION




EXHAUST TERMINAL AND RETURNED TO THE SHIP'S VENTILATION SUPPLY HEADER WHERE IT IS DISPERSED THROUGHOUT THE SHIP.

#### CO-H2 BURNERS

2-412 THE CHEMICAL REACTION WHICH TAKES PLACE WITHIN THE CELLS OF THE MAIN STORAGE BATTERY DURING CHARGE AND DISCHARGE, PRODUCES HYDROGEN GAS WHICH IS DISPERSED INTO THE SUBMARINE ATMOSPHERE BY THE VENTILATION SYSTEM. CARBON MONOXIDE AND HYDROCARBONS FROM VARIOUS SOURCES ARE ALSO PRODUCED IN THE SHIP AND MUST BE CONTROLLED AT ACCEPTABLE LEVELS TO PREVENT EXCESSIVE BUILDUPS IN THE SHIP'S ATMOSPHERE. THE FUNCTION OF THE CO-H2 BURNERS IS TO REMOVE THESE CONSTITUENTS FROM THE ATMOSPHERE. THE VENTILATION SYSTEM SUPPLIES A REPRESENTATIVE MIXTURE OF AIR FROM THE SHIP'S EXHAUST HEADER TO THE INLET OF THE CO-H2 BURNERS. THE AIR ENTERS EACH UNIT WHERE IT IS HEATED AND, BY CATALYTIC ACTION, MOST OF THE HYDROGEN, HYDROCARBONS, AND CARBON MONOXIDE ARE BURNED. UNFORTUNATELY, SOME HYDROCARBONS WHEN BURNED PRODUCE BY-PRODUCTS WHICH ARE THEMSELVES TOXIC. THE DISCHARGE OF THE CO-H2 BURNER IS PASSED THROUGH A LITHIUM CARBONATE FILTER DESIGNED TO REMOVE THESE BY-PRODUCTS. THE AIR IS THEN DISCHARGED INTO A VENTILATION EXHAUST TERMINAL WHERE IT IS RETURNED TO THE VENTILATION SUPPLY HEADER FOR DISTRIBUTION THROUGHOUT THE SHIP.

#### OXYGEN SYSTEM

TO MAINTAIN THE OXYGEN CONTENT OF THE SHIP'S ATMOSPHERE AT THE PROPER LEVEL TO SUPPORT HUMAN LIFE DURING SUBMERGED OPERATIONS, OXYGEN IS PRODUCED BY TWO OXYGEN GENERATORS AND A CHLORATE CANDLE FURNACE. OXYGEN MAY BE BLED FROM STORAGE BANKS INTO THE SHIP FOR DILUTION AND DISPERSAL THROUGHOUT THE SHIP.



OXYGEN SYSTEM

## II.

### OXYGEN SYSTEM

STANDARD DESIGN PRACTICE CALLS FOR A NORMAL SYSTEM DESIGN OXYGEN FLOW RATE OF 1.0 SCFH PER MAN. THE PRIMARY O2 SYSTEM IS CAPABLE OF PROVIDING THIS DESIGN FLOW AS A MINIMUM FOR THE DURATION OF THE MISSION (90 DAYS). PEAK O2 REQUIREMENTS MAY BE AS MUCH AS 1.65 SCFH PER MAN FOR LIMITED PERIODS OF GREATER CREW ACTIVITY.

AN O2 BACKUP SYSTEM IS PROVIDED WHICH IS CAPABLE OF PROVIDING NORMAL O2 REQUIREMENTS OV THE CREW OVER A TEN DAY PERIOD OF SUBMERGED OPERATION.


IN ADDITION, AN EMERGENCY O2 SYSTEM IS CAPABLE OF PROVIDING NORMAL O2 REQUIREMENTS OVER SHORTER PERIODS OF TIME.

THE PRIMARY SOURCE OF OXYGEN ON A NUCLEAR SUBMARINE IS AN ELECTROLYTIC OXYGEN GENERATOR WHICH SUPPLIES 3000-PSI OXYGEN TO CHARGE OXYGEN STORAGE FLASKS.

OXYGEN IS NORMALLY DISCHARGED DIRECTLY TO THE SHIP'S ATMOSPHERE THROUGH PRESSURE-REDUCING VALVES AND DIFFUSERS. THE OXYGEN FLASKS ARE CHARGED FROM SHORE AT THE START OF A PATROL AND ARE KEPT FULLY CHARGED BY THE OXYGEN GENERATOR TO PROVIDE SIX DAYS' RESERVE SUPPLY IN THE EVENT OF O2 GENERATOR FAILURE.

THE OXYGEN GENERATOR PRODUCES O2 BY THE ELECTROLYSIS OF DEMMERALIZED WATER USING ELECTROLYTIC CELLS, DISPELLING THE HYDROGEN OVERBOARD. A POTASSIUM HYDROXIDE SOLUTION TO PROVIDE CONDUCTIVITY IS USED AS THE ELECTROLYTIC SOLUTION.

CHLORATE CANDLES ARE AVAILABLE FOR A BACKUP SYSTEM AND THE STORED OXYGEN IS CLASSIFIED AS AN EMERGENCY SUPPLY.



2-45

**CHILLED WATER SYSTEM**

### III.

### AIR CONDITIONING


AN AIR CONDITIONING SYSTEM PROVIDES AND MAINTAINS A COOLED AND DEHUMIFIED ATMOSPHERE FOR EQUIPMENT AND PERSONNEL ON THE SHIP. THE SYSTEM CONSISTS OF R-114 AIR CONDITIONING UNITS, A CHILLED WATER SYSTEM, AND AN AIR CONDITIONING CONTROL SYSTEM.

THE R-114 AIR CONDITIONING PLANTS EMPLOY DICHLOROTETRAFLUORETHANE (R-114) AS A REFRIGERANT. THE THERMODYNAMIC PROPERTIES OF R-114 MAKE IT IDEAL AS A HEAT TRANSFER MEDIUM. R-114 IS ALSO CHEMICALLY STABLE, NON-CORROSIVE, AND NON-TOXIC. THE R-114 VAPOR COMPRESSION UNITS REMOVE HEAT PICKED UP THE CHILLED WATER SYSTEM FROM EQUIPMENT AND LIVING SPACES AND TRANSFERS THE HEAT TO SEAWATER.

A CHILLED WATER SYSTEM CIRCULATES WATER CHILLED BY THE REFRIGERANT TO COOLING COILS AND HEAT EXCHANGERS FOR AIR CONDITIONING AND EQUIPMENT COOLING. VENTILATION FANS FORCE AIR PAST THE COOLING COILS WHERE THE AIR IS COOLED AND DEHUMIDIFIED. HEAT IS TRANSFERRED FROM THE AIR TO THE CHILLED WATER IN THE COILS. OTHER COMPONENTS ARE COOLED BY CHILLED WATER FLOWING THROUGH THEIR HEAT EXCHANGERS. THE WARM CHILLED WATER RETURNS TO THE AIR CONDITIONING UNIT CHILLERS, WHERE ITS HEAT IS TRANSFERRED TO THE REFRIGERANT AND ULTIMATELY TO THE SEAWATER.

THE AIR CONDITIONING CONTROL SYSTEM SENSES TEMPERATURE AND HUMIDITY IN EQUIPMENT AND LIVING SPACES. THE SENSING DEVICES ARE PNEUMATICALLY OPERATED THERMOSTATS AND HUMIDISTATS

WHICH SENSE CHANGES IN TEMPERATURE AND HUMIDITY AND CONVERT THESE SIGNALS INTO AIR SIGNALS. RESULTING AIR SIGNALS ARE COMPARED IN LOGIC CIRCUITS WHERE THE STRONGEST DEMAND ACTUATES THE FINAL CONTROL ELEMENT TO SATISFY COOLING, DEHUMIDIFICATION, OR HUMIDIFICATION REQUIREMENTS.



IV.

CARBON MONOXIDE REMOVAL

STANDARD PRACTICE IN SUBMARINE DESIGN CALLS FOR MAINTAINING CO<sub>2</sub> LEVELS AT OR BELOW 0.5%.

A PROVISION FOR BACKUP AND EMERGENCY CO<sub>2</sub> REMOVAL SPECIFIES A SUPPLY OF LITHIUM HYDROXIDE (LiOH).

THE PRIMARY SYSTEM FOR CO<sub>2</sub> REMOVAL IS THE MONETHANOL AMINE (MEA) SCRUBBER. GENERALLY, EACH SUBMARINE WILL HAVE TWO OF THESE UNITS. THE PROCESS FOR CO<sub>2</sub> REMOVAL IS ONE OF ABSORPTION. THE ABSORPTION AGENT IS MONETHANOLAMINE (AMINE OR MEA). THE LATEST SCRUBBERS CAN REMOVE THE INLET AIR CO<sub>2</sub> CONCENTRATION OF 1.5% TO ABOUT 0.2% AT THE OUTLET, AT A RATE OF 170 CUBIC FEET PER MINUTE. THE TWO SCRUBBERS TAKE SUCTION ON THE SHIP'S AIR AND ABSORB THE CO<sub>2</sub> IN AN AMINE SOLUTION. THE CO<sub>2</sub> IS REMOVED FROM THE AMINE SOLUTION AND DISCHARGED OVERBOARD. THE AMINE SOLUTION IS RE-USED IN THE SCRUBBERS.

THE CO<sub>2</sub> REMOVAL PLANT CONTAINS FIVE INTERRELATED SYSTEMS: AIR CIRCULATION SYSTEM, MONOETHANOLAMINE (MEA OR AMINE) CIRCULATING SYSTEM, CARBON DIOXIDE REMOVAL SYSTEM, AIR-CONDITIONING CHILLED WATER SYSTEM, AND AN ELECTRICAL AND INSTRUMENTATION SYSTEM.

THE AIR CIRCULATION SYSTEM FORCES ATMOSPHERIC AIR INTO THE TOWER AND DOWN THROUGH PACKING. AS THE AIR PASSES THROUGH THE TOWER, THE CO<sub>2</sub> IS ABSORBED BY A COOL AMINE SOLUTION, WHICH IS SPRAYED OVER THE PACKING. AT THE BOTTOM OF TOWER, A FILTER FUNNEL



LEADS THE PURGED AIR TO AN AIR PURIFIER WHERE THE AIR IS WASHED IN A SOLUTION OF FRESH WATER AND SODIUM BISULPHATE TO REMOVE THE ODOR OF AMMONIA.

THE AMINE IS CONTINUOUSLY RECYCLED THROUGH THE ABSORBER TOWER, ENTERING THE TOP THROUGH SPRAY NOZZLES, FLOWS DOWN THROUGH THE PACKING, COLLECTS IN THE BOTTOM, AND RETURNS TO THE SPRAY HEAD VIA A RECYCLING PUMP.

CO<sub>2</sub> IS REMOVED FROM THE AMINE BY HEATING AND STRIPPING. A SMALL AMOUNT OF THE CO<sub>2</sub> SATURATED AMINE IS DRAWN FROM THE BOTTOM OF THE TOWER AND ENTERS A HEAT EXCHANGER WHERE IT IS PREHEATED BY HOT, LEAN (STRIPPED) AMINE RETURNING FROM THE STRIPPER TOWER.

IN THE STRIPPER TOWER, AMINE ENTERS THE MIDDLE SECTION THROUGH SPRAY NOZZLES WHERE IT SEPARATES INTO MOISTURE AND AMINE VAPOR AND CO<sub>2</sub> GAS. THE AMINE VAPORS CONDENSE ON RINGS BENEATH SPRAY NOZZLES AND FLOWS DOWN TO THE BOTTOM SECTION. THE CO<sub>2</sub> AND A SMALL AMOUNT OF MOISTURE RISE TO THE TOP SECTION.


IN THE TOP SECTION, FRESH WATER TUBES CONDENSE THE MOISTURE, AND THE CO<sub>2</sub> PASSES TO A WATER SEPARATOR WHERE THE REMAINING MOISTURE IS REMOVED.

AFTER COMPRESSION, THE CO<sub>2</sub> FROM BOTH SCRUBBERS IS DISCHARGED OVERBOARD VIA SEA WATER PIPING. THE AIR-CONDITIONING CHILLED WATER COOLING SYSTEM SUPPLIES WATER TO THE COOLER SECTION OF THE AIR PURIFIER, THE CO<sub>2</sub> COOLER, AND AN AMINE COOLER.

THE ELECTRICAL AND INSTRUMENTATION SYSTEMS CONTROL ALL ASPECTS OF THE CO<sub>2</sub> SCRUBBER.

CANISTERS ARE USED FOR BACKUP AND EMERGENCY CO<sub>2</sub> REMOVAL. IN THE BACKUP METHOD, AIR IS VENTILATED THROUGH CANISTERS OF LIOH BY A FAN AND FILTER ARRANGEMENT.

IN THE EMERGENCY MODE, THE CANISTERS ARE OPENED AND THE LIOH SPREAD ON THE FLOOR OR OTHER HORIZONTAL SURFACES WHERE NATURAL DIFFUSION ACTS TO CONTACT THE CO<sub>2</sub> WITH THE LIOH.



CO-H<sub>2</sub> BURNER

15  
V.

#### CARBON MONOXIDE AND HYDROGEN REMOVAL

CARBON MONOXIDE (CO) AND HYDROGEN (H<sub>2</sub>) CONCENTRATIONS AND HYDROGEN CONTAMINANTS ARE MAINTAINED WITHIN ESTABLISHED LIMITS BY MEANS OF THE SHIP'S AIR REVITALIZATION SYSTEM.

CARBON MONOXIDE (CO) IS PRODUCED BY THE SMOKING OF TOBACCO, COOKING (PARTICULARLY WHEN FOOD IS BURNED), AND OVERHEATING OF ELECTRICAL EQUIPMENT. A SMALL AMOUNT OF CO IS ALSO GIVEN OFF BY THE HUMAN BODY. THE AMOUNT OF CO A PERSON CAN TOLERATE IS DEPENDENT ON THE LENGTH OF EXPOSURE. THE MAXIMUM CONCENTRATION FOR 90 DAYS CONTINUOUS EXPOSURE HAS BEEN ESTABLISHED AS 25 PARTS PER MILLION.

THE MAJOR SOURCE OF HYDROGEN (H<sub>2</sub>) IS THE SHIP'S BATTERY, WHICH GIVES OFF HYDROGEN DURING CHARGING. OTHER SOURCES ARE POSSIBLE LEAKAGE OF THE HYDROGEN BOTTLES, THE OXYGEN GENERATOR, AND THE SANITARY TANK PIPING.

NUMEROUS TYPES OF HYDROCARBONS ARE PRODUCED FROM MATERIALS SUCH AS DIESEL FUEL OIL, CLEANING SOLVENTS, LUBE OILS, COOKING FATS, CIGARETTE LIGHTER FLUID, PAINTS, AND MANY OTHER SOURCES.

DURING SUBMERGED OPERATIONS, CO-H<sub>2</sub> BURNERS REMOVE CARBON MONOXIDE AND HYDROGEN FROM THE SHIP'S ATMOSPHERE BY OXIDIZING CARBON MONOXIDE TO CO<sub>2</sub>, HYDROGEN TO WATER VAPOR AND HYDROCARBONS TO CO<sub>2</sub> AND WATER VAPOR.

THE PURIFIED AIR IS RETURNED TO THE SHIP'S ATMOSPHERE. THE CO<sub>2</sub> IS REMOVED BY THE CO<sub>2</sub> SCRUBBERS AND THE WATER VAPOR IS CONDENSED BY THE AIR CONDITIONING COOLING COILS.

IN THE CO-H<sub>2</sub> BURNERS, A FAN DRAWS COMPARTMENT AIR INTO THE INLET DUCT THROUGH A FILTER AND INTO THE INLET SIDE OF A HEAT EXCHANGER WHERE THE AIR IS PREHEATED TO THE FIRST OF THREE LEVELS. THE AIR IS HEATED TO A SECOND LEVEL BY PASSING OVER A BANK OF ELECTRIC HEATERS, AND TO THE THIRD AND FINAL LEVEL BY BURNING HYDROGEN IN THE CATALYST BED AT A TEMPERATURE OF 600°F. THE HEAT IS PARTIALLY REMOVED FROM THE AIR STREAM AS IT PASSES THROUGH THE OUTLET SIDE OF THE ~~MAN~~ HEAT EXCHANGER. THIS HEAT IS TRANSFERRED TO THE AIR ENTERING THE INLET DUCT OF THE HEAT EXCHANGER. BECAUSE THE HEAT EXCHANGER CANNOT REMOVE ALL THE HEAT FROM THE OUTGOING AIR, AN AFTERCOOLING COIL IS USED TO COOL THE AIR TO THE REQUIRED EXIT TEMPERATURE BEFORE IT IS DISCHARGED FROM THE UNIT.

IT IS IN THE CATALYST CHARCOAL BED, CONSISTING OF 10% LIOH AND 90% HOPCALITE THAT THE CHEMICAL REACTIONS TAKE PLACE PRODUCING THE CO<sub>2</sub> AND H<sub>2</sub>O. THE INCREASING AIR <sup>TEMP.</sup> IS SUFFICIENT TO START THE REACTIONS. THE CHARCOAL BED IS CHANGED PERIODICALLY.


SOME PROBLEMS OCCUR WITH THE DECOMPOSITION OF HALOCARBONS WHICH MAY RESULT IN THE PRODUCTION OF ACIDE GASSES. THE OUTLET AIR IS THUS PASSED THROUGH A LiCO<sub>3</sub> FILTER WHICH DECOMPOSES MOST OF THE HALOCARBONS. THE EFFICIENCY OF THE FILTER HOWEVER IS LESS THAN 100%.

VI.

OTHER CONTAMINANT REMOVAL SYSTEMS

AIR PROCESSING UTILIZING ELECTROSTATIC PRECIPITATORS IS THE PRINCIPLE METHOD FOR REMOVING PARTICULATES (AEROSOLS).

ACTIVATED CHARCOAL BEDS AND HIGH EFFICIENCY FILTERS ARE ALSO IN USE THROUGHOUT THE SHIP'S VENTILATION SYSTEMS.



2-56

# ATMOSPHERE ANALYZING SYSTEM

ORIGINAL PAGE IS  
OF POOR QUALITY


6  
VII.

ATMOSPHERE MONITORING SYSTEMS

2-57 THE ATMOSPHERE ANALYZER SYSTEMS AND THE TOTAL HYDROCARBON ANALYZER COMPRISE THE PRIMARY ATMOSPHERE MONITORING SYSTEMS FOR THE SHIP. THE ATMOSPHERE MONITORING EQUIPMENT, TERMED THE CENTRAL ATMOSPHERE MONITORING SYSTEM (CAMS) ANALYZES REPRESENTATIVE AIR SAMPLES FROM VARIOUS LOCATIONS WITHIN THE SHIP THROUGH A SAMPLE SELECTOR VALVE. IN ADDITION, THE TOTAL HYDROCARBON ANALYZER IS USED TO EVALUATE THE EFFECTIVENESS OF THE INSTALLED VENTILATION SYSTEM CARBON FILTERS. THE LOCATION AND IDENTIFICATION OF ATMOSPHERIC CONTAMINANT CONCENTRATIONS BY THESE SYSTEMS IS THE BASIS FOR THE CORRECTIVE ACTION WHICH MUST BE TAKEN TO SOLVE THE CONTAMINANT PROBLEM IN THE SHIP'S ATMOSPHERE SUCH AS THE PROPER USE OF THE SCRUBBERS, BURNERS, AND O<sub>2</sub> GENERATORS. MANIPULATION OF THE VENTILATION SYSTEM IS ALSO NECESSARY TO CONTROL CONTAMINANTS. FOR INSTANCE, EMERGENCY EVACUATION OF A COMPARTMENT WITH SPECIAL BLOWERS MAY BE REQUIRED TO REMOVE HIGH CONCENTRATIONS OF CONTAMINANTS. PORTABLE ANALYTICAL MONITORING EQUIPMENT IS ALSO AVAILABLE.

THE ABILITY TO CONTROL SUBMARINE ATMOSPHERE QUALITY RESTS ON PRECISE MONITORING OF ATMOSPHERIC CONSTITUENTS. PROPER USE OF THE SCRUBBERS, BURNERS, AND OXYGEN GENERATORS IS GOVERNED BY CONCENTRATION MEASUREMENTS OF BOTH VITAL AND HARMFUL GASES IN THE SHIPS ATMOSPHERE. THIS INFORMATION IS OBTAINED FROM THE SHIPS CAMS, TOTAL HYDROCARBON ANALYSIS (THA), AND PORTABLE ANALYTICAL MONITORING EQUIPMENT.





**CAMS MK I  
MASS SPECTROMETER ANALYZER**


THE CAMS MONITORS AND MEASURES THE FOLLOWING CONTAMINANTS AND COMPONENTS OF THE SHIPS ATMOSPHERE:

- (1) CARBON MONOXIDE (CO)
- (2) HYDROGEN (H<sub>2</sub>)
- (3) OXYGEN (O<sub>2</sub>)
- (4) CARBON DIOXIDE (CO<sub>2</sub>)
- (5) NITROGEN (N<sub>2</sub>)
- (6) WATER VAPOR (H<sub>2</sub>O)
- (7) FREON 12
- (8) FREON 11 OR 114, AS SELECTED

CAMS, UTILIZING THE PRINCIPLES OF MASS SPECTROSCOPY AND NON-DISPERSIVE INFRARED TO ANALYZE THE SUBMARINE'S ATMOSPHERE CONSTITUENTS, IS THE RESULT OF A NUMBER OF EXPERIMENTS WITH SUBMARINES AND THE ADVANCES IN MASS SPECTROMETRY IN THE LATE 1960'S, LARGELY BECAUSE OF THE SPACE PROGRAM.

SUBMARINES HAVE APPROXIMATELY A DOZEN LOCATIONS FROM WHICH SMALL TUBING LEADS TO A SAMPLE SELECTOR VALVE. A SAMPLE IS DRAWN THROUGH A COMPARTMENT FILTER, THROUGH THE TUBING AND SELECTOR VALVE, AND INTO THE CENTRAL ANALYZER. INDIVIDUAL COMPARTMENTS CAN BE SAMPLED BY TURNING THE SAMPLE SELECTOR VALVE TO THE APPROPRIATE POSITION. SAMPLES ENTER ALL THE CENTRAL ANALYZERS AT ATMOSPHERIC PRESSURE.


ORIGINAL PAGE IS  
OF POOR QUALITY



CENTRAL ATMOSPHERE MONITOR MK I  
FUNCTIONAL BLOCK DIAGRAM

②  
IN CAMS, GASEOUS SAMPLES ARE INTRODUCED INTO THE MASS SPECTROMETER THROUGH AN INLET SYSTEM WHICH REDUCES THE SAMPLE PRESSURE TO A LEVEL COMPATIBLE WITH THE ION-SOURCE OPERATING PRESSURE. THE SAMPLE IS SEPARATED AND SENT TO THE MASS SPECTROMETER PORTION OF THE INSTRUMENT. THE MAJOR PORTION OF THE INLET SAMPLE IS DIVERTED TO A NON-DISPERSIVE INFRARED ANALYZER WHICH EXAMINES THE SAMPLE FOR CARBON MONOXIDE.

THE CAMS PERFORMANCE HAS BEEN EXCELLENT. THE TWO MOST SIGNIFICANT PROBLEMS HAVE BEEN WITH THE CO ANALYZER AND THE INLET LEAK VALVE. OTHER PROBLEMS HAVE OCCURRED IN THE MASS SPECTROMETER POWER SUPPLY AND THE ION PUMP POWER SUPPLY. BOTH OF THESE POWER SUPPLIES HAVE MODIFICATION KITS WHICH CAN UPGRADE THE ANALYZERS TO PERFORM MORE SATISFACTORILY.



2-62

THA SYSTEM


## VII.

### TOTAL HYDROCARBON ANALYZER

DURING SUBMERGED OPERATION, THE CLOSED ATMOSPHERE OF A SUBMARINE IS SUSCEPTIBLE TO A BUILDUP OF TOXIC AND A CORROSIVE GASES, A PORTION OF WHICH ARE HYDROCARBONS. EXAMPLES OF THE MORE COMMON HYDROCARBONS ARE METHANE (FROM CIGARETTE SMOKE AND THE SANITARY TANKS), BENZENE (FROM SOLVENTS, FUEL OIL, AND LUBE OIL), R-12 (FROM REFRIGERATION PLANTS) AND R-114 (FROM THE AIR CONDITIONING PLANTS). THE TOTAL HYDROCARBON ANALYZER (THA) MEASURES THE CONTAMINANT LEVELS OF SOME SPECIFIC HYDROCARBONS AND GROUPS THE HEAVIER HYDROCARBONS INTO A MEASURABLE QUANTITY.

2-63 THE TOTAL HYDROCARBON ANALYZER (THA) IS AN INSTRUMENT WHICH UTILIZES GAS CHROMATOGRAPHY TO INDICATE THE CONCENTRATIONS OF HYDROCARBON GASES. THE SYSTEMS CONSISTS OF AN ANALYZER CONSOLE, WHICH SEPARATES AND MEASURES THE HYDROCARBON GASES; AN AIR PURIFIER AND ACID SCRUBBER ASSEMBLY, WHICH PURIFIES AIR FROM THE SHIP'S COMPRESSED AIR SYSTEM AND REMOVES ANY ACIDS WHICH MAY BE FORMED DURING THE PURIFICATION PROCESS; A STRIP CHART RECORDER, WHICH RECORDS THE INDICATED CONCENTRATIONS OF HYDROCARBON GASES; HYDROGEN CYLINDERS TO PROVIDE FUEL WHICH IS USED IN THE FLAME IONIZATION DETECTOR; TWO CALIBRATION GASES; AND A 100CC GLASS SYRINGE WHICH IS USED TO COLLECT GAS SAMPLES.

THE OPERATION OF THE ANALYZER CONSOLE, IN WHICH THE SEPARATION AND ANALYSIS OF A GAS SAMPLE OCCURS, IS FUNCTIONALLY DEPENDENT UPON THE SIMULTANEOUS OPERATION OF THE AIR




**TOTAL HYDROCARBON ANALYZER**  
**SIMPLIFIED DIAGRAM OF A GAS CHROMATOGRAMS**

PURIFIER/ACID SCRUBBER. THE AIR PURIFIER/ACID SCRUBBER PROVIDES A PURE AIR SUPPLY FOR USE AS A CARRIER GAS (COLUMN AIR) AND FOR USE AS COMBUSTION AIR (FLAME AIR) USED IN THE FLAME IONIZATION DETECTOR.

THE AIR PURIFIER/ACID SCRUBBER RECEIVES AIR FROM THE EAB SYSTEM WHICH FLOWS THROUGH A HEATER AND INTO THE ACID SCRUBBER LIOH CARTIRIDGE FOR REMOVAL OF ANY RESIDUAL ACIDS PRODUCED BY THE CHEMICAL REACTION OF CONTAMINANTS WITH THE AIR PURIFIER CATALYST. THE AIR, NOW FREE OF HYDROCARBON AND ACID CONTAMINANTS, FLOWS THROUGH THE AIR OUT PORT ON THE FRONT PANEL AND THROUGH THE CONNECTED HOSE TO THE AIR INLET PORT OF THE ANALYZER CONSOLE.

THIS IS WHERE THE ACTUAL BREAKDOWN AND ANALYSIS OF GAS SAMPLES OCCURS. THERE, THE CHROMATOGRAPH COLUMN SEPARATES A MULTICOMPONENT GAS SAMPLE MIXTURE INTO ITS INDIVIDUAL COMPONENTS. A CONSTANT FLOW OF GAS, CALLED CARRIER OR COLUMN GAS, PASSES THROUGH THE COLUMN CONTINUOUSLY AND TRANSPORTS THE SAMPLE GAS THROUGH THE COLUMN. A PRECISELY MEASURED VOLUME OF THE SAMPLE GAS IS INTRODUCED INTO THE COLUMN. A FLAME IONIZATION DETECTOR, LOCATED AT THE OUTLET OF THE COLUMN, DETECTS THE CONCENTRATIONS OF THE SAMPLE GAS COMPONENTS AS THEY EMERGE FROM THE CHROMATOGRAPH COLUMN IN THE CARRIER GAS STREAM. THE ASSOCIATED ELECTRICAL SIGNAL GENERATED BY THIS PROCESS IS AMPLIFIED AND FED TO A STRIP CHART RECORDER. THE RECORDER PLOTS THE OUTPUT SIGNAL AGAINST TIME, AND THE RESULTING GRAPH IS CALLED A CHROMATOGRAM.





INTEGRATED LIFE SUPPORT MONITORING/CONTROL

IX.


INTEGRATED LIFE SUPPORT SYSTEM

AN IMPROVED CAMS HAS BEEN DEVELOPED, EVALUATED AND LABORATORY-TESTED AND IS SCHEDULED FOR QUALIFYING FOR SUBMARINE USE BY THE NAVAL RESEARCH LABORATORY AND PERKINS-ELMER CORP. THE NEW CAMS (TERMED MK11) CAN MONITOR MORE GASES, HAS A PROGRAMMABLE PROCESSOR THAT PERMITS THE SELECTION OF GASES TO BE MONITORED, AND HAS DATA-RECORDING CAPABILITIES.

THE EARLIER CAMS (MK1) IS A FIXED COLLECTOR MASS SPECTROMETER CAPABLE OF MONITORING ONLY EIGHT IONS OF PRE-SELECTED MASS TO CHARGE RATIOS.

NEW ENVIRONMENTAL CHANGES COULD REQUIRE THE NEED TO MONITOR NEW TYPES AND LEVELS OF CONTAMINANTS, THUS, A SCANNING MASS SPECTROMETER HAS BEEN DEVELOPED. THE USE OF THIS SOMEWHAT DELICATE INSTRUMENT IS NOW CONSIDERED FEASIBLE BECAUSE OF ADVANCED COMPUTER TECHNOLOGY AND INSTRUMENTATION PACKAGING. THE IMPROVED CAMS WILL MEASURE HYDROCARBONS (ELIMINATING THE NEED FOR THAS), HAVE THE CAPABILITY TO CONTINUOUSLY DISPLAY CONCENTRATION OF SELECTED GAS, ADD AND/OR DELETE CONTAMINANTS VIA COMPUTER SOFTWARE CHANGES, AND ACTIVATE AN ALARM SYSTEM FOR OUT-OF-TOLERANCE CONDITIONS.

IF PROVEN SUCCESSFUL, MINOR MODIFICATIONS COULD ALLOW AN INTEGRATED LIFE SUPPORT SYSTEM WITH APPROPRIATE ALARMS AND CONTROLS.



RELATIONSHIP OF RELIABILITY MINIMUMS  
TO DEGRADATION RATE

12  
X.

PERFORMANCE MONITORING/CONDITION ASSESSMENT

MANY SUBMARINE LIFE SUPPORT SYSTEMS AND COMPONENTS HAVE THEIR OPERATING PERFORMANCE MEASURED, ANALYZED FOR DEGRADATION TRENDS, AND ASSESSED FOR MATERIAL CONDITIONS IN ORDER TO CONDUCT MAINTENANCE ACTIONS PRIOR TO REACHING UNRELIABLE CONDITIONS.

THE PROCESS OF ESTABLISHING A PERFORMANCE MONITORING/MATERIAL ASSESSMENT PROGRAM INVOLVES THE SELECTION OF SYSTEMS AND COMPONENTS, THE PERFORMANCE AND MATERIAL CONDITION CRITERIA, INSPECTIONS AND MONITORING PROCEDURES, AND ANALYSIS AND ASSESSMENT TECHNIQUES. RELIABILITY MINIMUM VALUES NEED TO BE ESTABLISHED PRIOR TO ATTEMPTING TO DETERMINING WHETHER OR NOT THE PROPER PARAMETER CAN BE MEASURED TO ALLOW SOME REASONABLE TREND ANALYSIS AND PREDICTION FOR MAINTENANCE.

IN THE SAMPLE GRAPH, CURVE A INDICATES THE DEGRADATION RATE OF COMPONENTS WHERE LITTLE, OR NO MEASURABLE REDUCTION IN PERFORMANCE OR CONDITIONS IS EXPERIENCED OVER TIME. AT THE OTHER EXTREME, CURVE B SHOWS A COMPONENT SUBJECT TO INSTANTANEOUS FAILURE WITHOUT ANY PRIOR MEASURABLE DEGRADATION IN PERFORMANCE. RELIABILITY HAS NO REAL MEANING IN EITHER CASE. CURVE C ILLUSTRATES, AFTER SOME LEVEL OF DEGRADATION IS REACHED, THAT THE RATE OF DEGRADATION ACCELERATES RAPIDLY.

TOXICITY AND THE SMOKE PROBLEM: Harold L. Kaplan, Arthur F. Grand  
and Gordon E. Hartzell, Department of Fire Technology, Southwest  
Research Institute, San Antonio, TX 78284

This paper was originally printed in COMBUSTION TOXICOLOGY:  
PRINCIPLES AND TEST METHODS, Techomic Publishing Company, Inc.,  
Lancaster, PA (1983), and was reprinted by their permission in the  
Fire Safety Journal No. 7., (1984) 11-23.

AMBIENT AIR CONTAMINATION--CHARACTERIZATION AND DETECTION TECHNIQUES  
C. P. Nulton and H. S. Silvas

Until recently, work on indoor contamination has focused primarily on: 1) the criteria air pollutants [oxides of S, N and C, particulates and ozone]; 2) uniquely indoor contaminants [e.g., radon, formaldehyde, tobacco smoke and asbestos]; and 3) the work place pollutants for which American Conference of Governmental Industrial Hygienists (ACGIH) sets guidelines [e.g., organic solvents, metal fumes and wood dust].

Currently, concern centers on outgassing of synthetic construction and maintenance materials such as adhesives, sealants, insulation, wall coverings, cleaners, and electronic equipment inside of new, well-insulated, energy-conserving buildings. The effects of outgassing of synthetic materials in a closed system on human health and productivity is relevant to Space Station.

Indoor contaminants may cause acute reactions (e.g., poisoning by combustion products) or, more often, chronic problems develop due to low-level, long-term exposure. Southwest Research Institute (SWRI) has assisted many industrial clients in determining the source of contamination of the latter type that cause decreased worker productivity.

Chemical characterization of indoor contaminants can be divided into methods which are designed to target compounds, and those which provide for a broad range search. Typical of the former are the National Institute of Occupational Safety and Health methods that often involve either the use of solid adsorbants, or liquid impingers for sampling followed by analysis for target compounds by GC, or colorimetric detection. In cases where an

organic contaminant is suspected but unknown, broader range techniques are required. Samples may be taken by pulling ambient air through adsorbants, e.g., Tenax® and Carbosieve®, which can be desorbed thermally onto GC columns for subsequent GC/MS analysis. A further refinement is to cryogenically focus the trapped organics then to volatilize them as a discrete plug onto a fused-silica capillary GC column, thus obtaining the advantages of increased resolution and overall superior chromatography.<sup>1</sup>

Another approach to organic sampling is the use of polyurethane foam (PUF) plugs which are relatively inert and allow for the collection of large sample volumes (e.g., 285 L/min for 4 hours). PUF samples have been used to sample for trace concentrations of relatively high molecular weight organics, e.g., PCBs, dioxins and pesticides.<sup>2,3</sup>

At SWRI we are characterizing the organics generated from indoor materials at ambient conditions and upon combustion. These experiments are conducted in a closed system (bell jar) with evolved organic compounds being collected on Tenax®, PUF plugs and/or liquid impingers. In one such study organic emissions from a very small electrical fire were characterized. A 5-cm<sup>2</sup> portion of circuit board was placed in the test vessel and a resistor (100 ohm) was overloaded causing it to flare and scorch approximately 1 cm<sup>2</sup> of the circuit board. The duration of the "fire" was approximately 10 seconds. The volume of the test vessel (2.8 L) was then collected on Tenax® and analyzed by GC/MS to reveal a variety of organics (Table 1) including halogenated and aromatic hydrocarbons. Analysis of system blanks also showed that the 5-cm<sup>2</sup> portion of circuit board emitted detectable levels of trichloroethylene and trichlorotrifluoroethane at ambient conditions.

An additional example is provided by the organic emissions from an insulation material that causes dramatic biological effects when combusted.<sup>4</sup> Although a wide variety of organics were characterized (Table 2), the chemical responsible for its unusual biological activity has not yet been identified.

Departing from the discussion of airborne contaminant characterization, I want to mention briefly the detection of critical levels of specific compounds or compound classes with coated quartz oscillators. Sensors of this type may be used to protect equipment as well as people.

Piezoelectric quartz crystals have been used for many years as precision frequency-determining elements in electronic oscillators. When properly cut and prepared, such crystals can maintain the frequency of an oscillator stable within a few parts per million over a nominal temperature range; with close temperature control, frequency stability on the order of parts per billion can be achieved.

The resonant frequency of a piezoelectric quartz crystal is determined by the particular mechanical mode in which the crystal operates and by certain critical dimensions characteristic of the mode. Additionally, as with any mechanical vibrating system, mass added to the surface of the crystal produces a loading effect that lowers resonant frequency. The absolute change in frequency is linearly related to added mass over a substantial range.

At Southwest Research Institute, this basic principle has been applied to measurement of the quantity of odorant in natural gas.<sup>5</sup> The technique employed is to apply a thin coating to the surfaces of a quartz frequency-



control crystal. The materials in the coating were designed to react with tertiary butyl mercaptan (TBM), a commonly used odorant for natural gas. The crystal was connected in an electronic oscillator circuit, oscillation frequency of which was monitored by a precision electronic counter. Odorant-containing natural gas was flowed through a sample chamber surrounding the crystal (see Figure 1), and oscillator frequency changed in inverse proportion to the mass added to the crystal by reaction of the odorant with the crystal coating. By using known concentrations of odorant, it was possible to calibrate the frequency change in terms of odorant concentration.

Approximately 5 parts per million of TBM is commonly used in natural gas as odorant. The instrument described could readily quantify this concentration of odorant with a precision of  $\pm 0.5$  part per million (Figure 2) and could detect changes in odorant concentration of less than 1 part per million absolute.

Quartz oscillators have a number of advantages for air monitoring including their small size, inherent sensitivity and potential for tailoring either coatings or the active quartz surface for high specificity.

Although the work I have briefly described characterizing organic air contaminants and detecting critical levels of target compounds in air is not related directly to cabin atmospheres the techniques involved become increasingly relevant to NASA as the duration of manned flights is extended and the volume and variety of on-board materials increase.

#### REFERENCES

1. Pellizzari, E. D. Development of Analytical Techniques for Measuring Ambient Atmospheric Carcinogenic Vapors. EPA Contract 68-02-1228, November 1975.
2. Lewis, R. G., A. R. Brown, M. D. Jackson. Anal. Chem., **49**:1668, 1977.
3. Lewis, R. G. and M. D. Jackson. Anal. Chem. **54**:592, 1982.
4. Kaplan, H. These proceedings.
5. Millar, J. D., H. S. Silvus, L. M. Adams, H. J. Schattenberg III and L. L. Altpeter. Development of a Portable Instrument to Determine Odorants in Gas Distribution Lines. Presented at the International Gas Research Conference, London England, June 1983.

TABLE 1. ORGANICS ARISING FROM FLARING A RESISTOR

Class	Compound	Amount, ng
Br-containing	bromomethane	26,000
	dibromomethane	3,400
	bromobenzene	2,500
	bromoethane	<1,000
Cl-containing	1,1,1-trichloroethane	170,000
	dichlorobenzene	78,000
	trichlorotrifluoroethane	53,000
	1,1-dichloroethane	22,000
	1,1-dichloroethylene	20,000
	dichlorotrifluoroethane	6,400
	chloroform	6,400
	vinyl chloride	<1,000
Aromatic Hydrocarbons	toluene	75,000
	C <sub>2</sub> -benzenes	36,000
	benzene	22,000
Aliphatic Hydrocarbons		~80,000
Others	benzofuran	1,800
	benzaldehyde	1,800
	phenol	<1,000
	acetone	5,200
	methylbutynol	5,200
	methylbutanol	5,100
	methylpentanone	<1,000
	2-furancarboxaldehyde	<1,000
	dimethylethylborane	1,000
	benzonitrile	1,000
	2-propenenitrile	<1,000

TABLE 2. COMPOUNDS GENERATED BY HEATING COMMERCIAL INSULATION

Chloromethylpropane  
Dichlorobenzene

Benzene  
Toluene  
Xylenes

Pyridine  
Methylpyridine

Methylpropenenitrile  
Benzonitrile  
Methylbenzonitriles  
Dimethylbenzonitrile

Carbon Disulfide  
Methylthiophene  
Methylisothiocyanate




Figure 1. Experimental Arrangement for Evaluation of Quartz-Crystal Odorant Analyzer




Figure 2. Response of Quartz-Crystal Sensor to Known Concentrations of Tertiary Butyl Mercaptan in Methane

N85-29547



National  
Aeronautics and  
Space  
Administration

---

# EXTENDED MISSION LIFE SUPPORT SYSTEMS

Prepared by  
P. D. QUATTRONE

June, 1981

AMES RESEARCH CENTER  
NATIONAL AERONAUTICS AND SPACE ADMINISTRATION

## FOREWORD

The material in this paper was presented at the Case For Mars Conference, Boulder, Colorado, April 30, 1981. This paper in its entirety, will be published by the Boulder Center for Science and Policy. Any inquiries for official conference papers and proceedings should be directed to:

Case For Mars  
P. O. Box 4877  
Boulder, CO 80306

This pre-print was prepared solely for internal use by NASA.

## LIST OF ACRONYMS

ARS	Air Revitalization System
ARX-1	Air Revitalization System (Experimental) - 1 person
ASF	Amps per Square Foot
CELSS	Controlled Ecological Life Support System
C/M I	Control/Monitor Instrumentation
CRT	Cathode Ray Tube
EC/LSS	Environmental Control/Life Support Systems
EDC	Electrochemical Depolarized Concentrator
EDO	Enhanced Duration Orbiter
IARS	Independent Air Revitalization System
NSS	Nitrogen Supply Subsystem
OGS	Oxygen Generation Subsystem
PEP	Power Extension Package
R&D	Research and Development
RLSE	Regenerative Life Support Evaluation
RO	Reverse Osmosis
SF-WES	Static Feed - Water Electrolysis Subsystem
SOC	Space Operations Center
SPE-WES	Solid Polymer Electrolyte - Water Electrolysis Subsystem
SR&T	Supporting Research and Technology
SSP	Space Station Prototype
TIMES	Thermoelectric Integrated Membrane Evaporation Subsystem
VCD	Vapor Compression Distillation
WVE	Water Vapor Electrolysis



## INTRODUCTION

Extended manned space missions, including interplanetary missions, will require regenerative life support systems. In order to place manned mission life support considerations into perspective, this paper will review previous manned space life support system technology, activities and accomplishments in NASA's current supporting research and technology (SR&T) program, the life support subsystem/system technologies required for an Enhanced Duration Orbiter (EDO) and a Space Operations Center (SOC), regenerative life support functions and technology required for manned interplanetary flight vehicles, and future development requirements.

## BACKGROUND

The life support systems technology utilized on Projects Mercury, Gemini and Apollo used expendables: liquid oxygen ( $O_2$ ) for breathing; lithium hydroxide (LiOH) canisters for carbon dioxide ( $CO_2$ ) removal; activated charcoal canisters for trace contaminant removal; stored water for drinking and washing; stored freeze-dehydrated food; urine collection and storage and/or overboard dump; and collection, stabilization/treatment and storage of solid waste. These spacecraft had an atmosphere of 5 psia  $O_2$  with no inert diluent gas.

Skylab utilized a two-gas atmosphere ( $N_2$  diluent at 1.5 psia) with a total pressure of 5 psia. Skylab also used a regenerable  $CO_2$  removal subsystem (molecular sieve/silica gel adsorption beds).


The Space Shuttle Orbiter (Space Transportation System) ushers in a new era in American manned space vehicles. Not only is the Shuttle a reusable spacecraft, but the space cabin atmosphere is maintained at Earth ambient pressure of 14.7 psia (20%  $O_2$  and 80%  $N_2$ ). The early Shuttle flights will be seven-day flights, and the life support system flight hardware will still utilize expendables.

## ADVANCED LIFE SUPPORT SYSTEMS TECHNOLOGY

Growth in space transportation capability will provide extended stay times for the Shuttle Orbiter, permanent manned facilities in low earth orbit, and ultimately, manned planetary vehicles. Regenerative life support technology is one of the rate controlling technologies for future manned space habitability including EDO, SOC and future manned planetary flight vehicles.

The use of expendables for life support, rather than regenerative techniques, for future manned missions beyond the seven-day Shuttle Orbiter, will become prohibitively expensive in terms of logistics costs. For example, the Skylab missions required the launching of 12,000 pounds of water. Regenerative systems hardware tends to be bulkier, heavier and more power consuming than short-term expendable systems. How-

ever, for some missions of only 40 person-day durations the penalties for utilizing the expendable approach will exceed any drawbacks of regenerative systems. Equivalent weight trade-off of regenerative vs total expendable (open loop) life support systems is shown in Figure 1.



### SEQUENTIAL STEPS IN LOOP CLOSURE

DEFINITION	DESCRIPTION
PARTIAL WATER RECOVERY	HUMIDITY CONDENSATE COLLECTION
WATER RECOVERY	POTABLE WATER RECOVERY AND TREATMENT FROM URINE AND WASH WATER
CO <sub>2</sub> REMOVAL (NONEXPENDABLE)	REPLACEMENT OF EXPENDABLE LIQH WITH REGENERATIVE CO <sub>2</sub> COLLECTION TECHNIQUE
O <sub>2</sub> GENERATION	GENERATION OF O <sub>2</sub> THROUGH WATER ELECTROLYSIS USING RECLAIMED WATER
N <sub>2</sub> GENERATION	GENERATION OF N <sub>2</sub> THROUGH DISSOCIATION OF HYDRAZINE
CO <sub>2</sub> REDUCTION	DECREASE IN EXPENDABLE WATER BY RECOVERING PRODUCT FROM CO <sub>2</sub> REDUCTION (SABATIERI) PROCESS

Figure 1. Regenerative vs Open Loop EC/LSS

Advanced life support systems technology, also referred to as Environmental Control/Life Support Systems (EC/LSS), consists of a number of areas including air revitalization, water reclamation, solid waste management, food service, and control/monitor instrumentation.

1. Air Revitalization System — This system integrates processes (subsystems) for:  $CO_2$  removal,  $CO_2$  reduction,  $O_2$  generation,  $N_2$  generation, humidity control, water handling, trace contaminant control, and control/monitor instrumentation for subsystem and integrated system operation.
2. Water Reclamation System — This system provides integrated processes for recovery of potable water from fuel cell water, cabin humidity condensate, wash water and urine. The system(s) must also include provisions for water quality monitoring, sterilization, and control/monitor instrumentation for subsystem and integrated system operation.
3. Solid Waste Management System — This system includes the collection, transfer, treatment and subsequent storage of treated/stabilized waste mass. Treatment processes are designed to minimize storage requirements, increasing in complexity from vacuum drying to sterilization to oxidation. Fecal water reclamation is feasible, but it is

impractical unless the solid waste treatment process can totally oxidize solid organic wastes. Fecal treatment leading to food generation is considered to be part of the Controlled Ecological Life Support System (CELSS) program and is not included in this paper.

4. Food Service System — This system involves packaging, storage and service of expendable foods for maintenance of proper human nutrition.
5. Control/Monitor Instrumentation — This technology category deals with the control, monitoring and fault diagnostic instrumentation required for reliable computer-controlled subsystem and/or system operation.

All of these technology areas, with the exception of Food Service Systems, will be discussed in this paper. This paper will emphasize the technology developments in Air Revitalization because of their relative complexity and the corresponding amount of SR&T activities completed and currently underway.

## AIR REVITALIZATION

### CO<sub>2</sub> Removal

Regenerable CO<sub>2</sub> removal techniques can utilize cyclic sorbers or continuous CO<sub>2</sub> removal processes such as an Electrochemical Depolarized Concentrator (EDC).

#### CO<sub>2</sub> Sorbers

Some solid materials such as molecular sieves or solid amines have the capability of preferentially adsorbing gases such as CO<sub>2</sub> on their surfaces. The adsorbed gases can then usually be desorbed by a combination of thermal and vacuum treatment processes. In all sorber system applications continuous adsorption capability is achieved only by using parallel adsorption beds which alternately cycle between adsorption and desorption operational modes.

Adsorption materials cannot provide a constant adsorption rate for any gas since the adsorption rate and capability of the material are dependent on the quantity of gas already adsorbed on the material. The adsorption rates attainable with a "nearly-spent" adsorption material are very low. As a result, the maintenance of low cabin partial pressures of the gas in question (e.g., pCO<sub>2</sub> = 2-3 mm Hg) necessitates frequent bed recycling and large volume beds.

The molecular sieve material used for Skylab is a good CO<sub>2</sub> adsorber, but the material also preferentially adsorbs water vapor vs CO<sub>2</sub>. Therefore, a silica gel sorber bed was required in series with the molecular sieve bed in order to preserve the CO<sub>2</sub> adsorption capability. The desorption cycle consisted of thermal treatment and overboard venting of the CO<sub>2</sub> and water vapor to space vacuum.

<sup>(1)</sup>References cited are listed at end of paper.

Solid amine CO<sub>2</sub> adsorption material is made from a spherical porous substrate coated with a non-volatile liquid amine. The substrate is a polymeric acrylic ester similar to plexiglas and the coating is a polyethylenimine with a molecular weight of 1800. The solid amine adsorbs CO<sub>2</sub> and also adsorbs water vapor.

The thermal/vacuum operational desorption mode for solid amines also involves the overboard venting of CO<sub>2</sub> and water vapor adsorbed on the bed<sup>(1)</sup>. Such venting by any sorber subsystem may be used only on missions in which overboard CO<sub>2</sub> and water vapor dumping is permissible and advantageous. The solid amine sorber subsystem does, however, offer advantages over the silica gel/molecular sieve subsystem: lower weight, lower volume, reduced cabin heat load, and lower power requirements. The solid amine material has demonstrated negligible off-gassing (i.e., ammonia) with 1300 hours of endurance test time.



The solid amine CO<sub>2</sub> adsorber subsystem has also been proposed to be used in a steam desorbed mode (212 F, 14.7 psia), so that interfacing with a spacecraft CO<sub>2</sub> reduction subsystem is possible<sup>(2)</sup>. Before this operational mode can be seriously considered the stability of the resin bed to a significant number of steam desorption cycles must be demonstrated, which has not occurred to date.

### EDC



The EDC offers significant operational advantages and weight savings over non-regenerative techniques and sorber beds, especially at low cabin CO<sub>2</sub> partial pressures (2-3 mm Hg.)<sup>(3)</sup>.

The EDC is an electrochemical method that continuously removes CO<sub>2</sub> from a flowing air stream and concentrates the CO<sub>2</sub> to a level useful for O<sub>2</sub> recovery. The CO<sub>2</sub> removal takes place in an electrochemical module consisting of a series of cells. Each cell (see Figure 2) consists of two electrodes separated by a matrix containing an aqueous carbonate electrolyte (Cs<sub>2</sub>CO<sub>3</sub>). Plates adjacent to the electrodes provide passageways for distribution of gases and electrical current. The electrochemical and chemical reactions that take place are:


Cathode:



Anode: (depolarized with H<sub>2</sub>)



Overall:






Figure 2. EDC Cell Functional Schematic

Two moles of  $\text{CO}_2$  are theoretically transferred for one mole of  $\text{O}_2$  consumed. This ratio represents the process efficiency, and 100% efficiency occurs when 2.75 g of  $\text{CO}_2$  is transferred for each g of  $\text{O}_2$  consumed. The electrical power produced by the EDC can be directly utilized by the Oxygen Generation Subsystem.

Considerable research and development work has been carried out with this concept and has resulted in increased process efficiency, demonstrated long-term performance and advanced hardware development status<sup>(4)</sup>. Extended testing with EDC modules (single cells to six-person cell stacks) has exceeded over 2,000,000 cell-hours. Recent developments in the R&D program have resulted in a one-person capacity liquid-cooled module that has demonstrated a constant  $\text{CO}_2$  removal efficiency of 91% over an inlet relative humidity range of 16-75%. In addition, this advanced module has demonstrated a static pressure differential capability of 60 psid, which is extremely important in interfacing with the Sabatier  $\text{CO}_2$  reduction subsystem.

A three-person capacity EDC subsystem has been developed for the Regenerative Life Support Evaluation (RLSE) program (see Figure 3)<sup>(5)</sup>. The EDC module in this subsystem is air-cooled, has demonstrated in excess of 72%  $\text{CO}_2$  removal efficiency at 85% inlet relative humidity, and the  $\text{CO}_2$  removal efficiency was increased by approximately 12% by operating the module at a 60% inlet relative humidity.

#### $\text{CO}_2$ Reduction

There are two principal methods for combining  $\text{CO}_2$  with  $\text{H}_2$  to form water for the eventual recovery of  $\text{O}_2$ . These are the Sabatier and Bosch processes. The factors that govern process selection deal with the availability of  $\text{H}_2$  and the requirement for no overboard dumping of gases.





Figure 3. Three-Person RLSE  $\text{CO}_2$  Removal Subsystem

#### Sabatier Process<sup>(6)</sup>

This CO<sub>2</sub> reduction process is ideally suited for an air revitalization system that uses a hydrazine-based N<sub>2</sub> generation subsystem. CO<sub>2</sub> and H<sub>2</sub> from the EDC enter the Sabatier reactor (see Figure 4) and are converted to methane (CH<sub>4</sub>) and water per the following reaction:



The reaction occurs around 700 F and is aided by a catalyst. The water is condensed in a liquid cooled porous plaque condenser/separator. The exhaust gases, primarily CH<sub>4</sub>, are vented overboard. Single pass high conversion efficiency (98-99%) subsystems have been developed.




Figure 4. Sabatier Reactor

#### Bosch Process<sup>(7)</sup>

This CO<sub>2</sub> reduction process reduces CO<sub>2</sub> and H<sub>2</sub> to solid carbon (C) and water. The reaction occurs in the range of 980 - 1340 F in the presence of an iron (Fe) catalyst. The overall reaction is:



In practice, single pass efficiencies through the Bosch reactor are less than 10%. Complete conversion is obtained by recycling the process gases with continuous deposition of carbon and removal of water vapor. The recycled gas mixture contains CO<sub>2</sub>, carbon monoxide (CO), water vapor and CH<sub>4</sub>. The carbon remains in the reactor and is collected in expendable cartridges. The Bosch development efforts have been limited, and a laboratory breadboard subsystem is shown in Figure 5.

In terms of equivalent weight, the Sabatier and Bosch CO<sub>2</sub> reduction processes trade off as shown in Figure 6 for an 8-person capacity SOC Application. The Bosch CO<sub>2</sub> reduction process does not trade off favorably with a Sabatier oriented ARS that uses a hydrazine-based N<sub>2</sub> generation subsystem. However, as cabin atmosphere leakage is reduced (less H<sub>2</sub> available for CO<sub>2</sub> reduction) and/or overboard venting of gases becomes detrimental to a mission, the Bosch process becomes attractive.

#### Oxygen Generation

Oxygen generation in a regenerative air revitalization system involves electrolyzing water recovered from on-




Figure 5. Bosch Laboratory Breadboard Subsystem




Figure 6. Comparison of CO<sub>2</sub> Reduction Subsystem Concepts

board waste water sources, cabin humidity condensate and from the CO<sub>2</sub> reduction process. In the electrolysis subsystems the electrolyte must be maintained between the electrodes, and the water that is electrolyzed must be replenished. This is not a simple task in zero gravity.

Two liquid-feed water electrolysis concepts offer the potential for minimizing and containing bulk electrolyte and maximizing the subsequent reliability and safety of the O<sub>2</sub> Generation Subsystem (OGS). These two concepts are the Solid Polymer Electrolyte (SPE-WES) and Static Feed (SF-WES) Water Electrolysis Subsystems.

#### SPE-WES<sup>(8)</sup>

The SPE-WES uses a perfluorinated sulfonic acid polymer membrane electrolyte in the electrolysis cells (see Figure 7). The electrolyte membrane is in contact





Figure 7. SPE-WES Cell Functional Schematic

with two electrodes and must be kept moist. In the case represented in Figure 7, the cathode cavity is flooded with liquid water. The electrochemical reactions that occur are:

Cathode:



Anode:



A three-person capacity SPE-WES OGS that includes a twelve-cell electrolysis module (see Figure 8), has been developed for the RLSE program. This subsystem has demonstrated voltages of approximately





Figure 8. RLSE SPE-WES Module

1.6 volts (V) at operating conditions of 180 F and a current density of 150 Amps per square foot (ASF). This subsystem offers advantages over other acid electrolyte water electrolysis technologies (low voltages and no free electrolyte in the subsystem), but it does require subsystem support components (and complexities) to deal with gas/liquid separation and removal of dissolved gases in the condensed water exhaust.

#### SF-WES<sup>(9)</sup>

This concept utilizes static-feed water addition to an alkaline electrolyte (see Figure 9). The water is fed as vapor through the H<sub>2</sub> cavity to the electrolysis site (cathode/matrix/anode composite assembly). The reactions occurring in the alkaline electrolysis cells are:

Cathode:



Anode:






Figure 9. SF-WES Cell Functional Schematic

Initially the water feed cavity, the water feed matrix and the cell matrix (with electrodes) contain an aqueous solution of potassium hydroxide (KOH) electrolyte at equal concentrations. When power is applied to the electrodes, water from the cell electrolyte is decomposed and the cell electrolyte concentration increases, with a resultant decrease in electrolyte vapor pressure. The vapor pressure of the electrolyte in the feed matrix causes water vapor to diffuse through the  $H_2$  cavity and to be absorbed in the cell electrolyte matrix. This process establishes a new equilibrium based on the water requirements for electrolysis and humidification of the product gases and continues as long as electrical power is applied to the cell electrodes. When electrical power is discontinued, water vapor will continue to diffuse across the  $H_2$  cavity until the electrolyte concentration in the cell matrix is equal to that in the water feed matrix and the water feed compartment.

The static-feed water addition concept is simple, reliable and minimizes subsystem components and controls. In addition, the use of alkaline electrolyte allows low cell voltages, which result in low power penalties. Long duration testing with the SF-WES and electrochemical modules has demonstrated voltages of 1.45-1.49V at operating conditions of 180 F and a current density of 150 ASF.

A self-contained one-person capacity SF-WES has been developed and is currently undergoing tests (see Figure 10).

#### Nitrogen Generation

With the advent of a two-gas space cabin atmosphere using nitrogen ( $N_2$ ) as the diluent, storage and supply of  $N_2$  for cabin leakage make-up is essential. The preferred method of providing  $N_2$  make-up is to store the  $N_2$  as hydrazine ( $N_2H_4$ ), to catalytically dissociate




Figure 10. One-Person SF-WES OGS

the  $N_2H_4$  into  $N_2$  and  $H_2$ , and to separate the  $N_2$  and  $H_2$  gases<sup>(10)</sup>. This concept is especially attractive if the Sabatier  $CO_2$  reduction process is utilized (see Figure 6).

This Nitrogen Supply Subsystem (NSS) has a module containing catalytic dissociation and Pd/Ag passive gas separation stages. Dissociation of  $N_2H_4$  (at 1350 F, 250 psia) involves the equilibria in the following reactions:

- (1)  $N_2H_4 = \frac{1}{2}N_2 + \frac{1}{2}NH_3$
- (2)  $\frac{1}{2}NH_3 = \frac{1}{2}N_2 + 2H_2$

A staging concept has been developed in order to separate the  $H_2$  from the product  $N_2$  and to reduce the  $NH_3$  concentration in the product  $N_2$  gas. A schematic demonstrating the staging concept is shown in Figure 11. All of the  $N_2H_4$  and some  $NH_3$  are catalytically dissociated in the first stage. The  $N_2$ ,  $H_2$  and non-dissociated  $NH_3$  enter the first  $H_2$  separation stage where most (90%) of the  $H_2$  is removed and collected for use in the  $CO_2$  reduction subsystem. The  $N_2$  product gas stream then passes successively through




Figure 11. Nitrogen Generation Subsystem Schematic

three additional dissociation/separation stages. This alternate dissociation/separation staging and subsequent venting of  $H_2$  to vacuum (10%) is necessary to favor further  $NH_3$  dissociation and thus to lower the  $H_2$  and  $NH_3$  concentrations in the product  $N_2$ . A nitrogen generation module that includes these stages is shown in Figure 12. Testing with this NSS hardware has demonstrated that the product  $N_2$  stream contains less than 10 ppm  $NH_3$  and 0.5%  $H_2$ .

Nitrogen generation using hydrazine should be considered as both a spacecraft resource or function and an air revitalization function. The hydrazine based  $N_2$  generation approach utilizes expendable  $N_2H_4$  (11 lb/day) to generate  $N_2$  (9.6 lb/day) and provides  $H_2$  (1.23 lb/day) for air revitalization. It is assumed that the NSS will be located external to the manned space cabin with bulkhead feedthroughs for product  $N_2$  and  $H_2$ . This subsystem isolation not only contributes to safety considerations, but passive thermal control of the  $N_2$  generation module and the use of space vacuum for byproduct  $H_2$  would also be possible.

#### Trace Contaminant Control

Contaminants in a manned spacecraft emanate from both the crew and the equipment. As mission durations, vehicle sizes, crew sizes, and vehicle payload and experiment complexities increase and as spacecraft leak rates decrease, there will be a concomitant increase in concentration and variety of potential contaminants. In addition, the increased crew exposure time (with longer mission durations) will dictate a reduction in the allowable contaminant concentrations.

A spacecraft contaminant control subsystem that deals with an expected wide variety of contaminants will involve several elements including catalytic oxidation, charcoal adsorbers and chemical absorbers. No single contaminant control process is suitable for all contaminants. Some, such as  $CO$ ,  $CH_4$  and  $H_2$ , can be catalytically oxidized to  $CO_2$  and water relatively easy. Some gases will poison oxidation catalysts and must be removed by pre-sorbent beds to protect the




Figure 12. Advanced  $N_2$  Generation Module



catalyst. Some gases, when oxidized, form extremely toxic substances (i.e., fluorocarbons form carbonyl fluoride) that must be removed by post-sorbent beds, and some organic materials cannot be oxidized efficiently and must be adsorbed.

A limited amount of work has been performed on adsorber/absorber characterization and on catalytic oxidation schemes. Some development efforts have also been directed toward regeneration of activated charcoal. These contaminant control R&D efforts have been very sporadic, and the technology has not progressed sufficiently to be commensurate with other regenerative air revitalization processes.

#### Air Revitalization System Integration

As mentioned previously, an Air Revitalization System (ARS) requires the individual subsystem technologies listed in Figure 13. An engineering breadboard integrated air revitalization system (ARX-1), including all ARS subsystem functions with the exception of contaminant control has been fabricated (see Figure 14).




Figure 13. Air Revitalization System Block Diagram

Preliminary testing of the ARX-1 was conducted for a period of 120 days and included checkout, shakedown and endurance testing. Almost 500 hours of integrated operation at nominal steady-state conditions corresponding to a one person level were achieved. Additional testing, currently underway, will examine subsystem interactions by varying parameters such as CO<sub>2</sub> generation rate, humidity load, coolant temperature and power availability. One goal of this testing is to demonstrate the readiness of this integrated air revitalization system for prototype development and flight demonstration.

#### Control/Monitor Instrumentation

A major development goal of the advanced life support program is long duration operation with minimal servicing and maintenance by the crew and the avoidance




Figure 14. ARX-1

of excessive crew training requirements. An integrated air revitalization system, for example, contains a range of electrochemical, chemical, mechanical and electrical components/subsystems; and automatic process control and monitoring are an absolute necessity.

This computer-based Control/Monitor Instrumentation (C/M I) must provide: monitoring capability; control functions including subsystem/system mode transitions; and fault diagnostics including fault prediction, fault detection, fault isolation, fault correction, and fault correction instructions. In addition, the C/M I hardware and software must be "operator error-proof."

Advanced life support C/M I developments have progressed along with current life support technology advancements. The early stages of C/M I development provided for manual or automatic operation. C/M I development has progressed through the hard-wired primary and emergency controller stage to a programmable mini-computer with a customized keyboard for operator commands, a Cathode Ray Tube (CRT) for operator/system messages, a system status panel, a system control panel, and an actuator override panel (see Figure 15).

The current stage of development: C/M I is dedicated to the control and monitoring of engineering breadboard systems, such as the ARX-1 (see Figure 16). Test programs with advanced life support developmental hardware involve off-design, parametric and life testing. Therefore, C/M I components such as an actuator override panel are included. Advanced life support flight hardware will, of course, be dedicated to steady state operation; and the same is true for the






Figure 15. C/M I Control Panel



Figure 16. ARX-1 C/M I

C/M I. Therefore, flight C/M I hardware will become considerably smaller and will utilize dedicated microprocessors. A flight oriented C/M I design concept for an EDC subsystem is shown in Figure 17.




Figure 17. Flight-Oriented C/M I For CO<sub>2</sub> Removal Subsystem

### Independent Air Revitalization System

NASA has investigated partial air revitalization systems for intermediate manned space applications. One of these is an Independent Air Revitalization System (IARS), which is perceived as a "semi-portable" ARS. The IARS includes a water vapor electrolysis (WVE) subsystem and an EDC subsystem. The IARS provides simultaneous CO<sub>2</sub> removal, O<sub>2</sub> generation and partial humidity control<sup>(11)</sup>. The IARS can operate as a separate system, or it can operate as a back-up to a central ARS, described previously<sup>14</sup>. A schematic of the IARS is shown in Figure 18.




Figure 18. IARS Schematic

### Water Vapor Electrolysis Subsystem

The WVE subsystem, which uses a hygroscopic electrolyte (H<sub>2</sub>SO<sub>4</sub>), absorbs water vapor from the cabin air stream and generates O<sub>2</sub> and H<sub>2</sub> per the following reactions:

Anode:



Cathode:



A functional WVE cell schematic is shown in Figure 19. Cabin air moisture is absorbed at the anode/electrolyte interface and the O<sub>2</sub> generated by electrolysis is released into the cabin air flowing through the anode compartment. Hydrogen (H<sub>2</sub>) is generated at the cathode and is utilized at the anode of the EDC subsystem.

### EDC Subsystem

The EDC subsystem technology used in the IARS has already been described in an earlier section of this paper; and the subsystem electrochemical module hardware is similar to the EDC RLSE hardware shown in Figure 3.




Figure 19. WVE Cell Functional Schematic

### IARS Development Unit

A functional IARS development unit has been developed for the NASA RLSE program (see Figure 20), and a ninety (90) day characterization/endurance test program has been successfully completed with this three-person capacity IARS. Characterization testing included measuring the effect of cabin air pCO<sub>2</sub> and moisture levels on electrochemical cell performance (EDC and WVE cell voltages) and on CO<sub>2</sub> removal efficiency. For nominal operating conditions the EDC voltage averaged 0.4 V/cell at 20 ASF while the WVE voltage was 1.70 V/cell at 42 ASF. The CO<sub>2</sub> removal efficiency averaged 80% (2.2 lb. of CO<sub>2</sub> removed per pound of O<sub>2</sub> consumed). Additional testing of the above unit is scheduled.

### WATER RECLAMATION

Water reclamation in a manned spacecraft is of equal importance with air revitalization. Water reclamation involves processes to reclaim water from waste water sources such as fuel cell water, cabin humidity condensate, wash water and urine. These waste water sources represent increasing degrees of contamination and will generally require reclamation processes of increasing complexity. Various processes, including multi-filtration, phase change and membrane processes, have been investigated for these applications; and limited subsystem and component development efforts have been undertaken to date.

Recovery of fecal water is considered to be difficult but feasible. Fecal water reclamation will be discussed briefly in the solid waste treatment section of this paper.




Figure 20. IARS RLSE Development Hardware

#### Multi-Filtration

Multi-filtration processes can be used for treating waste water containing contaminants in low concentrations (e.g., fuel cell water, cabin humidity condensate, and possibly wash water). Typically, a multi-filtration process will include a particulate/bacterial filter, an activated charcoal canister, an anion exchange resin bed, and a cation exchange resin bed<sup>(12)</sup>. Very little development work has been performed in this area, and this process technology will not be discussed in further detail in this paper.

#### Phase Change Processes

Phase change processes that have been considered for spacecraft water reclamation from waste water sources such as urine include air evaporation, vapor compression distillation, vapor diffusion/evaporation, and a relatively new concept that uses vapor phase ammonia removal. In a distillation/condensation process, the goal is to retain the solutes (in a stabilized form) in the evaporator and to reclaim the energy involved with the vaporization process. Three of these concepts will be discussed in the following sections of this paper.

#### Vapor Compression Distillation

A Vapor Compression Distillation (VCD) process schematic is shown in Figure 21<sup>(13)</sup>. The recovery of latent heat in the VCD process is accomplished by compressing the vapor to raise its saturation temperature and then condensing the vapor on a surface which is in thermal contact with the evaporator. The resultant




Figure 21. Vapor Compression Distillation Schematic

heat flux from the condenser to the evaporator is sufficient to evaporate an equal mass of water. Thus the latent heat of condensation is recovered for the evaporation process; and the only energy required by the process is that necessary to compress the vapor and to overcome the thermal and mechanical inefficiencies.

The VCD process occurs in a 70 to 95 F temperature range by maintaining a nominal condenser pressure of 0.70 psia. The evaporator, condenser and condensate collector are rotated at approximately 220 rpm to provide zero-gravity phase separation. The VCD components are sized to recover 96% of the water from the waste water feed by concentrating this feed stock to 50% solids. The VCD process requires pretreatment chemicals to complex with urea and to provide anti-foaming in the evaporator. The product water from this subsystem requires post-treatment in charcoal and ion exchange beds in order to remove trace amounts of organic materials and dissolved  $\text{NH}_3$ , and the product water also requires the addition of small amounts of biocide to control bacterial growth.

Testing of two six-person capacity preprototype VCD units (one shown in Figure 22) has been completed with over 1000 hours of test time accumulated on each unit. Pretreated urine has been concentrated to 50% solids with water quality at projected levels (pH 5.0, conductivity of 16  $\mu\text{mho/cm}$  nominal). Specific energies, expressed in watt-hours per pound of water recovered (the key VCD performance parameter), averaged from 45 to 55 W-h/lb. Additional testing of existing VCD units plus the development of an advanced development unit are underway.




Figure 22. VCD Water Recovery Subsystem

#### Thermoelectric Integrated Membrane Evaporation Subsystem

A schematic of the Thermoelectric Integrated Membrane Evaporation Subsystem (TIMES) is shown in Figure 23. This concept<sup>(14)</sup> recovers the latent heat of condensation and transfers this heat to the evaporator




Figure 23. Thermoelectric Integrated Membrane  
Evaporation Subsystem  
Functional Schematic

via a thermoelectric heat pump. Waste water (urine), pretreated with a sulfuric acid/chromium trioxide solution, is heated to approximately 150 F in the thermoelectric heat exchanger, and the heated waste water is pumped through a hollow fiber polysulfone membrane evaporator module. The exterior of the module tubes is exposed to reduced pressure, and water evaporates from the tube surface and is condensed on a chilled porous plate surface in thermal contact with the cold junction surfaces of the thermoelectric heat exchanger. The heat of vaporization is provided by recycling the waste water to the heat exchanger where it is reheated and recycled. The product water from this subsystem concept requires the same post-treatment steps as those used by the VCD process. Typically the solids concentration in the recycle loop gradually increases until 95% of the original water is removed and the solids concentration is approximately 40%. At this point, the recycle tank containing the concentrated waste water sludge is removed for storage and a replacement tank is installed. The energy requirements for this process are primarily for the thermoelectric heat pump and for the subsystem pumps (recycle, cooling, and condensate).

A photograph of TIMES development hardware is shown in Figure 24. This subsystem has undergone limited testing and an analysis of subsystem performance cannot be made at this time.

#### Vapor Phase Catalytic Ammonia Removal

Ultimately, a water reclamation process that requires neither pretreatment nor post-treatment expendable chemicals would be desirable for manned spacecraft use. The vapor phase catalytic ammonia removal process offers this potential advantage<sup>(15)</sup>. A schematic of the process is shown in Figure 25.

Waste water (urine) is vaporized, and the vapor stream is mixed with air or  $\text{O}_2$  and passes through an oxidation reactor. Ammonia, urea and light organics are oxidized in this reactor. Water is condensed and separated, and the vapor phase then passes through a nitrous oxide ( $\text{N}_2\text{O}$ ) decomposition reactor which converts the  $\text{N}_2\text{O}$  to  $\text{N}_2$  and  $\text{O}_2$ . Studies with "laboratory-




Figure 26. Solid Waste Management System/Space Shuttle

### MANNED TESTING AND LIFE SUPPORT INTEGRATION

The majority of NASA's advanced life support R&D efforts have been directed at subsystem technologies or components, but there have also been efforts to integrate subsystem technologies and to perform manned chamber tests with the most advanced life support hardware available. These efforts were not directed particularly toward subsystem integration optimization, but they were directed toward manned chamber/life support subsystem hardware tests. The early manned chamber tests were performed successively at 30-, 60-, and 90-day durations<sup>(18, 19, 20)</sup> under the sponsorship of Langley Research Center.

Prototype integrated life support subsystem hardware has also been developed for "integrated systems" programs such as the Space Station Prototype (SSP) program (1971-1975)<sup>(21)</sup> and the Regenerative Life Support Evaluation (RLSE) program (1975-present) under the sponsorship of Johnson Space Center<sup>(22)</sup>. This hardware has included: EDC CO<sub>2</sub> concentration, Sabatier CO<sub>2</sub> reduction, SPE water electrolysis O<sub>2</sub> generation, Independent Air Revitalization System (EDC CO<sub>2</sub> concentration and WVE O<sub>2</sub> generation), VCD urine water recovery subsystem, dynamic membrane wash water recovery subsystem, subsystem computerized C/M I and various components and sensors. The manned chamber tests and the testing of the SSP and RLSE hardware have been limited, but the subsystem SR&T program has benefited from both the hardware development phases and the test results.

### ENHANCED DURATION ORBITER

As mentioned previously, the early Shuttle Orbiter flights will be limited to seven-day missions. In order to maximize the effective use of this Space Transportation System, Extended Duration Orbiter (EDO) missions of 30, 60 and 90 days are under active consideration. Such extended Orbiter missions will make it mandatory to reduce life support and auxiliary power (fuel cell) expendables. Significant weight savings for these missions can be realized by replacing the

expendable lithium hydroxide canisters with a regenerable/continuous CO<sub>2</sub> removal subsystem. For longer missions, an IARS may also become applicable.

It should also be emphasized that if auxiliary power supplies such as the Power Extension Package (PEP) or a full power module (25 kW) are substituted for the Orbiter fuel cells, large O<sub>2</sub> and H<sub>2</sub> expendable requirements are eliminated; but large quantities of relatively clean fuel cell water will not be available for reclamation and subsequent use. Water reclamation from humidity condensate and wash water would then become attractive and provide weight savings.

### SPACE OPERATIONS CENTER

The Space Operations Center (SOC) has been conceived as a modular space station serviced by the Space Shuttle. The SOC is a low earth orbit permanent manned facility with a 14.7 psia mixed gas atmosphere. A Shuttle resupply interval of 90 days is planned. The nominal volume for SOC is 22,000 ft<sup>3</sup>, and the vehicle has been planned for a crew size of eight persons<sup>(23)</sup>.

The SOC life support system is regenerative in order to minimize crew expendables. The life support system functional schematic and mass balances are shown in Figure 27. The baseline SOC life support system includes the following subsystems:

- (1) liquid water electrolysis O<sub>2</sub> generation (solid polymer or static-feed)
- (2) VCD urine water recovery
- (3) hyperfiltration wash water recovery
- (4) condensing heat exchanger humidity control
- (5) EDC CO<sub>2</sub> control
- (6) Sabatier CO<sub>2</sub> reduction
- (7) hydrazine dissociation N<sub>2</sub> generation

The SOC life support system will regenerate all metabolic water and O<sub>2</sub> requirements. The only crew expendable requirement is wet food. Resupply of N<sub>2</sub>H<sub>4</sub> will be required for the N<sub>2</sub> generation subsystem and subsequent cabin leakage make-up. Some expendables will also be required for filters, chemical beds, urine pretreatment chemicals, etc.

The SOC life support system configuration is planned so that reclaimed water from urine will be utilized primarily for O<sub>2</sub> production. The system will provide drinking water reclaimed from cabin humidity condensate, water vapor from the CO<sub>2</sub> concentrating process and water from the CO<sub>2</sub> reduction process. The mass balance demonstrates that surplus reclaimed water will be available beyond that required by the crew and the life support processes.

It should be emphasized that the SOC program is currently in the early definition phases, and it is possible that other life support subsystem technologies will replace the baseline subsystems in the future. The




Figure 27. Space Operations Center Life Support System Functional Schematic and Mass Balance

controlling factors governing subsystem selection are, of course, the actual SOC project schedule and the concurrent subsystem development status.

#### MANNED INTERPLANETARY LIFE SUPPORT SYSTEMS

The life support functions required for manned interplanetary flight vehicles are essentially the same as those provided for Earth orbital space stations: regenerative air revitalization; water reclamation from humidity condensate, wash water and urine; and advanced solid waste management techniques.

It is anticipated that upgrading and possible substitution of subsystem technology will occur in order to increase performance capability and reliability. Subsystem selection and system integration will be dependent on the significant vehicle trade-offs that are relevant at the time of selection.

A Controlled Ecological Life Support System (CELSS) that includes food production is considered to be non-competitive for a manned planetary flight vehicle, but a CELSS is applicable for space settlements (i.e., lunar, Mars, L<sub>5</sub>, etc.).

#### FUTURE DEVELOPMENT REQUIREMENTS

The ultimate goal of NASA's advanced life support Research and Development (R&D) program is to

develop the technology base for future manned space requirements. This program has been responsible for the successful developments that have been discussed in the advanced technology section of this paper.

It should be emphasized, however, that the current technology data base is not adequate for space mission planners. A significant amount of additional development activity in systems, subsystems and components must be accomplished. It should also be emphasized that the advanced life support systems technology developed to date deals with chemical processes that require proper gas/liquid separation in reduced gravity. However, none of the regenerative systems/subsystems/components described in the advanced technology section of this paper have been tested in reduced or zero gravity. Long term tests on spacecraft, such as Spacelab, are absolutely essential to the data base generation and to mission planners. Short term (approximately 30 sec) aircraft parabolic flight tests will not suffice.

NASA's advanced life support R&D program must address these issues in order to guarantee an adequate technology base for future manned space missions. An adequate technology base will not guarantee that future manned missions such as SOC or interplanetary flights will be carried out. The failure to develop the technology base *will guarantee* either that "we aren't going", or that future manned missions will require concurrent program and project hardware developments, which have historically resulted in large cost overruns (e.g., Shuttle).



In order to develop an adequate technology base, it is essential that additional R&D efforts at the following technology levels be carried out:

- (1) Flight technology demonstrations
- (2) System developments
- (3) Subsystem developments
- (4) Components/parts developments
- (5) Engineering analysis/applications, system and trade studies
- (6) Basic and applied research (scientific and engineering data)

These efforts are essential for air revitalization, water reclamation and solid waste management.

It is obvious from the advanced technology development section of this paper that the development status for air revitalization, water reclamation and solid waste management systems differs significantly, with air revitalization system/subsystem technology having the highest. A ten-year development plan that delineates the currently obvious additional technology level requirements for air revitalization is shown in Figure 28. This listing is not all-inclusive, but




Figure 28. ARS Development Schedule According To Technology Levels

ORIGINAL PAGE IS  
OF POOR QUALITY

it clearly demonstrates the magnitude of R&D activity that must be performed in order to establish the required air revitalization technology base. One of the Space flight technology demonstrations identified in Figure 28 is a Sabatier based Air Revitalization System (ARS). A mock-up of this ARS flight demonstrator is shown in Figure 29.

Program planning activities are required in order to establish similar ten-year program requirements for water reclamation and solid waste management. The identified technology data gaps must, of course be filled if advanced water reclamation and solid waste management systems technology is to be selected and baselined for future manned space flight hardware.





Figure 29. ARS-Space Flight Demonstrator Mock-Up

## REFERENCES

- (1) A Regenerable CO<sub>2</sub> and Humidity Control System for Shuttle, A.M. Boehm, ASME Publication Number 76-ENAS-60, July 1976.
- (2) A Regenerative Life Support System for Space Operations Center (SOC), H.F. Brose, ASME Publication Number 81-ENAS-12, July 1981.
- (3) EDC-A Regenerable CO<sub>2</sub> Removal Subsystem for an Enhanced Capability Orbiter, R.D. Marshall, F.H. Schubert, and P.Y. Yang, ASME Publication Number 79-ENAS-34, July 1979.
- (4) Regenerative CO<sub>2</sub> Collection for Spacecraft Application, N. Lance, Jr., and F.H. Schubert, ASME Publication Number 81-ENAS-28, July 1981.
- (5) Development of a Three-man Prototype CO<sub>2</sub> Collection Subsystem for Spacecraft Application, F.H. Schubert, R.D. Marshall, R.A. Wynveen, and P.D. Quattrone, ASME Publication Number 77-ENAS-19, July 1977.
- (6) Sabatier Reactor Design Verification Testing, R.J. Cusick, ASME Publication Number 74-ENAS-58, July 1974.
- (7) Bosch: An Alternate CO<sub>2</sub> Reduction Technology, D.B. Heppner, T.M. Hallick, D.C. Clark, and P.D. Quattrone, ASME Publication Number 79-ENAS-22, July 1979.
- (8) Development Status of a Preprototype Water Electrolysis Subsystem, R.B. Martin and A.C. Erickson, ASME Publication Number 81-ENAS-9, July 1981.
- (9) Oxygen Generation Subsystem for Spacecraft, F.H. Schubert, K.A. Burke, and P.D. Quattrone, ASME Publication Number 81-ENAS-40, July 1981.
- (10) Nitrogen Supply System Based on Hydrazine Dissociation, D.B. Heppner and P.D. Quattrone, ASME Publication Number 81-ENAS-27, July 1981.
- (11) Development of a Three-man Preprototype Independent Air Revitalization Subsystem, R.D. Marshall, R.R. Woods, T.M. Hallick, and F.H. Schubert, ASME Publication Number 77-ENAS-31, July 1977.
- (12) Space Vehicle Water Reclamation Systems, D.C. Popma and V.C. Collins, AIChE Preprint Number 54A, February 1965.
- (13) Preprototype Vapor Compression Distillation Subsystem Development, C.D. Thompson and G.S. Ellis, ASME Publication Number 81-ENAS-25, July 1981.
- (14) Development of a Preprototype Thermoelectric Integrated Membrane Evaporation Subsystem for Water Recovery, H.E. Winkler and G.J. Roebelin, Jr., ASME Publication Number 80-ENAS-46, July 1980.
- (15) Removal of Ammonia from Urine Vapor by a Dual-Catalyst System, P. Budininkas, ASME Publication Number 77-ENAS-48, July 1977.
- (16) Dynamic Membrane Hyperfiltration Wash Water Recovery, B.M. Greenough and R.L. Goldsmith, ASME Publication Number 77-ENAS-21, July 1977.
- (17) Waste Management for Shuttle, R.W. Murray, J.K. Mangialardi, O.T. Stoll, and G.E. Bazell, ASME Publication Number 77-ENAS-26, July 1977.
- (18) 60-Day Manned Test of a Regenerative Life Support System with Oxygen and Water Recovery, Part I — Engineering Test Results, McDonnell Douglas Astronautics Co., NASA Contract NASw-1612, NASA-CR-98500, December 1968.
- (19) Test Report — Test Results — Operational Ninety-day Manned Test of a Regenerative Life Support System, McDonnell Douglas Astronautics Co., NASA Contract NAS-1-8997, NASA-CR-111881, May 1971.
- (20) An Overview of a 90-Day Manned Test in a Space Station Simulator, J.K. Jackson, J.R. Wamsley, and J.S. Seeman, ASME Publication Number 71-AV-38, July 1971.
- (21) Space Station Prototype Environmental/Thermal Control and Life System — A Current Overview, N.C. Willis, Jr. and J.M. Neel, ASME Publication Number 72-ENAS-35, July 1972.
- (22) Regenerative Life Support Evaluation, G.N. Kleiner and C.D. Thompson, ASME Publication Number 77-ENAS-35, July 1977.
- (23) Space Operations Center — A Concept Analysis — Volume II, JSC Document Number 16277, November 1979.




# SPACE SHUTTLE AIR REVITALIZATION SYSTEM



QUATRONE FIGURE 1  
SPACE SHUTTLE AIR REVITALIZATION  
SYSTEM

REGENERATIVE vs OPEN LOOP ECLSS  
TRADE-OFFZ


REGENERATIVE vs OPEN LOOP EC/LSS



SEQUENTIAL STEPS IN LOOP CLOSURE


DEFINITION	DESCRIPTION
PARTIAL WATER RECOVERY	HUMIDITY CONDENSATE COLLECTION
WATER RECOVERY	POTABLE WATER RECOVERY AND TREATMENT FROM URINE AND WASH WATER
CO <sub>2</sub> REMOVAL (NONEXPENDABLE)	REPLACEMENT OF EXPENDABLE LiOH WITH REGENERATIVE CO <sub>2</sub> COLLECTION TECHNIQUE
O <sub>2</sub> GENERATION	GENERATION OF O <sub>2</sub> THROUGH WATER ELECTROLYSIS USING RECLAIMED WATER
N <sub>2</sub> GENERATION	GENERATION OF N <sub>2</sub> THROUGH DISSOCIATION OF HYDRAZINE
CO <sub>2</sub> REDUCTION	DECREASE IN EXPENDABLE WATER BY RECOVERING PRODUCT FROM CO <sub>2</sub> REDUCTION (SABATIER) PROCESS

# REGENERATIVE AIR REVITALIZATION SYSTEM




QUATTRONE  
FIGURE 3  
REGENERATIVE AIR REVITALIZATION  
SYSTEM SCHEMATIC

# REGENERATIVE AIR REVITALIZATION SYSTEM



QUATRONE  
FIGURE 4  
REGENERATIVE AIR REVITALIZATION  
SYSTEM SCHEMATIC

# REGENERATIVE AIR REVITALIZATION SYSTEM




QUATRONE  
FIGURE 5  
REGENERATIVE AIR VITALIZATION  
SYSTEM SCHEMATIC, NUMBER 2.

ORIGINAL PAGE IS  
OF POOR QUALITY

QUATTRONE

FIGURE 6

EXPERIMENTAL AIR REVITALIZATION  
SYSTEM




QUATTRONE

FIGURE 7

AIR REVITALIZATION SYSTEM  
SCHEMATIC

2-105

## AIR REVITALIZATION SYSTEM

ORIGINAL PAGE IS  
OF POOR QUALITY


ORIGINAL PAGE IS  
OF POOR QUALITY

QUATTRONE

FIGURE 8

ELECTROCHEMICAL DEPOLARIZED CARBON  
DIOXIDE CONCENTRATOR CELL  
SCHEMATIC

### EDC CELL FUNCTIONAL SCHEMATIC






ORIGINAL PAGE IS  
OF POOR QUALITY.

QUATTRONE

FIGURE 9

ELECTROCHEMICAL DEPOLARIZED CARBON  
DIOXIDE CONCENTRATOR SUBSYSTEM




ORIGINAL PAGE IS  
OF POOR QUALITY

QUATTRONE

FIGURE 10


SOLID AMINE-WATER DESORBED CARBON  
DIOXIDE CONCENTRATOR SUBSYSTEM



QUATTRONE

FIGURE 11


SABATIER CARBON DIOXIDE  
REDUCTION SUBSYSTEM




2-109

ORIGINAL PAGE IS  
OF POOR QUALITY

QUATRONE  
BOSCH CARBON DIOXIDE REDUCTION  
SUBSYSTEM  
FIGURE 12



# COMPARISON OF CO<sub>2</sub> REDUCTION SUBSYSTEM CONCEPTS



QUATRONE  
SABATIER/BOSCH TRADE-OFF COMPARISON  
FIGURE 13

ORIGINAL PAGE IS  
OF POOR QUALITY


ORIGINAL PAGE IS  
OF POOR QUALITY

QUATRONE

FIGURE 14


WATER VAPOR ELECTROLYSIS CELL  
SCHEMATIC

### WVE CELL FUNCTIONAL SCHEMATIC




ORIGINAL PAGE IS  
OF POOR QUALITY

QUATRONE      FIGURE 15  
WATER VAPOR ELECTROLYSIS SUBSYSTEM





## IARS RLSE DEVELOPMENT HARDWARE




QUATRONE  
INDEPENDENT AIR REVITALIZATION SYSTEM  
FIGURE 16

ORIGINAL PAGE 15  
OF POOR QUALITY




# SF-WES CELL FUNCTIONAL SCHEMATIC



QUATRONE  
FIGURE 17  
STATIC FEED WATER ELECTROLYSIS CELL  
SCHEMATIC

ORIGINAL PAGE IS  
OF POOR QUALITY

QUATRONE  
STATIC FEED WATER ELECTROLYSIS  
SUBSYSTEM  
FIGURE 18




QUATTRONE

FIGURE 19

SOLID POLYMER ELECTROLYTE WATER  
ELECTROLYSIS CELL SCHEMATIC

**SPE-WES CELL FUNCTIONAL SCHEMATIC**




## RLSE SPE-WES MODULE


QUATTRONE

FIGURE 20

SOLID POLYMER ELECTROLYTE WATER  
ELECTROLYSIS MODULE





### AIR REVITALIZATION SYSTEM SCHEMATIC



ORIGINAL PAGE IS  
OF POOR QUALITY


# NITROGEN GENERATION

(1000 °K; 200 PSIA)




NITROGEN SUPPLY SUBSYSTEM STAGING  
SCHEMATIC

## NITROGEN GENERATION SUBSYSTEM SCHEMATIC



## ADVANCED N<sub>2</sub> GENERATION MODULE




QUATRONE  
NITROGEN SUPPLY SUBSYSTEM MODULE  
FIGURE 24

ORIGINAL PAGE IS  
OF POOR QUALITY




# VAPOR COMPRESSION DISTILLATION SCHEMATIC




QUATRONE  
FIGURE 25  
VAPOR COMPRESSION DISTILLATION SUB-  
SYSTEM SCHEMATIC

ORIGINAL PAGE IS  
OF POOR QUALITY




QUATTRONE                      FIGURE 26  
VAPOR COMPRESSION DISTILLATION SUB-  
SYSTEM HARDWARE

# **THERMOELECTRIC INTEGRATED MEMBRANE EVAPORATION SUBSYSTEM FUNCTIONAL SCHEMATIC**



QUATRONE  
FIGURE 27  
THERMOELECTRIC INTEGRATED MEMBRANE  
EVAPORATION SUBSYSTEM SCHEMATIC


## TIMES WATER RECOVERY SUBSYSTEM



ORIGINAL PAGE IS  
OF POOR QUALITY

QUATRONE  
FIGURE 28  
THERMOELECTRIC INTEGRATED MEMBRANE  
EVAPORATION SUBSYSTEM HARDWARE


# VAPOR PHASE CATALYTIC AMMONIA REMOVAL FUNCTIONAL SCHEMATIC



QUATRONE  
CATALYTIC DISTILLATION WATER RECLAMATION  
SUBSYSTEM SCHEMATIC

FIGURE 29

# **SOLID WASTE MANAGEMENT SYSTEM/SPACE SHUTTLE**



QUATTRONE  
FIGURE 30  
SPACE SHUTTLE SOLID WASTE MANAGEMENT  
SYSTEM

INTERNAL CONTAMINATION

IN THE

SPACE STATION

February 1984

Prepared for:

NASA Headquarters  
Space Station Task Force  
Human Productivity Working Group

## INTRODUCTION

This paper discusses atmosphere trace contaminant control systems used in the past (Lunar Module and Skylab) and present (nuclear submarines and Shuttle), and makes recommendations for the future Space Station contaminant control system. The prevention and control methods used are judicious material selection, detection, and specific removal equipment. Sources and effects of contamination relating to crew and equipment are also discussed.

## EFFECTS OF TRACE CONTAMINANTS

Trace contaminants can affect the crew, equipment and experiments.

### Effects On The Crew

The compounds found in the trace contaminants can be divided into categories based on their major toxic effects. These categories, with examples are<sup>(1)</sup>:

1. Irritants: aldehydes, ketones and esters.
2. Asphyxiants: carbon monoxide, carbon dioxide\*, fluorinated hydrocarbons\* and methane\*.
3. Central Nervous System Depressants: aliphatic hydrocarbons and alcohols.
4. Systemic Poisons: chlorinated hydrocarbons and aromatic hydrocarbons.

---

\*Displaces oxygen at high concentrations



An indication of the toxic risk from a given atmospheric contaminant is the ratio of its concentration (C) to its SMAC (Spacecraft Maximum Allowable Concentration) value. The relative toxic hazard index (RTHI) value of compound X would be expressed as  $C_x/SMAC_x$ . Any atmospheric contaminant that exceeds its SMAC value ( $RTHI > 1$ ) would be considered to be at an unacceptably high level.

To some extent, multiple atmospheric contaminants that are in the same toxicological category exert an additive effect. The sum of all RTHI values in one toxicological category of an atmospheric sample can be referred to as the total relative toxic hazard index (TRTHI). It may be expressed mathematically as follows:

$$TRTHI = C_1/SMAC_1 + C_2/SMAC_2 + C_3/SMAC_3 + C_n/SMAC_n$$

$C_x$  = concentration of chemical  
 $SMAC_x$  = SMAC value of chemical

The level of toxicity can be subjectively graduated from nuisance valve, to reduced productivity, to health hazard, to life threatening.

Contamination may affect the drinking water supply, food storage and preparation equipment and air circulation equipment.

An additional hazard of some contaminants is their property as fuel for propagation of fire and explosion. Examples are  $H_2$ ,  $CO$ , and  $CH_4$ .

#### Effects on Equipment

Monomolecular layers on microchips can affect the conductivity of electrical paths and capacitance of elements. Surface degradation and adverse corrosion can occur as well as clogging of microporous membranes, filters and operations. Optical surfaces are particularly vulnerable.

## Effects on Experiments

Cross contamination can occur in biological experiments which can affect growth and fatality rates, thereby coloring conclusions referring to cause and effect. Non-biological experiments can also be influenced by contamination. Crystal growth, plating, flow reduction, and assembly can be affected.

## SOURCES OF CONTAMINATION

Contaminants have been found to be generated by the crew vehicle equipment, experiments, operations, food and human waste disposal, cleaning fluids, and repairs.

### Crew

Principal sources of contaminants from man are expired air, urine, feces, flatus, perspiration, vomitus and saliva (sneezing). Major contaminants generated by metabolic processes of the crew are:  $\text{CO}_2$ ,  $\text{NH}_3$ ,  $\text{CO}$ ,  $\text{H}_2\text{S}$ ,  $\text{H}_2$ ,  $\text{CH}_4$ , organic acids and mercaptans. In addition, bacteria, virus, fungus, skin particles and hair and nail clippings will occur. (2),(3)

### Equipment

Compounds generated by equipment generally have relatively high vapor pressure and are outgassed from solid materials and lubricants. Although NASA has done an outstanding job eliminating most of these contaminants in NASA owned equipment, experimenters and developers of manufacturing processes may not be able to conform to the guidelines presented in NHB 8060.1B, "Flammability, Odor, and Offgassing Requirements and Test Procedures for Materials in Environments that Support Combustion," September 1981. (4)

### Experiments and Crew Activities

Experiments can release inorganic, organic, viral and bacteriological contaminants.

Contaminants will probably be released during food preparation, food and human waste disposal, and crew cleansing.

### Accidents, Fire, Explosion, and Spillage

In addition to contaminants present during normal operations, one must consider the toxic atmospheres resulting from such upset conditions as fire or equipment failure, as well as the products of thermal decomposition due to overheating of electrical and hydraulic equipment. Carbon monoxide and aldehydes are frequent breakdown products in equipment fires. Thermal degradation of plastics will yield monomers and large chain fragments such as methyl alcohol, hydrochloric and hydrofluoric acids, and hydrogen cyanide.<sup>(5)</sup>

Accidents may occur during servicing of satellites, leading to an EVA astronaut's exposure to rocket fuels and oxidizers. These contaminants may then be brought into the station on EMU clothing or tools.

### PAST CONTAMINANT CONTROL

#### Lunar Module

The lunar module contaminant control system consisted of particulate filters and activated carbon, for odor control, both packaged in the LiOH cartridges used to control CO<sub>2</sub>. The pressure suits worn by the crew also aided contaminant control.

### Langley (MDAC) 90-Day Manned Test - 1970

Objectives of the 90-day operational manned test involved the evaluation of an advanced regenerative life support system similar to that of an orbiting scientific laboratory under closed-door conditions. These objectives included determination of long-term operating characteristics and power requirements of individual subsystems and the total system; measurement of mass and thermal balances; determination of the ability of the test crew to operate, maintain, and repair onboard equipment; measurement of chemical and microbial equilibrium of the closed life support system; assessment of the effect of confinement on the psychological and physiological characteristics of the test crew; and collection of data to assist in determining the role of man in performing in-flight experiments.<sup>(6)</sup>

This test operated with no materials passed into or out of the test chamber. The composition of the atmosphere during the manned operation was determined on a continuous basis and by individual samples taken at frequent intervals. Analysis was done by chromatograph on direct samples. Concentrated samples were also obtained by freeze-out techniques and sent through the gas chromatograph to determine the presence of organic compounds. Inorganic compounds were measured by wet chemical analysis on samples taken daily.<sup>(7)</sup>

Contaminants were controlled during the 90-day test by employing a 1.5 cfm toxin burner (integrated with a Sabatier reactor for thermal efficiency), along with particulate filters, solid amine  $\text{CO}_2$  control, molecular sieve  $\text{CO}_2$  control and a condensing heat exchanger. The cabin air was almost free of contaminants during the unmanned and manned periods preceding the 90-day test. During the 90-day test there were no inorganic compounds noted. There were no  $\text{NO}_x$  compounds until  $\text{NH}_3$  reached 0.5 ppm. The  $\text{NO}_x$  disappeared when the toxin burner was shut down, indicating  $\text{NO}_x$  was formed from  $\text{NH}_3$  in the toxin burner.

Analysis of the CO<sub>2</sub> just upstream of the Sabatier reactor showed the presence of Freon 113. The average detected concentration of Freon 113 varied from 9.0 ppm, when the solid amine unit was operating, to 33.8 ppm, when the molecular sieve unit was operating. Acetone and ethyl alcohol were also detected in the CO<sub>2</sub> at low concentrations. These results indicate that the CO<sub>2</sub> scrubbers were able to remove some of the trace contaminants.

### Skylab

The Skylab environmental control system had considerable capability to scrub the cabin air of generated contaminants. Principal elements of the system were the charcoal canisters in the molecular sieve unit and waste management systems, the condensing heat exchangers, and the Linde 13X and 5A molecular sieve material.

The molecular sieve and charcoal canisters performed their design function of removing odors, as well as removing contaminants. The only means available to evaluate the performance of the odor removal system was via crew comments, but all three crews indicated that the system performed very well.

Ground tests in which air laden with various concentrations of trace contaminants was passed through special test bed molecular sieves, qual unit molecular sieves and a Gemini condensing heat exchanger indicated that molecular sieve material had 100% removal efficiency for all contaminants tested with the exception of H<sub>2</sub> and CO as shown in Table 1. No removal capability was noted for these two gases. The condensing heat exchanger had some capability for contaminant removal, especially for Coolanol 15.

TABLE 1  
SKYLAB CONDENSING HEAT EXCHANGER AND  
MOLE-SIEVE CONTAMINANT REMOVAL EFFICIENCY

Contaminant	Test Inlet Concentration, ppm	Removal Efficiency, Percent	
		CHX	Mole-Sieve
1. Hydrogen	900	(1)	0
2. Ammonia	60	(1)	100
3. Methyl Chloride	20	(1)	100
4. Freon 12	500	(1)	100
5. Benzene	5	8.7	100
6. Freon 113	500	(1)	100
7. Xylene	50	(1)	100
8. Toluene	50	(1)	100
9. Acetone	500	(1)	100
10. Isopropyl Alcohol	100	(1)	100
11. Acetaldehyde	50	2.6	100
12. Methyl Isobutyl Ketone	10	33	100
13. Dichloromethane	25	(1)	100
14. Carbon Monoxide	75	(1)	0
15. Methyl Chloroform	90	15.2	100
16. Methyl Ethyl Ketone	100	1.1	100
17. Coolanol 15	50	89	100

(1) Not tested.

## PRESENT CONTAMINANT CONTROL

### Shuttle and Spacelab

The Shuttle and Spacelab trace contaminant control systems each include activated LiOH canisters, a condensing heat exchanger and a carbon monoxide oxidizer.

Four atmospheric samples were collected at approximately 12-hour intervals in the orbiter crew cabin during the 56-hour STS-1 mission on April 12-14, 1981.<sup>(8)</sup> Post-mission gas chromatographic/mass spectrometer analysis showed 57 different chemical contaminants; 38 were structurally identified. The total quantity of gases in each toxicological category was below the SMAC value of any one of its constituents. The only categories of gases that approached the SMAC value for any one gas in their category were the systemic poisons and asphyxiants. However, in both cases, these values were below the concentration of gases with the lowest SMAC value. The catalytic oxidizer for CO control was not present on the STS-1 mission.

### Submarines

In view of the convergence of the requirements for spacecraft and submarine life support systems a study, jointly funded by the Navy NAVSEC and NASA was prepared by Hamilton Standard in 1974<sup>(9)</sup>.

In this study, for submarines, activated carbon was selected to control trace contaminants, as well as odors, hydrocarbons and "Freon" spills. On present submarines, aerosols are controlled with strategically placed filters and electrostatic precipitators. A Hopcalite catalyst operated at high temperature is now used to control CH<sub>4</sub>, H<sub>2</sub> and CO.

Detection of trace contaminants on submarines is accomplished by a Perkin-Elmer Central Atmosphere Monitoring System (CAMS) which uses a mass spectrometer to monitor all trace contaminants except CO. An infrared analyzer monitors CO.

#### SPACE STATION

Contaminants expected in the Space Station can be divided into the following main categories:

- Those present during normal operation
  - Contaminants generated by the crew and equipment
  - Contaminants generated by experiments and manufacturing
- Contaminants generated by fire and explosion

As demonstrated by previous Skylab flights and STS-1, the combination of prevention (selection of materials), proper waste handling, and minimal removal equipment resulted in odor-free flight on Skylab and no contaminant reaching its SMAC value on STS-1.

However, it is expected that the desire to open the station to a broad user community will necessitate some relaxation of NHB 8060.1B. Therefore, higher levels of particulate and gaseous contaminants will be generated, requiring control equipment which is more sophisticated and has larger throughput than that used on Skylab and Shuttle.

In addition, the cabin volume and crew size will increase in proportion to the space station size while cabin air leakage can be expected to decline, particularly for non or low EVA activity missions.



As a result, the need to control low molecular weight contaminants, particularly  $\text{CH}_4$ , will require a high temperature (600°F) catalyst.

The high temperature catalytic oxidizer developed by Hamilton Standard is relatively insensitive to the normal humidity levels found in the environment. Additional base sorbent beds such as  $\text{LiCO}_3$  should be placed upstream of the catalyst bed to protect it from acid gases such as  $\text{SO}_2$ ,  $\text{H}_2\text{S}$  and  $\text{HCl}$ . A base sorbent bed should be placed downstream of the high temperature catalyst to stop acid gases which may be produced in that catalyst bed, such as  $\text{HCl}$  and  $\text{HF}$ .

As noted earlier, the condensing heat exchanger can be used to control some of the trace contaminants, such as ammonia, methyl isobutyl ketone, methyl chloroform and benzene which have been demonstrated in laboratory tests to be removed in the condensate water. This water must then be filtered to remove these contaminants if it is to be reused.

Particulates and aerosols can be controlled using absolute filters placed upstream of the fan and a condensing heat exchanger to remove particles greater than 0.3 microns including bacteria. The absolute filter prevents growth in the activated carbon and condensing heat exchanger. Debris traps should be placed upstream of the absolute filters to stop coarse particles (wet and dry) which make up the bulk of the particulate matter and may quickly clog the absolute filter.

#### Post-Fire Atmosphere Cleanup

In the event of a fire within the space station, the routine procedures for controlling and extinguishing the blaze should include shutting down the environmental control equipment in or serving the affected section. This action helps to lower the oxygen concentration in the area of the fire and restricts the distribution of the combustion products in the atmosphere to a local area around the fire site.

Once the fire is extinguished, the local atmosphere must be cleaned to remove suspended particulate materials and objectionable or toxic gases generated by the combustion before the ECLSS is returned to duty in order to prevent spreading the fire-generated contaminants to other parts of the station. Portable oxygen systems or other self-contained breathing apparatus should be included in the on-board emergency equipment.

One method of cleaning the fire-contaminated atmosphere would be to dump it by depressurizing the affected section. Depressurization involves added risk such as the bends if the crew had no other area in which to seek protection. In addition, depressurization of a large section of the space station will require the replacement of the  $N_2$  and  $O_2$  required. For example, a 5000  $ft^3$  section will contain 300 lbs of  $N_2$  at standard conditions. In addition, there is a possibility of contaminating experiments or sensors outside the pressurized volume.

A portable post-fire air purification unit proposed by Hamilton Standard for use in U.S. Navy ships can provide the required cleanup capability without any interface with the ECLSS. The unit is entirely self-contained and requires only a source of electric power to operate its fan. It can reduce the level of carbon monoxide in a 5000 cubic foot enclosed volume from a fatal one-hour exposure level of 5000 parts per million to a safe one-hour inhalation level of less than 500 parts per million in about 20 minutes.

To clean up a contaminated compartment, the unit need only be allowed to run unattended within the closed volume until contaminant levels are sufficiently reduced as indicated by the ECLSS Monitor and Control sensors in the compartment or until visual and olfactory observations indicate the removal of smoke and odors.

## SUMMARY

Skylab and Shuttle results have indicated that the combination of materials selection, onboard removal devices, and preflight offgassing tests can be an effective means of controlling spacecraft contaminant levels.

The following are recommendations for atmospheric contamination control on Space Station:

1. The maximum allowable levels of contaminants should be established by NASA.
2. An effective materials screening program should be carried out to eliminate materials with offgassing characteristics above established criteria; i.e., NASA should produce a list of acceptable materials.
3. Contaminants should be selectively monitored using a CAMS or similar unit.
4. A simple, standard procedure should be developed to test the flammability and outgassing of flight payloads and experiments. Standard cabinets should be considered, especially designs which accommodate special sorbent beds and interface with the catalytic oxidizer so that unique contaminants can be efficiently controlled.

Table 2 defines the elements of a contaminant control system envisioned for a Space Station. Additional equipment or designed-in, controlled cabin leakage may later be required.

TABLE 2  
TYPICAL SS CONTAMINANT CONTROL SYSTEM

<u>ITEM</u>	<u>TO CONTROL</u>
Absolute Filters	Particulates, Bacteria and Aerosols
Condensing Heat Exchanger	Humidity Control (Moisture) and Water Soluble Compounds
CO <sub>2</sub> Removal Hardware	Carbon Dioxide Level
Activated Charcoal (Treated and Untreated)	High Molecular Weight Hydrocarbons and Ammonia
High Temperature Catalytic Oxidizer with Pre- and Post- Filters	Cabin Monoxide, Hydrogen and Low Molecular Weight Hydrocarbons; acid gases and products of oxidation

## REFERENCES

1. "Toxicological Assessment of the STS-1 56-Hour Outgassing Samples," S.L. Pool, M. E. Coleman, 6-26-81, SD/Chief, Medical Sciences Division, Johnson Space Center, NASA.
2. "A Detailed Study of Contaminants Produced by Man in a Space Cabin Simulator at 760 mm Hg." J. P. Conkle Mar 1967, SAM TR-67-16, USAF School of Aerospace Medicine, Aerospace Medical Division AFSC, Brooks Air Force Base, Texas.
3. "Bioastronautics Data Book," 2nd ed, NASA SP 3006, 1973.
4. "Flammability, Odor and Offgassing Requirements and Test Procedures for Materials in Environments that Support Combustion," NHB 8060.1B, Sep 1981.
5. "Compendium of Human Responses to the Aerospace Environment," Vol III Sec 13, NASA CR-1205 Nov 1968.
6. "Preliminary Results from an Operational 90-Day Manned Test of a Regenerative Life Support System," Nov 17, 1970, NASA SP-261, Langley Research Center, NASA.
7. "Test Report - Test Results - Operational Ninety-Day Manned Test of a Regenerative Life Support System," NASA CR-111881, MDC G2282, Langley Research Center, May 1971.
8. "Skylab Atmosphere Contamination Control," NASA TM X-64900, Marshall Spaceflight Center, NASA.
9. Advanced Life Support Application Study - Design Notebook N00024-74-C-5422 for Naval Sea Systems Command, HSD No. SVHSER 6536.

B90.07

23FEB84 P414

KS

# **INTERNAL CONTAMINATION: SPACE STATION LIFE SUPPORT ALTERNATIVES**

**Prepared for: Space Station Human Productivity  
Working Group**

**28 February 1984**

*Chris Eyer*

## **CONTAMINATION CONTROL ALTERNATIVES**

### **1. Business as usual (preventative)**

**NHB 1700.7A (safety policy)**

**NHB 8060.1B (flammability, odor, offgassing)**

### **2. Relax prevention guidelines**

### **3. Revise prevention approach to soften burden on users; increase on-board control**

# **THREE QUESTIONS FOR CONTAMINANT CONTROL**

- 1. What is the contaminant?**
- 2. What is its allowable level?**
- 3. What is its production rate?**


**Having answers to these questions is key to  
controlling the contaminant.**



## **CONTAMINATION AND HUMAN PRODUCTIVITY**

- **Effects on the crew**
  - **Categories/levels**
- **Sources of contaminants**
  - **Crew, equipment, experiments, accidents**
- **Non-venting regenerative life support for  
Space Station**

# TYPICAL TRACE CONTAMINANT CONTROL SYSTEM



# **SOME FLAMMABILITY/CONTAMINANT SCREENING IS MANDATORY**

**Without screening, Space Station payloads/  
experiments need:**

- **Isolated, fireproof module(s)**
- **Independent ECLS system(s)**
- **Over-designed contaminant control scheme  
with conservatively frequent filter/sorbent  
changes**

**The burden on station designers and the risk to  
the crew are inappropriate. Some screening  
is mandatory.**


## **CUSTOMER - FRIENDLY CONTAMINATION CONTROL**

- 1. NASA publish a list of approved materials**
- 2. NASA publish a list of prohibited materials**
- 3. NASA establish a "customer service" center  
with assigned payload "sponsors" to soften  
burden on users**

# USER'S EXPERIMENT/PAYLOAD CHECKOUT & SCREENING AT NASA FACILITIES


①

**Flammability  
test**



②


**Operational  
verification  
and outgassing  
test**



**Atmosphere  
sampling/analysis  
3 days**

③

**Select sorbent  
cartridges  
for experiment**




# STANDARD CABINET FOR EXPERIMENTS SUSCEPTIBLE TO OFFGASSING


Bleed air varied for each  
experiment to guarantee safe  
environment when opened

Bleed  
air inlet

Access doors for  
experiment operation  
and data collection



# SMOKE/TOXIC GAS AIR PURIFICATION UNIT






BIOTECHNOLOGY

SPACE STATION  
TRACE CONTAMINANT CONTROL

2-154


N85-29550





## SPACECABIN CONTAMINANT SOURCES

SOURCE	CONTAMINANT
o MAN	- METABOLIC PRODUCTS: $\text{CO}_2$ , $\text{NH}_3$ , $\text{CO}$ , $\text{H}_2\text{S}$ , $\text{H}_2$ $\text{CH}_4$ , ORGANIC ACIDS, MERCAPTANS
o SPACECRAFT SUBSYSTEMS, EXPERIMENT EQUIPMENT AND PAYLOADS	- BACTERIOLOGICAL CONTAMINANTS - WIDE VARIETY OF ALCOHOLS, ALDEHYDES, AROMATICS, ESTERS, ETHERS, CHLOROCARBONS, FLUOROCARBONS, HALOCARBONS, HYDROCARBONS, KETONES, ACIDS
o EMERGENCY SITUATIONS: FIRE, SPILLS, EQUIPMENT FAILURES	- $\text{CO}$ , $\text{CO}_2$ , HYDROCARBONS, AROMATICS, ACID GASES, OXIDES OF $\text{N}_2$ , $\text{SO}_2$ , $\text{NH}_3$ , ALCOHOLS, FORMALDEHYDE
o ANIMAL AND PLANT EXPERIMENTS	- METABOLIC, BACTERIOLOGICAL




TECHNOLOGY BASE

PROGRAMS

---

- o DEFINITION OF ACTIVATED CHARCOAL SORPTION CHARACTERISTIC FOR A WIDE VARIETY OF CONTAMINANTS AND CHARCOALS
  - o DEVELOPMENT OF ANALYTICAL TOOLS FOR PREDICTING CHARCOAL SORPTION AND SIZING OF BED
  - o DEVELOPMENT OF IN-FLIGHT CHARCOAL BED REGENERATION METHODS USING HEAT AND VACUUM
  - o DEFINITION OF CONDENSING HEAT EXCHANGER REMOVAL CAPACITY
  - o DEFINITION OF HIGH TEMPERATURE CATALYTIC OXIDIZER PERFORMANCE CHARACTERISTICS AND PRE AND POST SORBENT REQUIREMENTS
  - o DEFINITION OF PRE AND POST SORBENT BED PERFORMANCE
  - o DEVELOPMENT OF ROOM TEMPERATURE CATALYTIC OXIDIZER BED
  - o DEVELOPMENT OF ACID GAS REMOVAL BED
  - o DEVELOPMENT OF AMMONIA REMOVAL SORBENT
  - o DEVELOPMENT OF FORMALDEHYDE REMOVAL SORBENT
-




BIOTECHNOLOGY

## CONTAMINANT CONTROL SYSTEM ELEMENTS


### PROGRAMS

DEVICE	CONTROLS
FIXED CHARCOAL BED	LOW MOLAR VOLUME WELL ABSORBED CONTAMINANTS
REGENERATIVE CHARCOAL BED	HIGH MOLAR VOLUME MODERATELY WELL ABSORBED CONTAMINANTS
PHOSPHORIC ACID IMPREGNATED CHARCOAL	AMMONIA
CONDENSING HEAT EXCHANGER	HIGHLY SOLUBLE CONTAMINANTS
ROOM TEMPERATURE CATALYTIC OXIDIZER	CARBON MONOXIDE, HYDROGEN
HIGH TEMPERATURE CATALYTIC OXIDIZER	POORLY ABSORBED HYDROCARBONS
PRE AND POST SORBENT	ACID GASSES, SULFUR COMPOUNDS

## TYPICAL CONTAMINANT CONTROL SYSTEM CONFIGURATION



SPACE  
STATION



PROGRAMS

BIOTECHNOLOGY

## APPROACH TO CONTAMINANT CONTROL

- o DEFINE CONTAMINANT LOAD MODEL AND PRODUCTION RATES
- o DEFINE SPACECRAFT MAXIMUM ALLOWABLE CONCENTRATIONS (SMAC)
- o ESTABLISH FIXED CHARCOAL BED SIZE FOR EACH CONTAMINANT
- o DEFINE NEED FOR REGENERATIVE BED
- o DEFINE CONTAMINANTS NOT HANDLED BY FIXED AND REGENERATIVE BEDS
- o SIZE SPECIAL SORBENT BEDS OR CATALYTIC OXIDIZERS
- o OPTIMIZE SYSTEM CONSIDERING CONTAMINANT LOAD AND SYSTEM INTERACTION



BIOTECHNOLOGY

## CONTAMINANT LOAD MODEL DEFINITION


PROGRAMS

### DATA SOURCES

- o WSTF MATERIALS OFFGASSING TESTS
- o SPACE COMPONENTS OFFGASSING TESTS
- o PAYLOAD EQUIPMENT OFFGASSING TESTS
- o MANNED SPACECRAFT CONTAMINANT MONITORING (GROUND AND FLIGHT)
- o GROUND BASED MANNED SIMULATOR TESTS
- o LITERATURE AND TEST DATA FOR METABOLIC CONTAMINANTS

### DATA COMPILATION

- o DETERMINATION OF PAYLOAD GENERATION RATES PER UNIT WEIGHT
- o ESTIMATE OF TOTAL PAYLOAD WEIGHT
- o DETERMINATION OF SPACE SYSTEMS GENERATION RATES PER UNIT WEIGHT
- o METABOLIC LOADS FROM CREW SIZE
- o COMPOSITE CONTAMINANT LOAD




BIOTECHNOLOGY

## SPACECRAFT MAXIMUM ALLOWABLE CONCENTRATIONS

---

- o ESTABLISHED BY NASA JSC MEDICAL DIRECTORATE
  - o DOCUMENTED IN NHB 8060.113 FOR UP TO 7 DAYS
  - o SOME CONTAMINANTS NOT INCLUDED IN NHB 8060.113
  - o SEVERAL CONTAMINANTS HAVE VERY LOW ALLOWABLE LEVELS
- 
-



## CHARCOAL BED SIZING


- o CHARCOAL BED INCLUDES SATURATED ZONE PLUS ABSORPTION ZONE
  - o CAPACITY DEPENDS ON CONTAMINANT CHARACTERISTICS
    - TEMPERATURE
    - MOLAR VOLUME
    - VAPOR PRESSURE
    - INLET CONCENTRATION
- } "A" VALUE
- o "A" VALUE PLUS EXPERIMENTALLY DETERMINED POTENTIAL PLOT PROVIDES SATURATION CAPACITY
  - o ADSORPTION ZONE LENGTH IS ADDED TO SATURATED ZONE TO DETERMINE TOTAL BED SIZE
  - o BED SIZE ADJUSTED FOR COADSORPTION
  - o SIZING ACCOMPLISHED BY COMPUTER PROGRAM (ICHAR)







# TYPICAL CHARCOAL PERFORMANCE CHARACTERISTICS

POTENTIAL PLOT FOR VARIOUS CHARCOALS



ADSORPTION ZONE LENGTHS FOR VARIOUS CONTAMINANTS






## CATALYTIC OXIDIZER SIZING


---

- o ESTABLISH CONTAMINANTS THAT REQUIRE OXIDATION FOR CONTROL
- o DETERMINE NEED FOR HIGH OR LOW TEMPERATURE CATALYTIC OXIDIZER
- o SELECT MOST EFFECTIVE CATALYST FROM TEST DATA
- o DETERMINE FLOW RATE, RESIDENCE TIME AND CATALYST BED SIZE
- o OPTIMIZE INSULATION REQUIREMENTS VERSUS BED SIZE




# TYPICAL CATALYTIC OXIDIZER PERFORMANCE CHARACTERISTICS

CONVERSION EFFICIENCY  
FOR VARIOUS CATALYSTS



CONVERSION EFFICIENCY  
FOR VARIOUS RESIDENCE TIMES



2-165

ORIGINAL PAGE IS  
OF POOR QUALITY




BIOTECHNOLOGY

## SPECIAL SORBENT BED SIZING

- o USED FOR AMMONIA, ACID GASES AND OTHER SPECIAL CONTAMINANTS
- o BED SIZE DETERMINED BY
  - ALLOWABLE CONCENTRATION
  - TOTAL CONTAMINANT GENERATION RATE
  - EXPERIMENTALLY DETERMINED CONTACT TIME
  - MISSION DURATION
- o GENERALLY INTEGRATED INTO FIXED CHARCOAL BED
- o LITHIUM HYDROXIDE AND POTASSIUM HYDROXIDE IMPREGNATED CHARCOAL  
USED FOR ACID GASES
- o ACID IMPREGNATED CHARCOAL USED FOR AMMONIA
- o CHROMATE IMPREGNATED CHARCOAL USED FOR FORMALDEHYDE

SPACE  
STATION



PROGRAMS

BIOTECHNOLOGY

## ANIMAL AND PLANT RESEARCH PAYLOAD PROBLEMS


---

### PROBLEMS

- o WASTE REMOVAL AND STORAGE
- o BACTERIOLOGICAL CROSS CONTAMINATION

### SOLUTIONS

- o COMPLETE ISOLATION OF CREW AND EXPERIMENTS BY USE OF SEPARATE ENVIRONMENTAL SYSTEMS
- o USE OF HIGH EFFICIENCY BACTERIOLOGICAL FILTERS
- o USE OF ONLY SPF ANIMALS
- o USE OF ISOLATION TRANSPORTERS FOR WASTE REMOVAL AND STORAGE
- o USE OF SPECIALLY DESIGNED ISOLATION WORK STATIONS (GLOVE BOX DESIGN)



BIOTECHNOLOGY

## EMERGENCY UPSET CONTAMINANT REMOVAL

---

- o SAFE HAVEN CREW SHELTER
- o EMERGENCY CONTAMINANT REMOVAL SYSTEM REMOTELY ACTIVATED
- o PORTABLE BREATHING APPARATUS
  - OXYGEN LINE
  - SUPEROXIDE BREATHER
- o CABIN DECOMPRESSION AND REPRESSURIZATION



## CONCLUSIONS

- o TRACE CONTAMINANT CONTROL TECHNOLOGY BASE IS RELATIVELY FIRM
- o HARDWARE AND DESIGN TOOLS ARE AVAILABLE
- o PREVIOUS DESIGN PHILOSOPHY STILL APPLICABLE
  - I.E., CONSERVATIVE LOAD MODEL REFINED LATER AS ACTUAL OFFGASSING DATA ARE AVAILABLE
- o MAJOR CONCERNS
  - CATALYTIC OXIDIZER (NEED VS. DANGER)
  - CONTAMINANTS WITH VERY LOW ALLOWABLE CONCENTRATIONS
  - IMPACT OF RELAXING MATERIALS REQUIREMENTS

WEDNESDAY, FEBRUARY 29

		Page
Detection and Control		
Gas Chromatography: Possible Application of Advanced Instrumentation Developed for Solar System Exploration to Space Station Cabin Atmospheres	G. Carle	3-1 to 3-15
Mass Spectrometry at the Jet Propulsion Lab	C. Griffin	3-16 to 3-32
Trace Gas Analyzer and NASA Experience: Atmosphere Monitoring Requirements	M. Ruecker	3-33 to 3-61
Some Problems Associated with Trace Contaminant Removal Systems for Spacecabins	T. Wydeven	3-62 to 3-76
Contamination Control for Increased Crew Productivity	D. Heppner	3-77 to 3-105
Human Productivity Program Definition	D. Cramer	3-106 to 3-131
The Human Role in Space (THURIS)	H. Wolbers	3-132 to 3-175



GAS CHROMATOGRAPHY:  
POSSIBLE APPLICATION OF ADVANCED INSTRUMENTATION  
DEVELOPED FOR SOLAR SYSTEM EXPLORATION  
TO  
SPACE STATION CABIN ATMOSPHERES

GLENN C. CARLE  
SOLAR SYSTEM EXPLORATION OFFICE  
NASA, AMES RESEARCH CENTER  
MOFFET FIELD, CA 94035


Gas chromatography (GC) technology has been under development for flight experiments in solar system exploration for some years. GC is a powerful analytical technique where relatively simple devices can separate individual components from complex mixtures and then make very sensitive quantitative and qualitative measurements. It is particularly suited to monitoring samples containing mixtures of fixed gases and volatile organic molecules. GC has been used on the Viking mission in support of life detection experiments and on the Pioneer Venus Large Probe to determine the composition of the venusian atmosphere. A flight GC is currently being developed to study the progress and extent of STS astronaut denitrogenation prior to extravehicular activity. Advanced flight GC concepts and systems for future solar system exploration are also currently under study. Studies include miniature ionization detectors and associated control systems capable of detecting from ppb up to 100 percent concentration levels. Further miniaturization is being investigated using such techniques as photolithography and controlled chemical etching in silicon wafers. Novel concepts such as ion mobility drift spectroscopy and multiplex gas chromatography are also being developed for future flight experiments. These powerful analytical concepts and associated hardware are ideal for the monitoring of cabin atmospheres containing potentially dangerous volatile compounds and could be applied with minimal development.

TABLE 1

## PIONEER VENUS LGC RESULTS

SAMPLE NUMBER	1	2	3
ALTITUDE, KM	51.6	41.7	21.6
PRESSURE, BARS	0.7	2.9	17.8
GAS	% CONCENTRATION		
CO <sub>2</sub>	95	96	96
N <sub>2</sub>	4.6	3.5	3.4
H <sub>2</sub> O	<0.06	0.52	0.14
	ppm		
O <sub>2</sub>	44	16	
Ar	60	64	67
CO	32	30	20
Ne	8	11	4
SO <sub>2</sub>	<600	180	185

Figure 1: Pioneer Venus short column chromatogram of 24 km sample, showing raw data points. Solid line shows detector signal at a range of 0.7 to 1.6 mV. Dashed line shows detector signal at a range of 0.7 to 900 mV. Inset at right is expanded view of  $\text{SO}_2$  peak.



ORIGINAL PAGE IS  
OF POOR QUALITY

Figure 2: Pioneer Venus long column chromatogram of 24 km sample, showing raw data points. Solid line shows detector signal at a range of 0.6 to 1.5 mV. Dashed line shows detector signal at a range of 0.6 to 90.6 mV. Inset at left is expanded view of Neon peak.





Figure 3 - Evolution of Gas Chromatographic Detectors.  
From top to bottom: Commercial Thermoconductivity Detector (TCD);  
Viking GEX TCD; Mockup of commercial Metastable Ionization Detector  
(MID); ARC miniature MID (Woeller)



3-5

ORIGINAL PAGE IS  
OF POOR QUALITY

# GC / IMDS




Figure 4: Gas Chromatograph separates components of sample mixture. IMDS reactant ions ionize each sample component as it elutes from the GC column forming product ions. These product ions are separated in the drift tube according to their size and structure forming Ion Mobility Spectra of the sample components.

Figure 5: Top: Typical positive reactant ion spectrum (background).  
Bottom: IMDS spectra of three heptylhalides. Although similar in  
structure, the heptylhalides produce distinctly different spectra.





Figure 6: Block Diagram of Two-Dimensional Multiplex Gas Chromatographic System. Computer controls sample introduction using two concentration modulators and analyzes detector output to produce 2-dimensional chromatogram.





ORIGINAL PAGE IS  
OF POOR QUALITY




Figure 7. Exploded View of Instrument Packaging

# VIKING GEX CHROMATOGRAPHIC SEPARATIONS




Figure 8.

# VL-1 GAS CHANGES IN GEX HEADSPACE




Figure 9

ORIGINAL PAGE IS  
OF POOR QUALITY.

# PIONEER VENUS GAS CHROMATOGRAPHIC ATMOSPHERIC ANALYZER





Figure 10

ORIGINAL PAGE IS  
OF POOR QUALITY

DATE: 020482

DETECTOR: ARC-2  
20°C, 1-bar  
COLUMN: PORAPAK-N  
200-325  
8.0 m/20°C  
F = 12.2 cm<sup>3</sup>/min  
SAMPLE: 1 cm<sup>3</sup>  
DETECTOR SETTING:  
300 V/1.74 x 10<sup>-9</sup> A



CHROMATOGRAM DEMONSTRATING CAPABILITY OF CURRENT TECHNOLOGY TO MEASURE SPECIES IN THE PARTS-PER-BILLION RANGE (E.G.,  $CO_2$  AT 20 PPB)

Figure 11

# MODULATED VOLTAGE METASTABLE IONIZATION DETECTOR




Figure 12

3-14

C-4

# LABORATORY PROTOTYPE MICRO GAS CHROMATOGRAPH




Figure 13

2/28/84

Mass Spectrometry Technology at the Jet Propulsion Laboratory (JPL)

by

Charles E. Giffin

INTRODUCTION

The purpose of this presentation is to inform the members of the NASA Human Productivity Working Group about recent developments in the field of mass spectrometry taking place at the Caltech Jet Propulsion Laboratory. The pertinent research and development is aimed at producing an ultra-high sensitivity mass spectrograph for both spaceflight and terrestrial applications. The unique aspect of the JPL developed technology is an integrating focal plane ion detector that obviates the need for spectral scanning since all ions over a wide mass range are monitored simultaneously. The ion detector utilizes electro-optical technology and is therefore referred to as an Electro-Optical Ion Detector (EOID). A technical description of the JPL MS/EOID, some of the current applications, and its potential benefits for internal contamination analysis are discussed below.

MS/EOID TECHNOLOGY

Figure 1 illustrates the comparison between a scanning mass spectrometer and a non-scanning mass spectrograph. Simply put, the spectrometer can monitor only one ion species at a time while the spectrograph monitors simultaneously all ion species illuminating the focal plane. For high sensitivity, the spectrometer utilizes an electron multiplier for an ion detector which can achieve the ability to detect single ions passing through the image slit. Classically, the mass spectrograph has used a photoplate to simultaneously monitor all the ion species along the focal plane but required approximately 10,000 ions to generate a detectable image in the photographic emulsion. The duty cycle (i.e., the fraction of time spent measuring individual



ion currents during a spectral scan period) of a scanning mass spectrometer can be as low as 0.01% per mass peak over a mass range of 20:1. The mass spectrograph has a 100% duty cycle. Hence several orders of magnitude increase in spectral sensitivity can be achieved with a spectrograph fitted with an ion detector capable of detecting single ions. The EOID achieves this requirement.

Figure 2 illustrates the EOID concept. Ions exiting the magnetic field of a mass spectrograph impinge on a two dimensional microchannel electron multiplier array (MCA). For each ion entering a microchannel  $10^4$  electrons exit the channel and are accelerated to the phosphored surface of a fiber optic vacuum window. Approximately 100 photons are generated for each impinging electron giving an overall ion-to-photon gain of  $10^6$ . The photons are guided fiber optically to a self-scanned linear photodiode array (PDA) where signals are integrated, converted back to electrons and sent to a computer. Figure 3 is a photograph of "ion" images appearing on the exit face of the fiber optic window arising from a sample of perfluoro-iso-octane (MW = 438 amu).

Figure 4 is a schematic representation of the MS/EOID hardware implementation. The focal plane is 12.7 cm long and is viewed by five 1024 element PDAs interdigitated fiber-optically for mechanical reasons. Hence the MS/EOID has 5120 individual detector elements (photodiodes) continuously observing the mass spectral signal. Each photodiode is inactive for only 8.3  $\mu$ s while it is being readout to the computer. Spectral integration time can be varied from several tens of milliseconds to tens of seconds. Figure 5 is a summary of the existing "miniaturized" MS/EOID specifications and Figure 6 is a photograph of the instrument.

## APPLICATIONS

Inherent in the MS/EOID concept is the potential for both high sensitivity as well as rapid transient response. Different applications may stress one over the other and in some cases both are required. In general, however, the preservation of complete spectral information while detecting ion currents with single ion sensitivity has opened up some interesting fields of research.

An application stressing sensitivity is that of amino acid analysis from protein molecules sequenced by the Edman degradation chemical process. Determination of the protein structure is accomplished by successively clipping amino acids, one by one off the protein molecule in the sequenator, and analyzing each sample for the prominent amino acid in that residue. Liquid chromatography coupled with UV detection is typically used. This is both time consuming and not very sensitive (30 minutes for an LC run and  $\sim 1$  ng detectability). An automated MS/EOID is currently under development at JPL that has an analysis time of one minute and a detectability approaching 1 pg. Figure 7 is a block diagram of the system and Figures 8 and 9 are representative data. Efficient sample acquisition and transport together with sample contamination are areas of concern being presently worked.

An MS/EOID instrument system is currently under development that requires both fast transient response and high sensitivity. This system will be utilized for the real-time analysis of ambient aerosols and biological particles in air. This system concept is shown schematically in Figure 10. Ambient aerosol particles are extracted from the air and formed into a beam by a differentially pumped capillary/skimmer system. As the particles strike a hot rhenium filament, they are volatilized and the plume of vapor is subsequently ionized by an electron beam. The burst of ions thus generated (in a time span of  $\sim 100$ - $200$   $\mu$ s) is accelerated into the mass analyzer, separated according to mass, and integrated by the EOID. Complete mass spectra from each volatilized/ionized particle can be read out at intervals as

closely spaced as 40 ms. Figures 11 and 12 are data gathered from 1.7  $\mu\text{m}$  diameter potassium biphthalate particles and three different bacterial particles without the benefit of MS/EOID. In these cases approximately 1000 particles per peak were required to generate the statistics necessary to quantitate the ion intensity measurements using a quadrupole mass filter in the manual scan mode. The MS/EOID for the particle analysis research is currently being assembled and will be operational by early spring. A laser ionization method is also under development and will be studied in detail after the MS/EOID is interfaced to the particle beam inlet system.

#### APPLICATION TO SPACE STATION INTERNAL CONTAMINATION

It is the author's opinion that the potential role MS/EOID could play in the area of internal contamination would be as a quantitative analysis tool for the elucidation of atmospheric contaminants aboard Space Station. With the hundreds of contaminants found over the years in spacecraft environments, it would appear that combined gas chromatography-mass spectrometry offers the best chance for accurately assessing potentially hazardous conditions in the environment.

The existing MS/EOID at JPL covers a much broader mass range than is required (a maximum mass limit of 300 amu should be adequate). A small MS/EOID at the University of Minnesota (built for upper atmosphere balloon borne measurements) is too small with a maximum mass limit of 50 amu. Preliminary calculations show that if one limits the focal plane length to 6.4 cm a medium size MS/EOID could be constructed covering a mass range from 15 amu to 300 amu while taking advantage of the latest state-of-the-art high resolution microchannel electron multiplier array and photodiode array devices available on the market.

The rationale for using an MS/EQID over a more conventional mass spectrometer is speed of response coupled with high sensitivity. Were a micro GC column (silicon wafer type) developed that could effect the required separation of contaminant species then the MS/EQID would likely be the only mass spectrometer that could measure the spectra of the very narrow (fractional second) peaks eluting from the GC. Because of its small size, the silicon wafer GC also utilizes very small sample aliquots thus requiring a high sensitivity detector for the quantitative measurement of trace species.





Figure 1 - Comparison of Spectrometer and Spectrograph Geometries




Figure 2 - Electro-Optical Ion Detector Schematic

ORIGINAL PAGE IS  
OF POOR QUALITY.

Figure 3 ION IMAGES FROM MS/E01D




Figure 4 MS/EIOD IMPLEMENTATION SCHEMATIC

ORIGINAL PAGE IS  
OF POOR QUALITY



## MS/EQID PERFORMANCE

- MASS RANGE 25 - 500 AMU
- MASS RESOLUTION  $(M/\Delta M)_{10\%} = 515$
- DYNAMIC RANGE  $1.5 \times 10^4$
- SPECTRAL READOUT TIME 40 MILLISECONDS
- DETECTABILITY (WITH 100:1 SPECTRAL DYNAMIC RANGE)  $\sim 1 \times 10^{-15}$  GRAM\*

\*APPROXIMATELY EQUIVALENT TO 0.1  $\mu$ M DIAMETER PARTICLE OF UNIT DENSITY

Figure 5

DOUBLE FOCUSING FOCAL PLANE MASS SPECTROGRAPH WITH AN ELECTRO-OPTICAL ION DETECTOR




Figure 6






Figure 7: Mass Spectrograph System for Amino Acid Analysis

ORIGINAL PAGE IS  
OF POOR QUALITY



(a)



(b)

Figure 8 Representative Line Spectra;  
(a) Glycine-PTH, (b) Proline-PTH,  
(c) Leucine-PTH

ORIGINAL PAGE IS  
OF POOR QUALITY




Figure 9 Glycine/Proline-PTH Elution Characteristics and Sensitivity  
Curve #1:  $m/e = 192$ , Curve #2:  $m/e = 232$ ,  
 $T_I$  = Spectral Integration Time

## PAMS WITH ELECTRO-OPTICAL ION DETECTION




Figure 10




Figure 11a Mass spectrum obtained from potassium biphthalate particles of  $1.7 \mu\text{m}$  diameter.




Figure 11b Pulse height Distribution of ion pulses at 50 amu resulting from  $1.7 \mu\text{m}$  diameter KBP particles.

ORIGINAL PAGE IS  
OF POOR QUALITY




Figure 12 MASS SPECTRA FROM BACTERIAL PARTICLES



## ATMOSPHERE MONITORING REQUIREMENTS

INSTRUMENTATION REQUIREMENTS DEPEND ON MONITORING NEEDS

WHAT IS THE ACTION PROTOCOL?

WHAT ACTIONS CAN BE TAKEN?

WHAT INFORMATION IS NEEDED?

WHO DECIDES ON ACTION?

INFORMATION REQUIREMENTS

COMPOUND TYPE

QUANTITATION

RATE OF BUILD-UP

SOURCES AND CAUSES OF ATMOSPHERIC CONTAMINATION

SYSTEM DESIGN

MATERIALS

MAJFUNCTIONS

## ATMOSPHERE MONITORING REQUIREMENTS (CONT'D)

### RESULTING ATMOSPHERIC CONDITIONS

POSSIBLE COMPOUND TYPES

ORGANIC

INORGANIC

ANTICIPATED

STRANGERS

TOXICITY RANGE

CONTAMINANT MIXTURES

DYNAMICS

### WHAT CONSTITUTES ADEQUATE PROTECTION?

### WHAT PRICE IS ACCEPTABLE?

DOLLARS

SPACECRAFT DEMANDS

SYSTEM DEMANDS

PROGRAM DEMANDS

## INSTRUMENT REQUIREMENTS

### PERFORMANCE

COMPOUNDS

IDENTIFICATION

DETECTION LIMIT

DYNAMIC RANGE

INTERFERENCES

ANALYSIS TIME

INFORMATION OUTPUT

ACCURACY

OPERATING MODES

### DEMANDS

POWER

WEIGHT

SIZE

CONFIGURATION

INTERFACES

DATA FORMAT

OPERATOR INVOLVEMENT

RELIABILITY

MAINTAINABILITY

## INSTRUMENTATION -- SINGLE DEVICES

### GAS CHROMATOGRAPHY

- GOOD SENSITIVITY
- RELATIVELY SLOW
- BROAD COMPOUND COVERAGE
- GOOD MIXTURE CAPABILITY
- IDENTIFICATION NOT ASSURED
- STRANGERS CANNOT BE IDENTIFIED
- MODERATE SPACECRAFT DEMANDS
- RELATIVELY LOW COST
- FLIGHT HARDWARE EXPERIENCE

### MASS SPECTROMETRY

- GOOD SENSITIVITY
- EXCELLENT SPEED
- BROAD COMPOUND COVERAGE
- GOOD MIXTURE CAPABILITY FOR KNOWN COMPOUNDS ONLY
- IDENTIFICATION LESS DEPENDENT ON CALIBRATION
- STRANGERS CAN BE IDENTIFIED IF ISOLATED
- REASONABLE SPACECRAFT DEMANDS DEPENDING ON CONFIGURATION
- MODERATE COST
- EXTENSIVE FLIGHT HARDWARE EXPERIENCE

INSTRUMENTATION -- SINGLE DEVICES (CONT'D)

OTHER SINGLE DEVICES

INFRA RED--

NOT AS WIDELY USED

GENERALLY LESS SENSITIVE

MODERATE MIXTURE CAPABILITY

NON DISPERSIVE IR

CHEMILLUMINESCENT

ELECTROCHEMICAL

} SPECIFIC COMPOUNDS ONLY

## INSTRUMENTATION -- TANDEM DEVICES

### GAS CHROMATOGRAPH/MASS SPECTROMETRY

- WIDELY ACCEPTED FOR MIXTURE AND ATMOSPHERIC ANALYSIS
- PROVIDES MIXTURE SEPARATION AND POSITIVE IDENTIFICATION
- GOOD SENSITIVITY
- BROAD COVERAGE
- STRANGER IDENTIFICATION
- RELATIVELY SLOW
- MORE SIGNIFICANT SPACECRAFT DEMANDS
- EXPENSIVE
- FLIGHT HARDWARE EXPERIENCE

### TANDEM MASS SPECTROMETRY (CID)

- POTENTIALLY FASTER THAN GCMS
- SOMEWHAT LESS SEPARATION CAPABILITY
- LESS PROVEN THAN GCMS
- LESS SUITABLE FOR RELIABLE, LONG TERM MONITORING
- SUBSTANTIAL SPACECRAFT DEMANDS
- NO FLIGHT HARDWARE EXPERIENCE

## SPECIFIC COMPOUND ISSUES

### MAJOR CONSTITUENTS:

- $N_2$ ,  $O_2$ ,  $H_2O$ ,  $CO_2$
- MAY BE ADDRESSED EFFECTIVELY BY DIRECT MASS SPECTROMETRY
- SHOULD BE A DEDICATED DEVICE
- REQUIRES A DIFFERENT ANALYZER FOR OPTIMIZED PERFORMANCE

### CARBON MONOXIDE:

- DIFFICULT FOR GCMS
- PROBABLY DESERVES A DEDICATED DEVICE
- NDIR IS THE BEST APPROACH
- ELECTROCHEMICAL MAY BE ACCEPTABLE

### OTHER INORGANIC COMPOUNDS:

- $NO_x$ ,  $SO_2$ , HALOGENS, ACIDS
- SPECIAL PROBLEMS FOR GCMS
- DEDICATED GC A POSSIBILITY
- OTHER DEDICATED DETECTORS

## ATMOSPHERE MONITORING EXPERIENCE

### TWO GAS SENSOR DEVELOPMENT:

- 60 DAY MANNED CHAMBER TEST
- 90 DAY MANNED CHAMBER TEST
- OTHER APPLICATIONS

### LABORATORY TRACE CONTAMINANT SENSOR:

- ACCUMULATOR CELL/MASS SPECTROMETER

### CENTRAL ATMOSPHERE MONITORING SYSTEM -- CAMS MK I:

- MASS SPECTROMETRY OF MAJOR AND SELECTED CONSTITUENTS

### CONTAMINANT AND ATMOSPHERIC SENSOR

### FLIGHT TRACE CONTAMINANT SENSOR:

- CONCEPTUAL DESIGN OF FLIGHT ACCUMULATOR CELL/MS

### SPACELAB TRACE GAS ANALYZER:

- GCMS BASED ON VIKING GCMS TECHNOLOGY
- UTILIZED ACCUMULATOR CELL TECHNOLOGY

### CENTRAL ATMOSPHERE MONITORING SYSTEM -- CAMS MK II:

- MICROPROCESSOR CONTROLLED SCANNING MASS SPECTROMETER



### TGA PROGRAM HISTORY

1975 BREADBOARD FEASIBILITY PROGRAM  
1976 DATA SYSTEM DEVELOPMENT  
1977 GCMS INTERFACE STUDIES  
JAN 1978: INITIATED FLIGHT HARDWARE PROGRAM  
AUG 1978: PRELIMINARY DESIGN REVIEW  
AUG 1979: CRITICAL DESIGN REVIEW  
JUN 1981: ENGINEERING TEST UNIT DELIVERED  
JUL-SEPT 1981: ETU EVALUATION AT NASA/JSC  
OCT 1981: ETU RETURNED FOR MODS  
FEB 1982: QUAL UNIT DESIGN COMPLETED  
APR 1982: PROGRAM CANCELLED

SPACELAB PREMISES

TRACE CONTAMINANT MONITORING ORIGINALLY REQUIRED

NECESSARY DUE TO:

REDUCED MATERIAL TESTING  
LESS MATERIAL CONTROL

PRIMARY CONCERN-- SLOW BUILD-UP OF ORGANIC CONTAMINANTS

EIGHT ORGANIC COMPOUND CLASSES AND CARBON MONOXIDE

UP TO 30 DAY CONTINUOUS EXPOSURE

PERIODIC ANALYSIS

GROUND BASED DATA ANALYSIS

SINGLE POINT MONITORING

SHUTTLE ASSUMED TO BE A SAFE HAVEN

IMMEDIATE SHUTTLE RETURN POSSIBLE

## TGA MISSION REQUIREMENTS

### LOCATION:

- SPACELAB EXPERIMENT RACK

### MISSION DURATION:

- 7 DAYS NOMINAL
- 30 DAYS MAXIMUM

### ANALYSIS RATE:

- ONCE EVERY 6 HOURS
- REPETITIVE

### REPLENISHMENT:

- FOUR 7 DAY MISSIONS
- ONE 30 DAY MISSION

### DATA STORAGE:

- ONE ANALYSIS CYCLE
- DATA DOWNLINKED ON COMMAND

## TGA INSTRUMENT DESCRIPTION

GAS CHROMATOGRAPH-MASS SPECTROMETER

BASED ON VIKING TECHNOLOGY

TWO STAGE SAMPLE ENRICHMENT

DUAL GC COLUMNS:

- ORGANIC COMPOUNDS
- CARBON MONOXIDE

GCMS INTERFACES:

- FLOW SPLIT (ORGANICS)
- PALLADIUM ALLOY SEPARATOR (CO)

DOUBLE FOCUSING MAGNETIC SECTOR MS

ION PUMP VACUUM SYSTEM

MICROPROCESSOR CONTROLLED

DIGITAL RECORDER DATA STORAGE

DOWNLINKED MASS SPECTRAL DATA

GROUND BASED DATA ANALYSIS

IN FLIGHT CALIBRATION WITH INTERNAL STANDARD.

## TGA PERFORMANCE SPECIFICATION

### COMPOUNDS:

- 8 CLASSES OF ORGANICS
- 40 COMPOUNDS SPECIFIED
- CARBON MONOXIDE

### DETECTION LIMIT:

- 0.5 PPM FOR BENZENE

### FULL SCALE:

- 1000 PPM (NOMINAL)

### REPEATABILITY:

(1 TO 1000 PPM) -- +/- 20%

### ANALYSIS CYCLE TIME:

(ORGANICS) -- 90 MINUTES

(CO) -- 30 MINUTES

WARM UP TIME: 25 MINUTES

POWER OFF PERIOD: 100 HOURS

## TGA COMPOUNDS

	M	S <sub>R</sub>	REQUIRED DETECTION LEVEL	MINIMUM DETECTION LEVEL
<u>ALCOHOLS</u>				
METHANOL	32	0.45	20.1	2.5
N-BUTANOL	74	0.38	4.9	2.0
N-PROPANOL	60	0.5	19.9	1.7
ISOBUTANOL	74	0.54	4.9	1.4
ISOPROPANOL	60	0.7	20.0	1.2
<u>ALDEHYDES</u>				
ACETALDEHYDE	44	0.29	5.0	3.4
ACROLEIN	56	0.29	0.02	3.0
BUTYRALDEHYDE	72	0.29	24.8	2.6
PROPIONALDEHYDE	58	0.54	25.0	1.6
<u>ALIPHATICS</u>				
1,3-BUTADIENE	54	0.63	50.0	1.4
1-BUTENE	56	1.04	99.8	0.8
ISOPRENE	68	0.54	99.8	1.5

## TGA COMPOUNDS (CONT'D)

	M	S <sub>R</sub>	REQUIRED DETECTION LEVEL	MINIMUM DETECTION LEVEL
<u>AROMATICS</u>				
ETHYLBENZENE	106	2.8	9.8	0.22
MESITYLENE	120	2.0	1.5	0.39
N-PROPYLBENZENE	120	3.0	4.9	0.20
STYRENE	104	1.3	9.9	0.49
M-XYLENE	106	1.0	9.9	0.63
BENZENE	78	1.5	0.5	0.49
TOLUENE	92	1.3	9.8	0.52
P-XYLENE	106	1.1	9.9	0.62
<u>ESTERS</u>				
BUTYLACETATE	116	2.9	20.0	0.30
ETHYLACETATE	88	2.0	26.4	0.34
ISOBUTYLACETATE	116	2.5	15.0	0.24
N-PROPYLACETATE	102	2.1	19.9	0.30

## TGA COMPOUNDS (CONT'D)

	M	S <sub>R</sub>	REQUIRED DETECTION LEVEL	MINIMUM DETECTION LEVEL
<u>HALOCARBONS</u>				
CARBON TETRACHLORIDE	152	0.32	0.16	1.6
CHLOROBENZENE	112	1.2	3.7	0.51
DICHLOROBENZENE	146	1.2	2.5	0.21
METHYLCHLORIDE	50	0.62	4.8	1.5
METHYLCHLOROFORM	132	0.34	0.18	1.7
TETRACHLOROETHYLENE	164	0.82	2.5	0.61
TRICHLOROETHYLENE	130	0.38	0.19	1.5
VINEYLIDENE CHLORIDE	96	1.0	0.5	0.66
1,2-DICHLOROETHANE	98	0.14	4.9	4.7
DICHLOROFLUOROMETHANE	102	2.2	49.9	0.29
METHYLENE CHLORIDE	84	0.83	12.4	0.85
<u>HETEROCYCLICS</u>				
1,4-DIOXANE	88	1.6	2.5	0.43
TETRAHYDROFURAN	72	0.88	9.8	0.87



## TGA COMPOUNDS (CONT'D)

	M	S <sub>R</sub>	REQUIRED DETECTION LEVEL	MINIMUM DETECTION LEVEL (1)
<u>KETONES</u>				
METHYLETHYLKETONE	72	1.3	4.7	0.59
METHYLISOBUTYLKETONE	100	1.4	4.9	0.46
<u>INORGANICS</u>				
CARBON MONOXIDE	28	1.0	13.0	

(1) PROJECTED DETECTION LEVEL ASSUMING A 10% RELATIVE ION INTENSITY MUST BE DETECTED WHEN THE GC CURVE IS AT 50% OF PEAK VALUE.

## TGA INTERFACE SPECIFICATIONS

POWER: 150 WATTS AVERAGE  
12 WATTS STANDBY

WEIGHT: 145 POUNDS

SIZE: 4 CUBIC FEET

CONFIGURATION: 19 INCH RACK MOUNT  
15.7 INCHES HEIGHT

INPUT POWER: 28 V PRIMARY  
28 V ESSENTIAL

CARRIER GAS VENT: SORBED ON PALLADIUM  
OXYDIZED TO WATER

DATA INTERFACES:

DATA--HRM EXPERIMENT CHANNEL  
DOWNLINK COMMAND--RAU CHANNEL  
TIMING-- RAU GMT  
RAU USER CLOCK

COOLING AIR: 41 KG/HR


OPERATOR: TURN ON ANALYSIS START  
PERIODIC/REPETITIVE

GROUND SUPPORT: TIME ZERO UMBILICLE

## TGA PACKAGE

- COMPACT MODULAR DESIGN


- VOLUME 4.0 FT<sup>3</sup> (0.11 M<sup>3</sup>)
- WEIGHT 135 POUNDS (61.3 KG)



- DESIGNED FOR 19.00" ELECTRONIC RACK MOUNT


ORIGINAL PAGE IS  
OF POOR QUALITY

# TGA SYSTEM MECHANICAL ASSEMBLY



ORIGINAL PAGE IS  
OF POOR QUALITY

# H.S. SUBSYSTEM TOP ASSEMBLY TOP VIEW



ORIGINAL PAGE IS  
OF POOR QUALITY

TGA PARAMETERS (CONTINUED)

CARBON MONOXIDE COLUMN-- (CONTINUED)

TEMP -- 50-100°C AT 10°C/MIN

OTHER -- SAME AS ORGANIC

SEPARATION -- NOT FULLY RESOLVED FROM NITROGEN TAIL

CARRIER GAS SUPPLY --

VOLUME -- 100 ATM LITERS

PRIMARY PRESSURE -- 1500 PSI

DELIVERY PRESSURE -- 200 PSI

CALIBRATION GAS--

FLUOROBENZENE (INT. STANDARD)

CARBON MONOXIDE	}	EVERY FOURTH ANALYSIS
CO WITH OXYGEN-18		

## TGA PARAMETERS

### GC SUBSYSTEM

#### ACCUMULATOR CELLS--

#1 -- 0.5 G TENAX GC  
0.1 G SPHEROCARB  
#2 -- 0.05 G TENAX GC  
0.02 G SPHEROCARB  
ENRICHMENT -- 300:1

#### ORGANIC COLUMN--

TYPE -- CAPILLARY  
LENGTH -- 0.375 MM ID  
MATERIAL -- STAINLESS STEEL  
STATIONARY PHASE -- WITCONOL  
CARRIER GAS -- HYDROGEN  
FLOW RATE -- 2 CC/MIN  
TEMP -- 40-120°C AT 2 /MIN HOLD AT 120°C  
RANGE -- METHANOL TO ORTHODICHLOROBENZENE  
SEPARATION -- ORTHO AND META XYLENE; PEAK WIDTH -- 7-10 S HPWH

#### CARBON MONOXIDE COLUMN--

TYPE -- PACKED  
LENGTH -- 4.5 M  
DIAMETER -- 0.75 MM  
STATIONARY PHASE -- MOLE SIEVE 5A

TGA PARAMETERS (CONTINUED) .

MASS SPECTROMETER

TYPE -- DOUBLE FOCUSING MAGNETIC SECTOR

GEOMETRY --  $90^{\circ}$  -  $90^{\circ}$  NIER-JOHNSON

MAGNETIC SECTOR RADIUS -- 1.5 IN

MAGNET -- 7 KG PERMANENT

MV PRODUCT -- 32,000

MASS RANGE -- 24-250 AMU

RESOLUTION -- 20% VALLEY AT 240

SCAN SPEED -- 4.4 S/DECADE

SENSITIVITY --  $2 \times 10^{-6}$  AMPS/TORR

ION SOURCE -- DUAL FILAMENT --

-- 50 CC/S

--  $225^{\circ}\text{C}$

ION CURRENT DETECTOR --

ELECTRON MULTIPLIER

BOX AND GRID TYPE

GAIN-- $10^4$



TGA PARAMETERS (CONTINUED)

ION PUMP

TYPE -- DIODE

DIFFERENTIAL SPUTTERING

CONFIGURATION -- SPLIT ANODE

SPEED -- 4 L/S FOR AIR  
15 L/S FOR AIR

VOLTAGE -- 4 KV

GAS LOAD -- 0.08 TORR-CC/S

### TGA TECHNICAL STATUS

GENERALLY MET EXPECTED PERFORMANCE FOR ORGANIC COMPOUNDS

DIFFICULT WITH THE GCMS INTERFACE FOR CARBON MONOXIDE

HYDROGEN SAFETY ISSUES RESOLVABLE

MINOR CHEMICAL REACTIVITY

ENGINEERING PROBLEMS FULLY RESOLVED

POSSIBLE SPACE STATION PREMISES

LONGER TERM EXPOSURE MAY REQUIRE LOWER CONCENTRATION LIMITS

WIDER RANGE OF COMPOUND TYPES INCLUDING INORGANICS

RAPID CATASTROPHIC EVENT ASSESSMENT

ANSWERS NEEDED ON BOARD

MORE COMPLEX EVENT PROTOCOL

MAY REQUIRE MORE INFO  
GREATER INSTRUMENT FLEXIBILITY

GREATER ANTICIPATORY CAPABILITY?

MULTI-POINT SAMPLING

## TGA IMPROVEMENTS/MODIFICATIONS

ELIMINATE THE CO COLUMN

-- REDUCE COMPLEXITY

GLASS OR SILICA COLUMN

-- REDUCE REACTIVITY PROBLEMS

INCREASED SAMPLE ENRICHMENT

-- PERMITS LOWER LEVEL DETECTION

-- DUAL ENRICHMENT MODES

MULTIPLE GC COLUMN OPERATING MODES

-- FLOW RATES

-- TEMPERATURE PROGRAMMING

DIRECT MS AND/OR ACCUMULATOR CELL MS MODE

-- FASTER ANALYSIS OF HIGHER LEVEL CONSTITUENTS

ON BOARD DATA ANALYSIS

-- REVERSE SEARCH

-- TIE TO ELUTION TIME

MULTI-POINT SAMPLING

-- TEFLON TRANSPORT LINES

-- SAMPLE CARTRIDGES

TGA IMPROVEMENTS/MODIFICATIONS (CONT'D)

ELIMINATE TAPE RECORDER

-- SOLID STATE MEMORY

BATTERY BACK-UP FOR VACUUM

CARRIER GAS RECOVERY

UPDATED DESIGN AND PACKING

-- SPACE STATION INTERFACES

-- MODULAR FOR MAINTAINABILITY

-- UPDATED COMPONENT SELECTION

SOME PROBLEMS ASSOCIATED WITH TRACE CONTAMINANT  
REMOVAL SYSTEMS FOR SPACECABINS

T. Wydeven

NASA

Ames Research Center


Moffett Field, CA 94035

3-62

INTRODUCTION

This talk summarizes some of the potential problems associated with acid gas sorbents, activated charcoal beds and the catalytic oxidizer proposed for spacecabin trace contaminant control.


# CONTAMINANT FLOW CYCLE IN CLOSED ATMOSPHERIC SYSTEM



ORIGINAL PAGE IS  
OF POOR QUALITY



# TRACE CONTAMINANT CONTROL SYSTEM PROPOSED FOR A SPACE STATION



3-65

ORIGINAL PAGE IS  
OF POOR QUALITY

# REPRESENTATIVE SPACECABIN CONTAMINANTS

Acetone  
 Acetaldehyde  
 Acetylene  
 Allyl Alcohol  
 Ammonia  
 Vinyl Alcohol  
 Benzene  
 n-Butane  
 Butene-1  
 cis-Butene-2  
 trans-Butene-2  
 n-Butyl Alcohol  
 Butyraldehyde  
 Butyric Acid  
 Carbon Disulfide  
 Carbon Monoxide  
 Chlorine  
 Chloroacetone  
 Chlorobenzene  
 Caprylic Acid  
 Chloropropane  
 Cyclohexane  
 Cyclohexanol  
 Cyanamide  
 1, 1-Dimethylcyclohexane  
 trans-1, 2-Dimethylcyclohexane  
 2, 2-Dimethylbutane  
 1, 4-Dioxane  
 Dimethylhydrazine  
 Ethyl Alcohol  
 Ethyl Acetate  
 Ethylene Dichloride  
 Ethylene  
 Ethylene Glycol  
 trans-1, 3-Ethylcyclohexane  
 Ethyl Sulfide  
 Ethyl Mercaptan  
 Freon-1  
 Freon-11  
 Freon-12  
 Freon-111  
 Freon-114  
 Freon-113 Unsym.  
 Freon-1

Formaldehyde  
 Hydrogen  
 Hydrogen Chloride  
 Hydrogen Fluoride  
 Hexene-1  
 n-Hexane  
 Hexamethylcyclotrisiloxane  
 Hydrogen Sulfide  
 Indole  
 Isopropyl Alcohol  
 Isobutyl Alcohol  
 Methylene Chloride  
 Methyl Chloroform  
 Methyl Ethyl Ketone  
 Methyl Isopropyl Ketone  
 Methyl Alcohol  
 3-Methyl Pentane  
 Methane  
 Monomethylhydrazine  
 Methyl Mercaptan  
 Nitric Oxide  
 Nitrogen Tetroxide  
 Nitrous Oxide  
 Propylene  
 Isopentane  
 n-Pentane  
 Propane  
 n-Propylacetate  
 Propyl Mercaptan  
 Phenol  
 Skatole  
 Sulfur Dioxide  
 Toluene  
 Trichloroethylene  
 Tetrachloroethylene  
 1, 1, 3-Trimethylcyclohexane  
 Tetrafluoroethylene  
 Freon-21  
 Valeric Acid  
 Vinyl Chloride  
 Vinylidene Chloride  
 m-Xylene  
 o-Xylene  
 p-Xylene

BOILING POINTS OF  
SPACECRAFT CONTAMINANTS

Component <sup>(1)</sup>	Normal Boiling Point, °C <sup>(2)</sup>
Acetonitrile ( $C_2H_3N$ )	81.8
Benzene ( $C_6H_6$ )	80.1
t-Butanol ( $C_4H_{10}O$ )	82.9
Cyclohexane ( $C_6H_{12}$ )	80.7
1,2-Dichloroethane	83.7
O-Dichlorobenzene ( $C_6H_4Cl_2$ )	179.0
Ethyl Acetate ( $C_4H_8O_2$ )	77.1
Freon 12	-30
Freon 113	48.2
Furan (Furfuran) ( $C_4H_4O$ )	32
Isopropanol ( $C_3H_8O$ )	82.5
Methyl Chloroform (1,1,1 Trichloroethane) ( $C_2H_3Cl_3$ )	74.2
Methylethylketone ( $C_4H_8O$ )	79.6
Vinyl Chloride ( $C_2H_3Cl$ )	-13.8

(1) Green, B. D. and J. I. Steinfeld, SPIE Vol. 99, Third European Electro-Optics Conference (1976), p. 32

(2)  $CO_2$  condenses (to solid) at  $-78.5^\circ C$  at 1 atm

## BASIC ADSORBENT BEDS AS ATMOSPHERIC CONTAMINANT REMOVAL DEVICES

- BASIC ADSORBENT BEDS HAVE BEEN SHOWN TO REMOVE –  
CO<sub>2</sub>, HCl, H<sub>2</sub>S, Cl<sub>2</sub> AND SO<sub>2</sub> WITH SOME EFFECTIVENESS AND  
TO BE INEFFECTIVE FOR NO<sub>2</sub>, CH<sub>3</sub>SH, AND CHF<sub>3</sub> (FREON 23)
- DATA ON ADSORPTION OF ALL CONTAMINANTS ON BASIC BEDS  
IS INCOMPLETE WITH RESPECT TO EFFECT OF TEMPERATURE,  
CO<sub>2</sub> CONC, HUMIDITY, CONTAMINANT CONCENTRATION, REACTION  
RATES, AND BED CAPACITIES – NO DATA IS AVAILABLE FOR  
MANY CONTAMINANTS



## CONTAMINANT CONTROL BY ADSORPTION ON BASIC BEDS

$\text{LiOH}$ ,  $\text{Li}_2\text{CO}_3$ ,  $\text{MnO}_2$ ,  $\text{Na}_2\text{CO}_3$ ,  $\text{CaCO}_3$

- PROBLEM OF DETERMINING WHAT SPECIES WILL BE ADSORBED AND WHAT CONDITIONS FAVOR ADSORPTION
- PROBLEM OF ADSORPTION RATE AND BED CAPACITY IN STOICHIOMETRIC GAS-SOLID REACTION

## IDENTIFIABLE RESEARCH AREA

INVESTIGATIONS SHOULD BE MADE OF

- THE RANGE OF CONTAMINANTS REMOVABLE BY A BASIC ADSORBENT BED
- THE STABILITY OF REMOVAL EFFICIENCIES FOR HCl, HF, Cl<sub>2</sub> AND F<sub>2</sub> IN EXTENDED SERVICE
- THE REASON FOR LOW NO<sub>2</sub> AND SO<sub>2</sub> REMOVAL EFFICIENCY
- TEMPERATURE AND HUMIDITY OPTIMIZATION AND THE COMPATIBILITY OF OPTIMIZED CONDITIONS WITH OTHER SUB SYSTEMS

# ATMOSPHERIC TRACE CONTAMINANT CONTROL BY CATALYTIC OXIDATION PROBLEM OF MULTIPLE OXIDATION PRODUCTS

- INLET SPECIES  
 $H_2O$ ,  $O_2$ ,  $NH_3$ ,  $RH$ ,  $RS$ ,  $RX$ ,  $RN$ ,  $N_2$
- REACTOR AT 300-700 F  
 $Pt$ ,  $Pd/Al_2O_3$  OR  $MnO_2$ ,  $CuO$ ,  $AgO$
- POSSIBLE RADICAL SPECIES IN BED  
 $R\cdot$ ,  $H\cdot$ ,  $O\cdot$ ,  $X\cdot$ ,  $N\cdot$ ,  $S\cdot$ ,  $O-O\cdot$ ,  $OH\cdot$
- POSSIBLE EFFLUENT SPECIES  
 $CO_2$ ,  $H_2O$ ,  $R=O$ ,  $R=\overset{O}{\underset{||}{C}}H$ ,  $HX$ ,  $NO$ ,  $N_2O$ ,  $NO_2$ ,  $N_2O_4$ ,  $N_2$ ,  $SO_2$ ,  $R'X$ ,  $X_2$
- HIGH TEMPERATURE NEEDED FOR DIFFICULT TO OXIDIZE SPECIES
- SPECIES FRAGMENTS IN REACTOR CAN COMBINE TO FORM NEW COMPOUNDS
- $H_2O + CO_2$  ARE DESIRED PRODUCTS BUT CANNOT BE FORMED BY  $X$ ,  $N$ ,  $S$  COMPOUNDS
- NUMBER OF ACTIVE SITES FOR OXIDATION OF ANY PARTICULAR SPECIES LIMITED BY COMPETITIVE ADSORPTION OF OTHER SPECIES
- SUSTAINED CATALYST ACTIVITY DEPENDS ON MAINTENANCE OF PHYSICAL STRUCTURE AND CHEMICAL ACTIVITY—AVOID SINTERING AND POISONING

## CATALYTIC OXIDATION OF ATMOSPHERIC TRACE CONTAMINANTS

### IDENTIFIABLE RESEARCH AREA

- EVALUATE THE DESIRABILITY AND EFFICIENCY OF CATALYTIC OXIDATION AS A TRACE CONTAMINANT CONTROL METHOD WHEN FEED GAS CONTAINS COMPOUND OF NITROGEN, SULFUR, AND THE HALOGENS
  - INVESTIGATE PRODUCT IDENTIFICATION AND MASS BALANCE WITH S, N, OR X COMPOUNDS IN FEED
  - INVESTIGATE TRANSIENT REDUCTIONS IN ACTIVITY OF CATALYST BED CAUSED BY S, N, OR X COMPOUNDS IN FEED.
  - INVESTIGATE PERMANENT LOSS IN CATALYST ACTIVITY OR POISONING FROM S, N, OR X COMPOUNDS IN FEED



**SPECIFIC PROBLEMS IN ATMOSPHERIC TRACE CONTAMINANT REMOVAL  
CONTAMINANT CONTROL BY ADSORPTION ON CHARCOAL BEDS**

**PROBLEM OF BLOCKING OF ADSORPTION OF LIGHTER  
(MORE VOLATILE) SPECIES BY**

- **HEAVIER (LESS VOLATILE) CONTAMINANT SPECIES**
- **CONTAMINANT SPECIES REACTING OR CHEMISORBING  
ON CHARCOAL**
- **WATER ADSORBED FROM HUMID INLET GAS STREAM**

ORIGINAL PAGE 18  
OF POOR QUALITY

## ATMOSPHERIC TRACE CONTAMINANT CONTROL BY ADSORPTION ON CHARCOAL BEDS

WORK TO DATE HAS SHOWN HUMIDITY OF INLET  
GAS STREAM MAY:

- REDUCE ADSORPTION
- ENHANCE ADSORPTION
- PREFERENTIALLY BLOCK SOME SPECIES
- CHANGE OPTIMUM BED TEMPERATURE FOR  
CONTAMINANT REMOVAL

## IDENTIFIABLE RESEARCH AREA: HUMIDITY EFFECTS

### INVESTIGATIONS ARE NEEDED TO:

- CONFIRM BLOCKAGE EFFECTS OF WATER VAPOR
- INVESTIGATE HUMIDITY EFFECTS IN ADSORPTION OF  $\text{SO}_2$ , DIMETHYL HYDRAZINE, MONO-METHYL HYDRAZINE, DIOXANE, CYANAMIDE, HCN, METHYL ETHYL KETONE,  $\text{N}_2\text{O}_4$ , ETHYLENE GLYCOL, ALLYL ALCOHOL AND OTHER POLAR CONTAMINANTS
- PROVIDE MORE RELIABLE GENERALIZED EXPRESSIONS FOR HUMIDITY EFFECTS TO AID DESIGN ANALYSIS FOR MISSION REQUIREMENTS

## NEED FOR FURTHER RESEARCH ON ATMOSPHERIC TRACE CONTAMINANT CONTROL METHODS

- NO ONE METHOD CAN DO COMPLETE TASK
- IMPORTANT PROBLEMS REMAIN LARGELY UNSOLVED. PREDICTION OF EFFECTS OF CONTAMINANT MIXTURES, HUMIDITY VARIATION AND OFF-DESIGN LOADS, BED REGENERATION AND LONG-TERM ACTIVITY
- MORE DEFINITIVE EXPERIMENTS ARE NEEDED TO PROVIDE THE DESIGN DATA NECESSARY FOR CONTAMINANT CONTROL SYSTEMS WITH:
  - HIGHER RELIABILITY FACTOR
  - BETTER USE OF WEIGHT AND VOLUME AVAILABLE
  - LOWER POWER PENALTY
  - GREATER MARGIN FOR COMFORT AND HEALTH
- INTERFACE MUST BE MAINTAINED BETWEEN CONTROL METHODS RESEARCH AND MATERIALS AND PHYSIOLOGICAL RESEARCH AND DESIGN ENGINEERING

# **CONTAMINATION CONTROL FOR INCREASED CREW PRODUCTIVITY**

**FEBRUARY 29, 1984**

Space Station Task Force  
Human Productivity Group  
NASA Ames Research Center  
Moffett Field, CA 94035

D.B. Heppner  
C.W. Miller

W 85-29555

## **SCOPE OF PRESENTATION**

- Contaminant Sources and Loading - Air/Water
- Contaminant Control - Air
- Contaminant Control - Water
- Other Factors Affecting Productivity
- Issues

## SPACE STATION CONTAMINANT SOURCES — AIR

CONTAMINANT	SOURCE	LOADING
Metabolic Products: CO <sub>2</sub> , NH <sub>3</sub> , CO, H <sub>2</sub> S, H <sub>2</sub> , CH <sub>4</sub> , Organic Acids, Mercaptans, Bacteriological Contaminants.	Crew & Animal	Continuous
Wide Variety of Alcohols, Aldehydes, Aromatics, Esters, Ethers, Chloro-carbons, Fluorocarbons, Halocar-bons, Hydrocarbons, Ketones, Acids.	Subsystems & Payloads	Continuous & Periodic
CO, CO <sub>2</sub> , Hydrocarbons, Aromatics, Acid Gases, Oxides of N <sub>2</sub> , SO <sub>2</sub> , NH <sub>3</sub> , Alcohols, Formaldehyde.	Emergencies — Spills, Equipment Failures, Fire	Short Term, High Rate


## SPACE STATION CONTAMINANT SOURCES — WATER

Water Source	Quantity Per Person-Day (lb)	Suspended Solids (PPM)	Dissolved Solids			Urea (PPM)	Micro-Organism
			Inorganics (PPM)	Organics (PPM)	Total (PPM)		
Fuel Cell	As required	0 <sup>(a)</sup>	10 to 424	0 <sup>(a)</sup>	10 to 424	0	No
Condensate		0 <sup>(b)</sup>	12 <sup>(b)</sup>	4 <sup>(b)</sup>	16 <sup>(b)</sup>	No	Yes <sup>(b)</sup>
		10 to 600 <sup>(a)</sup>	20 to 350 <sup>(a)</sup>	25 to 87 <sup>(a)</sup>	45 to 450 <sup>(a)</sup>	0 to 5 <sup>(a)</sup>	Yes
without SDAS	7.15 <sup>(e,f,g,h)</sup>						
with SDAS	14.15 <sup>(d,e,f,g,h)</sup>						
Shower	5 <sup>(f)</sup> , 8 <sup>(g,h)</sup>	160 <sup>(i)</sup>	90 <sup>(i)</sup>	1,030 <sup>(i)</sup>	1,120 <sup>(i)</sup>	15 <sup>(i)</sup>	Yes
		650 <sup>(i)</sup>	270 <sup>(i)</sup>	800 <sup>(i)</sup>	1,070 <sup>(i)</sup>	260 <sup>(i)</sup>	Yes
Handwash	7 <sup>(f)</sup> , 4 <sup>(g,h)</sup>	110 <sup>(i)</sup>	60 <sup>(i)</sup>	1,020 <sup>(i)</sup>	1,080 <sup>(i)</sup>	10 <sup>(i)</sup>	Yes
Laundry	27.5 <sup>(f,g,h)</sup>	210 <sup>(i)</sup>	180 <sup>(i)</sup>	1,010 <sup>(i)</sup>	1,190 <sup>(i)</sup>	5 <sup>(i)</sup>	Yes
Dish Wash		9,000 <sup>(i)</sup>	580 <sup>(i)</sup>	500 <sup>(i)</sup>	1,080 <sup>(i)</sup>	0	Yes
CO <sub>2</sub> Reduction Water	1.80					0	No
EVA Wastewater (lb/8 hr EVA)	9.68 <sup>(f,g,h)</sup>	(Same as Condensate)					
Urine	3.31 <sup>(f,g,h)</sup>	38,000	12,500 <sup>(k)</sup>	29,200 <sup>(k)</sup>	41,700 <sup>(k)</sup>	16,300 <sup>(k)</sup>	Yes
Urinal Flush	1.09 <sup>(f,g,h)</sup>						
Fecal Water	Not Identified						
<b>Standard</b>							
Wash Water Standard <sup>(l)</sup>					≤1,500	≤50	≤10
Potable Water Standard <sup>(l)</sup>					≤ 500		≤10
Potable Water Standard <sup>(m)</sup>					14	0	

(a) References noted in ( )



## CONTAMINANT LOADING PROFILE (TYPICAL)



## CONTAMINANT CONTROL — AIR

- CO<sub>2</sub> Removal
  - SDAS vs. EDC
  - EDC vs. LiOH
- H<sub>2</sub>O Removal
  - Water Vapor Electrolysis
  - Condensing Heat Exchanger
  - Desiccant
- Trace Contaminant Control
  - Normal, Loading Removal
  - High Contaminant Loading Removal
- Microbial
  - Surface Wipe

# REGENERATIVE CO<sub>2</sub> REMOVAL

## COMPARISON ELECTROCHEMICAL VS STEAM DESORBED AMINE<sup>(a)</sup>

### PRIOR COMPARISONS

Year	Organization	CO <sub>2</sub> Removal Subsystem Selected
1970	Ham. Std.	EDC equiv. wt. less than half IR-45 amine. Also cited amine problems: bed expansion/contraction, steam/CO <sub>2</sub> separation, steam generation, long term degradation.
1971	Rockwell	EDC selected over amines based on weight, power and heat rejection (1/3 other techniques) and ideally integrates with fuel cell and propulsion system.
1972	NASA JSC/ Ham. Std.	Selected EDC for SSP.
1973	McDonnell Douglas	EDC selected over amine based on lower weight, volume and power.
1976	NASA	Selected EDC for RLSE.
1979	NASA JSC	Selected EDC for Space Operations Center.

### ASSUMPTIONS

1. 4-Person Subsystem
2. 2.2 lb CO<sub>2</sub>/Person Day
3. Inlet pCO<sub>2</sub> = 3.0 mm Hg
4. Flight Prototype Level
5. Spares Not Included
6. Penalties, lb/W
 

Power:	0.71 (AC)
	0.59 (DC)
Heat Rej:	0.18 (Liq.)
	0.44 (Air)

### COMPARISON RESULTS

Category	EDC	SDAS	Comments
Fixed Hardware Wt., lb	92	139	All components incld. in both
Power Wt. Penalty, lb	49	577	461 of 577 for steam gen. & heat loss
Heat Rej. Wt. Penalty, lb	145	394	EDC rejects heat to liquid, amine to air
Subtotal	286	1,110	Amine 3.6 times greater than EDC
O <sub>2</sub> Generation Penalty, lb	309	0	EDC integrates with H <sub>2</sub> , O <sub>2</sub> & H <sub>2</sub> O utilities
Humidity Control Penalty, lb	102	770	Amine dumps 8 x H <sub>2</sub> O vapor into cabin
Water Processing Penalty, lb	27	206	Cabin condensate processing penalty
Total Eg. Wt., lb	724	2,086	Difference even greater as pCO <sub>2</sub> spec-dec.
Operation Cont. or Cyclic	Either	Cyclic	Amine continuously cycles cabin RH, T
Vary CO <sub>2</sub> Removal Rate	Yes	No	EDC tolerates crew changes
Maintainability	Cell	Canister	EDC maintainable at lower level
Humidifier Load, lb H <sub>2</sub> O/day	4	32	Increases redundant dehumidifiers
Water Recov. Sys. Load, H <sub>2</sub> O/day	4	32	Amine 8 times EDC
Noise	Negl.	Large	On/off amine compressor noisy

a. Details found in Life Systems' TR-604, 7/11/83, and SAE Paper No. 831120.

## REGENERATIVE vs. NON REGENERATIVE CO<sub>2</sub> REMOVAL COMPARISON OF ELECTROCHEMICAL vs. LITHIUM HYDROXIDE


	EDC	LiOH
Weight	724 lbs <sup>(1)</sup>	3600 lbs <sup>(2)</sup>
Volume	2.4 ft <sup>3</sup>	100 ft <sup>3</sup>
Power	0.14 kW	0.03 kW
Crew Time	0	105 hrs. <sup>(3)</sup>
Resupply Weight	0	1523 lbs
Resupply Volume	0	51.3 ft <sup>3</sup>

(1) Weight includes penalty for power, heat rejection, O<sub>2</sub> generation, humidity control, and water processing.

(2) Weight includes penalty for power.

(3) Crew time was calculated assuming changing seven canisters per day requiring ten minutes to locate canister, log out, remove exhausted canister, install new canister and stow old canister.

## WATER VAPOR REMOVAL — SYSTEMS CONSIDERATION




3-85

### Water Vapor Loading

	<u>lb/man-day</u>
Metabolic	4.02
Hygiene	0.94
Food Preparation	0.06
Experiments	1.00
Laundry	0.13
Sub-Total	6.15
EDC	1.00
Total	7.15

Heat Exchangers Required      1 per Module



### Water Vapor Loading


	<u>lb/man-day</u>
Metabolic	4.02
Hygiene	0.94
Food Preparation	0.06
Experiments	1.00
Laundry	0.13
Sub-Total	6.15
SDAS	8.00
Total	14.15

Heat Exchangers Required      1 per Module plus  
1 per SDAS

## **CONTAMINANT CONTROL TECHNIQUES EVALUATED BY LIFE SYSTEMS**

- Catalytic Oxidation
- Corona Discharge
- Regenerative Adsorption
- Thermal Decomposition
- Laser Decomposition
- Combustion
- Chemical Decomposition
- Microwave/Plasma Decomposition
- Membranes

## BASELINE SEQUENTIAL CATALYTIC OXIDATION CONCEPT




<sup>(a)</sup>Some agent breakdown will occur during heatup. Potentially installing a portion of the absorber material upstream of the first bed will further improve longevity.

<sup>(b)</sup>First catalyst bed expected to provide alternate decomposition modes even after primary mode (oxidation) is destroyed.

ORIGINAL PAGE IS  
OF POOR QUALITY

## CORONA DISCHARGE REACTOR/ POST-TREAT CONCEPT




3-88



## FOCUS OF CORONA DISCHARGE INVESTIGATIONS


- Available Data
  - Very Little Data Available
  - Currently Existing Laboratory Reactors Not Amenable to Scaleup
  - Post-Treat Concept Not Explored to Date
- Focus of Present Work
  - Design Lab Scale Breadboard Reactor Compatible With Scaleup
  - Expand Data Base Considerably
  - Improve Process Performance
  - Investigate Post-Treat Concept(s)

## TRACE CONTAMINANT CONTROL SUBSYSTEM FOR NORMAL LOADING REMOVAL



## TRACE CONTAMINANT CONTROL FOR HIGH LOADING REMOVAL

3-91



## TCCS SIZING FOR SPACE STATION

<u>Subsystem</u>	<u>Normal</u>	<u>High Loading Canister</u>	<u>High Loading Catalytic Oxidation</u>
Weight, lb	105	TBD	26
Power, W (continuous)	165	100	140
Volume, ft <sup>3</sup>	8.3	TBD	0.8
<u>Resupply (90 days)</u>			
Weight, lb	250	TBD	TBD
Volume, ft <sup>3</sup>	9.8	TBD	TBD

3-92

## CONTAMINANT CONTROL — WATER


- Biocide Addition
- Microbial Checkvalve
- UV/Ozonation
- Phase Change Water Recovery
- Filtration Water Recovery
- Open Loop Regenerative Fuel Cell

## WATER CONTAMINANT CONTROL OPTIONS

Sources	Treatment	Quality
Fuel Cell	Biocide Addition	Potable
Condensate CO <sub>2</sub> Reduction EVA CO <sub>2</sub> Reduction	Multifiltration, Biocide Addition	Potable
Shower Handwash	Filtration Water Recovery, Microbial Check Valve, Biocide Addition	Reuse
Laundry Dishwash Urine Urinal Flush	Phase Change Water Recovery, Multifiltration, Biocide Addition	Reuse
Reuse	UV/Ozonation, Biocide Addition	Potable
Reuse	Open Loop Regenerative Fuel Cell, Biocide Addition	Potable


ORIGINAL PAGE IS  
OF POOR QUALITY

## PHASE CHANGE WATER RECOVERY — VAPOR COMPRESSION DISTILLATION SUBSYSTEM



3-95


## BIOCIDE ADDITION AND MONITORING UNIT



ORIGINAL PAGE IS  
OF POOR QUALITY



## OPEN LOOP REGENERATIVE FUEL CELL — FOR SECONDARY WATER TREATMENT




## OTHER FACTORS AFFECTING PRODUCTIVITY

- Automation
  - Subsystem Interaction
  - Man in Loop
- Mechanical Integration
  - Subsystem
  - System
- Crew Time
  - LiOH
  - TCCS Cannister Design


# SPACE STATION AUTOMATION CONCEPT

3-99



## SUBSYSTEM INTEGRATION

### Trace Contaminant Control Subsystem



### Sensors


Description	Qty	Subsystem Symbol
Speed Sensor for Fixed Carbon Blower	1	S1
Speed Sensor for Regen. Carbon Blower	1	S2
Regen. Carbon Bed Temperature	2	T1
Catalytic Oxidizer Temperature	2	T2
Total	6	

### Actuators

Description	Qty	Symbol
Blower, Cabin Air	1	B1
Blower, Cat. Oxid.	1	B2
Heater, Regen. Carbon	1	H1
Heater, Cat. Oxid.	1	H2
Valves, Carbon Bed Isolation	2	V1, V2
Valve, Vacuum	1	V3
Total	7	

## MECHANICAL ENGINEERING INTEGRATION

### Packaging



ORIGINAL PAGE IS  
OF POOR QUALITY

# MECHANICAL COMPONENTS INTEGRATION PROGRAM

Sponsored By:  
Ames, Lewis,  
JSC: Crow & Power,  
Life Systems

## PURPOSE: Save Money By


1. Decreasing Subsystem Complexity
2. Decreasing Wt, Vol., Power,...
3. Increasing Reliability

## STATUS:

- 5 - Completed
- 1 - in Development
- 3 - Planned


Avg. Results	% Red:
No. Components	83
Power	68
Weight	83
Volume	83
No. Connections	64

No.	Mechanical Integration	Units Produced	Testing	
			Hours	Cycles
1	3-Fluids Pressure Controller	7	15,000	11,800
2	Coolant Control Assembly	7	11,500	8,600
3	Fluids Control Assembly (EDC)	3	20,000	14,000
4	Fluids Control Assembly (SFE)	8	2,400	1,000
5	2-Fluids Pressure Controller	1	0	0



ORIGINAL PAGE IS  
OF POOR QUALITY

- 3-1-01
- 18 Components → 1
  - 7 - Two-way Valves
  - 2 - Check Valves
  - 4 - Filters
  - 3 - Orifices
  - 2 - Press. Trans.
  - 24 W → 2
  - 11.4 lb → 4
  - 400 in<sup>3</sup> → 200



Assembled: 4.8 x 3.0 x 3.5 In

- Next Steps:
1. Applicability of Super Plastics
    - Injection Molding To Save \$
    - Considerably Lighter Weight
  2. Increase Maintainability
    - Onboard Replacement Unit


# 12 YEARS OF CONTINUOUS INTEGRATED ARS EXPERIENCE

Air Revitalization System Development	Timeframe												CO <sub>2</sub> Rem.	CO <sub>2</sub> Red.	O <sub>2</sub> Gen.	Dehumidification	N <sub>2</sub> Gen.	Capacity
	73	74	75	76	77	78	79	80	81	82	83	84	85	86				
Lab. Breadboard													EDC	Sab.	SFE	-	-	1
Lab. Breadboard													EDC	Bos.	-	-	-	4
Flight Breadboard (EARS)													EDC	-	WVE	WVE	-	1
Lab. Breadboard													EDC	Bos.	SFE	-	-	4
Lab. Breadboard													EDC	Sab.	SFE	-	-	1
✓ Flight Breadboard (ARX-1)													EDC	Sab.	SFE	Slupper	N <sub>2</sub> H <sub>4</sub>	1
✓ RLSE Preprototype (IARS)													EDC	-	WVE	WVE	-	3
✓ Flight Experiment Mockup													EDC	Sab.	SFE	Slupper	-	1
✓ Engineering Model													EDC	Sab.	SFE	Slupper	-	1
✓ Flight Demonstration													EDC	Sab.	SFE	-	-	1


✓ = Subsystems no longer retained as separate entities.

ORIGINAL PAGE IS  
OF POOR QUALITY


3-102



- CO<sub>2</sub> Removal
- O<sub>2</sub> Generation
- Dehumidification



- CO<sub>2</sub> Removal
- O<sub>2</sub> Generation
- Dehumidification
- CO<sub>2</sub> Reduction
- N<sub>2</sub> Generation



- CO<sub>2</sub> Removal
- O<sub>2</sub> Generation
- Dehumidification
- CO<sub>2</sub> Reduction

## Result: Life Systems Has Indepth Knowledge Of:


- ARS Functional & Component Performances
- Process Dynamics
- Water Handling: Feed & Condensate
- Interactions Between Controllers
- Importance of Simplifying
- Software Requirement & Development Times

**ALSO:** WE ARE INTEGRATING THE SFE AND SHUTTLE ORBITER FUEL CELL INTO RFCS BREADBOARD


## CONTAMINANT CONTROL TECHNIQUE AFFECTS CREW PRODUCTIVITY

LiOH Canister  
Storage (90 Days)

3600 lb.  
100 ft<sup>3</sup>  
630 Canisters



Logistics Module



LiOH Use  
5 Locations


Crew Time Reqd.

10 min/Canister  
7 Canister/Day  
105 hr/90 Days


ORIGINAL PAGE IS  
OF POOR QUALITY

3-103


## CANISTER OPTIONS VS. CREW TIME



Canister With  
2 Clamps



Canister With  
1 Clamp



Multiple Canisters  
With Common  
Manifold



## ISSUES REGARDING CONTAMINATION CONTROL

- Sources — Space Station Design and Selection of Materials and Subsystems
- Loading — Multiple Capacity Equipment for Normal and High Loading
- Control Techniques — Additional Studies, Evaluation and Testing
- Productivity Factors — Automation, Mechanical Integration, Crew Time

N85-29556

ORIGINAL PAGE 13  
OF POOR QUALITY

# SPACE STATION TASK FORCE

## HUMAN PRODUCTIVITY PROGRAM DEFINITION

D. E. CRAWER

C-6

# **HUMAN PRODUCTIVITY: WHAT IS IT?**

**THE USE OF MAN TO ATTAIN UTILITARIAN  
OBJECTIVES IN THE SPACE STATION SYSTEM**

ORIGINAL PAGE IS  
OF POOR QUALITY

## HUMAN PRODUCTIVITY: WHY NOW?

- EARLIER ATTEMPTS TO START A SPACE STATION PROGRAM HAD NO SUCH THRUST
- PRESENT SPACE STATION PLANNING IS CHARACTERIZED BY:
  - TECHNICAL ACTIVITIES TIED CLOSELY TO MISSION REQUIREMENTS -- USER NEEDS ACKNOWLEDGED
  - COMMERCIAL THEME MORE PROMINENT
  - COMMERCIAL USERS HAVE MORE DETAILED REQUIREMENTS
  - CUSTOMER DEMAND FOR HIGH EFFICIENCY AND AFFORDABILITY
- CURRENT NATIONAL CONCERN OVER U.S. PRODUCTIVITY
- NASA'S GOAL TO BECOME "A LEADER IN THE DEVELOPMENT AND APPLICATION OF ADVANCED TECHNOLOGY AND MANAGEMENT PRACTICES WHICH CONTRIBUTE TO SIGNIFICANT INCREASE IN BOTH AGENCY AND NATIONAL PRODUCTIVITY"

## HUMAN PRODUCTIVITY: PROGRAM GOAL

TO OPTIMIZE HUMAN PRODUCTIVITY ON THE  
SPACE STATION WITHIN THE EXISTING RESOURCES  
AND OPERATIONAL CONSTRAINTS

## HUMAN PRODUCTIVITY FLIGHT OBJECTIVES

---

- DEVELOP HABITABILITY WHICH:
  - SUSTAINS HUMAN PRODUCTIVITY ABOVE 90% OF INITIAL PERFORMANCE THROUGHOUT A TOUR OF 90 DAYS
- MAXIMIZE IVA CREW TIME:
  - CURRENT GOAL: 9 HOURS/DAY EXCLUDING WEEKENDS
- ESTABLISH EVA WHICH IS:
  - ROUTINE
  - RELIABLE
  - CONVENIENT
  - AND ABOVE ALL — CAPABLE
  - CURRENT GOAL: 8 HOURS/DAY FOR 4 CREW MEMBERS
- MAXIMIZE USE OF SHUTTLE TO VALIDATE NEW SYSTEMS

3-110

ORIGINAL PAGE 18  
OF POOR QUALITY

## HUMAN PRODUCTIVITY: PROGRAM STRATEGY (I)

---

- INTEGRATE CREW-RELATED ACTIVITIES AND FACILITIES INTO A SINGLE, WELL INTEGRATED, AND COORDINATED PROGRAM
- CONDUCT ITERATIVE COST/TRADE STUDIES
- IDENTIFY COST EFFECTIVE PROGRAM ELEMENTS
- INCREASE SAFETY AND PRODUCTIVITY OF HUMAN OPERATIONS
- MATCH RESOURCES

## HUMAN PRODUCTIVITY: PROGRAM STRATEGY (II)

---

- PROVIDE FOR WELL ORGANIZED CUSTOMER INVOLVEMENT
- DEVELOP A MULTI-CENTER ACTIVITY
- PROVIDE A FORUM FOR CENTER, INDUSTRY, AND UNIVERSITY INTERACTION
- ACCOMMODATE GROWTH AND EVOLUTION
- CARRY OUT AN EARLY, DETAILED DEFINITION

3-112

ORIGINAL PAGE 16  
OF POOR QUALITY



# HUMAN PRODUCTIVITY

## STEERING ELEMENTS

- MAN/MACHINE ROLES
- AUTONOMY FROM THE GROUND
- SAFETY
- HUMAN FACTORS ENGINEERING

## COMMON ELEMENTS

- ANTHROPOMETRICS
- INFORMATION MANAGEMENT
- COMMUNICATIONS
- INFLIGHT MAINTENANCE
- QUALITY ASSURANCE
- LOGISTICS
- INFLIGHT TRAINING SIMULATORS
- TOOLS

## WORK ELEMENTS

ORIGINAL PAGE IS  
OF POOR QUALITY

## CUSTOMER SERVICES ELEMENTS

## SPACE STATION SUPPORT ELEMENTS

### IVA SYSTEMS

- WORK STATIONS
- SPECIAL FACILITIES
- CUSTOMER PAYLOADS
- CUSTOMER OPERATIONS
- [EVA/IVA MAINTENANCE FACILITY]
- [USER LOGISTICS]

### EVA SYSTEMS

- SPACE SUIT & PLSS
- ORBITAL SERVICE UNIT
- MMU
- AIRLOCK
- WORK STATIONS
- CUSTOMER PAYLOADS
- CUSTOMER OPERATIONS
- SPECIAL AIDS
- [EVA RESTRAINTS/MOBILITY AIDS]
- [EVA TOOLS]
- [LOGISTICS]

### ARCHITECTURE

- RESTRAINTS/MOBILITY AIDS
- LAYOUT
- TRAFFIC FLOW
- COMPARTMENT DESIGN
- WINDOWS
- MODULARITY
- DECOR
- FURNISHINGS
- LIGHTING
- STORAGE

### CREW FACILITIES

- ECLSS
- PERSONAL HYGIENE
- WASTE MANAGEMENT
- CONTAMINATION
- FOOD SYSTEMS
- LAUNDRY
- CLOTHING
- VIBROACOUSTICS
- MEDICAL
- HEALTH MAINTENANCE/EXERCISE
- RECREATION/LEISURE
- SAFE HAVEN
- [PRIVATE COMMUNICATIONS]

### CREW ACTIVITIES

- ONBOARD TRAINING
- SCHEDULING/WORK INTEGRATION
- ORGANIZATIONAL SYSTEMS
- INVENTORY
- HOUSEKEEPING
- OFF-DUTY
- [LOGISTICS]
- [INFLIGHT MAINTENANCE]

### GROUND SUPPORT

- TRAINING
- SIMULATORS
- GROUND-BASED MONITORING
- SELECTION
- CUSTOMER ORGANIZATION
- EMERGENCY SUPPORT

## WORK GROUPS

DSG-675

## CONCEPTUAL DEFINITION - WHAT IS IT?

---

- PHASE A STUDY OF HUMAN PRODUCTIVITY PROGRAM
- COMPETITIVE PROCUREMENT INVOLVING AEROSPACE INDUSTRY
- CONCEPTUAL DEFINITION OF ENTIRE PROGRAM, EXCLUDING EVA SYSTEMS
- DEFINITION NOT SO DETAILED AS TO INVOLVE PROPRIETARY INFORMATION
- IDENTIFIES IMPORTANT TRADE STUDIES, CRITICAL ASSUMPTIONS, AND DESIGN ISSUES
- STARTS 10/84 AND ENDS 6/85
- EXTENSION OF THE ACTIVITIES OF THE HUMAN PRODUCTIVITY WORKING GROUP
- FEEDS INTO PHASE B CONTRACTS

ORIGINAL PAGE IS  
OF POOR QUALITY

3-114

## CONCEPTUAL DEFINITION - WHY DO IT?

---

THE HUMAN PRODUCTIVITY PROGRAM IS NEW -- A DEFINITION IS REQUIRED:

- TO PROVIDE INFORMATION/REQUIREMENTS INTO PHASE B STUDIES
- TO IDENTIFY LONG LEAD TECHNOLOGY
- TO IDENTIFY RESPONSIBILITY FOR WORK ELEMENTS
- TO COORDINATE THE DEVELOPMENT OF CREW FACILITIES AND ACTIVITIES
- TO LAY THE FOUNDATION FOR A COST EFFECTIVE APPROACH TO IMPROVING HUMAN PRODUCTIVITY

3-115

ORIGINAL PAGE IS  
OF POOR QUALITY

## CONCEPTUAL DEFINITION - PROCESS

---

INCLUDES ALL OF THE HUMAN PRODUCTIVITY PROGRAM:

- EXCLUDING EVA SYSTEMS WHICH ARE COVERED IN SEPARATE, PARALLEL CONTRACTS
- EMPHASIS ON BREADTH NOT DEPTH
- DEFINITION IS ITERATIVE STARTING WITH "STEERING" WORK ELEMENTS

PROCESS INVOLVES THE FOLLOWING DIVISIONS:

- WORK ELEMENTS INTO WORK UNITS
- WORK UNITS INTO TASKS
- PRIMARY EMPHASIS ON TASK LEVEL:

- OBJECTIVE
- DELIVERABLE
- APPROACH
- INPUTS
- ELEMENT COORDINATION
- ELEMENT DELIVERABLE DISTRIBUTIONS

- ENGINEERING TRADE STUDIES
- REQUIRED MANPOWER
- SPECIAL REQUIREMENTS
- REQUIREMENTS REFERENCE
- START DATE
- COMPLETION DATE

ORIGINAL PAGE IS  
OF POOR QUALITY

## CONCEPTUAL DEFINITION - PROCESS (Continued)

---

### CONTRACT DELIVERABLES:


- 1) REVIEW OF LITERATURE AND "LESSONS LEARNED"
- 2) CRITIQUE OF CURRENT PROGRAM CONTENT
- 3) CRITICAL ASSUMPTION INVOLVED IN THE CONCEPTUAL DEFINITION
- 4) INTEGRATED AND PRIORITIZED TRADE STUDIES
- 5) FINAL CONCEPTUAL DEFINITION OF HUMAN PRODUCTIVITY PROGRAM
- 6) DESIGN DRIVERS

3-117

ORIGINAL PAGE 18  
OF POOR QUALITY


# HUMAN PRODUCTIVITY PROGRAM DEFINITION PROCESS

3-118



DSG-659


## CONCEPTUAL DEFINITION - SCHEDULE



ORIGINAL PAGE IS  
OF POOR QUALITY



# HUMAN PRODUCTIVITY PROGRAM - CONCEPTUAL DEFINITION




3-120

ORIGINAL PAGE IS  
OF POOR QUALITY



## HUMAN PRODUCTIVITY PROGRAM - DEFINITION PROCESS



### HUMAN PRODUCTIVITY WORK ELEMENTS

**A1**

Task	Time	Resources	Notes
Identify Trade Studies			
Goal			
Deliverables			
Approach			
Inputs			
Element Coordination			
Element Distribution of Deliverables			
Manpower			
Special Requirements			

**A2**

Task	Time	Resources	Notes
Identify Trade Studies			
Goal			
Deliverables			
Approach			
Inputs			
Element Coordination			
Element Distribution of Deliverables			
Manpower			
Special Requirements			

#### WORK ELEMENT

- DESCRIPTION
- WORK UNIT SUMMARY
- WORK UNIT FLOW

**B1**

Task	Time	Resources	Notes
Identify Trade Studies			
Goal			
Deliverables			
Approach			
Inputs			
Element Coordination			
Element Distribution of Deliverables			
Manpower			
Special Requirements			

**B2**

Task	Time	Resources	Notes
Identify Trade Studies			
Goal			
Deliverables			
Approach			
Inputs			
Element Coordination			
Element Distribution of Deliverables			
Manpower			
Special Requirements			

#### WORK UNIT

- DELIVERABLES
- TASK SUMMARY
- TASK FLOW

#### TASK DESCRIPTIONS

- IDENTIFY TRADE STUDIES
- GOAL
- DELIVERABLES
- APPROACH
- INPUTS
- ELEMENT COORDINATION
- ELEMENT DISTRIBUTION OF DELIVERABLES
- MANPOWER
- SPECIAL REQUIREMENTS

**C1**

Task	Time	Resources	Notes
Identify Trade Studies			
Goal			
Deliverables			
Approach			
Inputs			
Element Coordination			
Element Distribution of Deliverables			
Manpower			
Special Requirements			

**C2**

Task	Time	Resources	Notes
Identify Trade Studies			
Goal			
Deliverables			
Approach			
Inputs			
Element Coordination			
Element Distribution of Deliverables			
Manpower			
Special Requirements			

ORIGINAL PAGE 18  
OF POOR QUALITY

DSG-691

## CONCEPTUAL DEFINITION - EXAMPLE

### WORK ELEMENT:

### VIBROACOUSTICS

### WORK UNITS:

#### NOISE AND VIBRATION CONTROL

#### NOISE AND VIBRATION EFFECTS

### TASKS:

1. INVENTORY OF SOURCES
2. INDIVIDUAL SOURCE MODELS
3. DISTRIBUTED SOURCE PREDICTION MODEL
4. AIRBORNE TRANSMISSION
5. REVERBERATION CHARACTERISTICS
6. STRUCTURE-BORNE TRANSMISSION
7. PATH MODEL
8. ABSORPTIVE MATERIALS
9. DAMPING
10. ACTIVE SUPPRESSION
11. SYSTEM NOISE PREDICTION/CONTROL

1. NAS CONSULTATION
2. PRESSURE/GRAVITY EFFECTS
3. TTS MEASUREMENTS
4. INTELLIGIBILITY IN NOISE
5. EVA/IVA HEARING PROTECTION
6. PRESSURE/GRAVITY/BACKGROUND EFFECTS ON VOICE SIGNAL
7. VOICE COMMAND SYSTEM PERFORMANCE
8. COMMUNICATION DEVICES EVA/IVA
9. COGNITIVE EFFECTS
10. ANNOYANCE/SLEEP
11. EVA/IVA TASKS
12. CREW SURVEY
13. CONTINUED NAS CONSULTATION

ORIGINAL PAGE 16  
OF POOR QUALITY

## HUMAN PRODUCTIVITY PROGRAM DEFINITION ELEMENT SUMMARY

WORK ELEMENT: VIBROACOUSTICS

WORK ELEMENT SUMMARY				WORK ELEMENT DESCRIPTION
WORK UNITS	START DATE	STOP DATE	MANPOWER/ MAN-YEARS	<p>The objective of the vibroacoustic work element is to develop a strategy which facilitates effective communication of human speech and controls noise generation and exposure on board the Space Station. To meet this objective, we must better characterize the generation and transmission characteristics of noise aloft and the physiological effects of noise exposure in space. Two basic approaches will be used: (1) The development of cost-effective acoustic engineering control measures and (2) the development of communication aids and countermeasures. Of these two approaches, the development of engineering control measures is the preferred method.</p> <p>Terrestrial data bases provide information on the effects of noise on auditory thresholds, intelligibility, task performance, comfort and sleep. However, vibroacoustic data bases need to be developed for the space environment because the present approach which relies on terrestrial analogs may not be adequate. In lieu of adequate flight data, terrestrial data will be used in strategy development which will subsequently be updated based upon in-flight experience.</p> <p>The overall objective of this work element is to develop the most cost-effective combination of engineering controls and communication aids and countermeasures.</p>
Noise and Vibration Effects	4th Qtr FY 84	End FY 89		
Noise and Vibration Control	FY 85	End FY 89		

3-123


 ORIGINAL PAGE IS  
OF POOR QUALITY

# HUMAN PRODUCTIVITY PROGRAM DEFINITION

## WORK UNIT FLOW

A2

WORK ELEMENT: VIBROACOUSTICS



3-124

# HUMAN PRODUCTIVITY PROGRAM DEFINITION WORK UNIT SUMMARY

WORK ELEMENT: VibroacousticsWORK UNIT: Noise and Vibration Effects

TASK SUMMARY							
TASKS	START DATE	STOP DATE	MANPOWER/ MAN-YEARS	TASKS	START DATE	STOP DATE	MANPOWER/ MAN-YEARS
NAS Consultation	4th Qtr FY 84	2nd Qtr FY 85		EVA/IVA Tasks	FY 86	FY 89	
Pressure/Gravity Effects	FY 85	FY 87		Crew Survey	FY 85	4th Qtr FY 85	
TTS Measurements	FY 85	FY 87		NAS Cont'd Consult.	FY 86	FY 90	
Intelligibility in Noise	FY 86	FY 87					
EVA/IVA Hearing Protection	FY 87	FY 89					
Pressure/Gravity/ Background Effects on Voice Signal	FY 85	3/4 FY86					
Voice Command System Performance	FY 86	FY 88					
Communication Devices EVA/IVA	3/4 FY86	FY 89					
Cognitive Effects	FY 85	3/4 FY86					
Annoyance	3/4 FY86	FY 88					

3-125


ORIGINAL PAGE IS  
OF POOR QUALITY

# HUMAN PRODUCTIVITY WORK UNIT TASK FLOW

B 2

WORK ELEMENT: VIBROACOUSTICS  
WORK UNIT: NOISE AND VIBRATION EFFECTS  
TASK: \_\_\_\_\_

3-126





# HUMAN PRODUCTIVITY PROGRAM DEFINITION WORK UNIT SUMMARY

WORK ELEMENT: VibroacousticsWORK UNIT: Noise and Vibration Control

TASK SUMMARY							
TASKS	START DATE	STOP DATE	MANPOWER/ MAN-YEARS	TASKS	START DATE	STOP DATE	MANPOWER/ MAN-YEARS
Inventory of Sources	3/4 FY 84	3/4 FY 86		System Noise Prediction/Control	FY 87	FY 90	
Individual Source Models	FY 85	3/4 FY 87					
Distributed Source Prediction Model	3/4 FY 86	3/4 FY 88					
Airborne Transmission	FY 85	FY 87					
Reverberation Characteristics	FY 85	FY 87					
Structure-Borne Transmission	FY 85	FY 87					
Path Model	FY 87	3/4 FY 89					
Absorptive Materials	FY 85	FY 87					
Damping	FY 85	FY 87					
Active Suppression	3/4 FY 85	3/4 FY 88					

3-127

ORIGINAL PAGE IS  
OF POOR QUALITY

# HUMAN PRODUCTIVITY WORK UNIT TASK FLOW


B2

WORK ELEMENT: VIBROACOUSTICS

WORK UNIT: NOISE AND VIBRATION CONTROL

TASK: \_\_\_\_\_

3-128





## HUMAN PRODUCTIVITY PROGRAM DEFINITION TASK FORM

WORK ELEMENT: VibroacousticsWORK UNIT: Noise and Vibration ControlTASK: Inventory of Sources

**GOAL:** Determine the anticipated type of noise sources (e.g.) fans, pumps, etc.), estimate the number and nature of noise sources per module and the total acoustical energy generated.

**DELIVERABLE(S):** An inventory of the anticipated noise sources on Space Station including the acoustic spectrum and use profile of each source.

**APPROACH:** Carefully review Skylab, Spacelab, Skylab, Salyut, etc. as analogs. Space Station configurations and operations will then be studied to estimate the nature and magnitude of the various anticipated noise sources.

**INPUTS:**

1. Information on noise generation and transmission in space vehicles.
2. Known noise sources.
3. Anticipated noise sources.

**ELEMENT  
COORDINATION:**

1. ECLSS
2. Thermal
3. IVA - Work Stations; customer payloads
4. EVA - Airlock; orbital service unit
5. Personal hygiene
6. Health maintenance
7. Safe haven      8. Attitude and Orbital Control

**ELEMENT DISTRIBUTION  
OF TASK DELIVERABLES:**


Intermediate work unit product.

3-129

 ORIGINAL PAGE IS  
OF POOR QUALITY

## MANPOWER/MAN-YEARS

ENGINEERING TRADE STUDIES	GENERIC: _____ TEST BED: _____ FOCUSED TECHNOLOGY: <u>2 MY</u> FLIGHT TEST: _____ PROTOTYPE TECHNOLOGY: _____
(1) Distribution of noise sources relative to human activities  (2) Engineering alternatives to meet the functions associated with noise sources  (3) Utilization alternatives to meet the functions associated with noise sources  (4) Engineering alternatives to source isolation	<u>SPECIAL REQUIREMENTS</u>  1. NEW FACILITIES:  2. UNIQUE SKILLS: Knowledge of acoustics, and Space Station Systems and their operations  3. SPECIAL HARDWARE:  4. SPECIAL INFORMATION: Detailed design information on noise generating machinery in Shuttle, Skylab, and Spacelab  START DATE: <u>4th Quarter FY 84</u>  COMPLETION DATE: <u>Mid FY 86</u>  REQUIREMENTS DOCUMENT REFERENCE: 6.11.2.2.1B



ORIGINAL PAGE IS  
OF POOR QUALITY

N85-29557

VGL920

# THE HUMAN ROLE IN SPACE (THURIS)



ORIGINAL PAGE 16  
OF POOR QUALITY

Harry L. Wolbers, PhD  
Thuris Study Manager  
(714) 896-4754



## THE HUMAN ROLE IN SPACE

### Three Factors to Consider

#### ■ Performance —

- Where Along the Continuum From Direct Human Intervention, to Teleoperators, to Remotely Actuated and Controlled Systems, to Independent (Self-Actuating/Self-Healing Operations), Can The System Requirements Best Be Met?

#### ■ Cost —

- If Alternative Implementation Concepts Are Feasible, Which Is the Most Cost Effective?

#### ■ Risk —

- What is the Success Probability, or Conversely, What Is the Risk or Impact of System Failure?



## **PRESENCE OF CREW WAS ESSENTIAL TO SKYLAB MISSION SUCCESS**

VG0999


- **Assembled and Set Up Equipment**
- **Conducted Pre-Operations Tests (Checkout) of Experiment Equipment**
- **Performed Interactive Operations — Real-Time Display and Data Analysis to Determine Next Operation**
- **Management — Changed Ops Plans Due to “Surprises”**
- **Conducted Malfunction Tests**
- **Maintained and Repaired Subsystems**
- **Modified Instruments**
- **Analyzed and Interpreted Results**
- **Conducted Ground/Space Cooperative Tests**
- **Made Visual Observations — Discrimination**
- **Developed “Work-Arounds” — Heat Shield, Solar Array Deployment**
- **Recovered Payloads**
- **Assembled Large Experiments/Equipment From Parts**
- **Recovered Film**



## CAPABILITIES PROVIDED BY MAN

VFM203N

3-135



ORIGINAL PAGE IS  
OF POOR QUALITY

ORIGINAL PAGE IS  
OF POOR QUALITY

**SAR IMAGE — SANTA BARBARA CHANNEL**







## **OCEANOGRAPHIC EFFECTS DISCOVERED FIRST FROM MANNED SPACECRAFT**

VGG375

### **EDDIES**

- Existence at Coastal Boundaries (Gemini)
- Size Variability in Confined Seas (Apollo)
- Distribution Along Current Edges (Skylab)
- Kelvin-Helmholtz and Von Karman Vortices — Island Wakes (Apollo and Skylab)
- Scale Variability (Skylab)
- Surface Manifestation of Warm and Cold Core Eddies (Skylab and ASTP)
- Coalescence (Skylab)
- Associated Cloud Formations (Skylab)

### **FRONTS**

- Surface Manifestations of Fronts (Gemini — ASTP)
- Fronts and Thermal Boundaries (ASTP)
- Mesoscale Turbulence at Frontal Boundaries (Skylab)
- Plankton Distribution (Skylab)
- Wave/Front Interaction (Skylab)



# **OCEANOGRAPHIC EFFECTS DISCOVERED FIRST FROM MANNED SPACECRAFT**

VGG376

## **INTERNAL WAVES**

- Distribution Along Shelf Break (Apollo 6)
- Configuration Over Shelf (Apollo 6)
- Existence In the Open Ocean (Skylab)
- Extent and Configuration Along Ocean Fronts (Skylab)

## **OCEAN SWELL**

- Refraction and Absorption at Current Boundaries (Skylab)
- Refraction In Fjords (Skylab)
- Dissipation at Upwelling Boundaries (Skylab)

## **UPWELLING**

- Configuration of Upwelling Boundaries (Apollo, Skylab)

## **CURRENTS**

- Current Confluence and Retention of Identity (Skylab)



## **BENEFITS OF MAN IN ORBIT**

### **Scientist/Observer**

- **Real-Time Data Analysis**
- **Multiple Sensor Use**
- **Sensor Mode/Parameter Selection**
- **Cooperation With Principal Investigator**
- **Target Selection**

### **Development Engineer**

- **Sensor Operation**
- **Sensor Evaluation**
- **Component Testing**

### **Technical Operations Specialist**

- **Equipment Setup, Checkout, Maintenance, Calibration**
- **Servicing of Sensor and Equipment Consumables**



VFX881


# CONCERNS OF MAN IN ORBIT

## Safety of Flight

- External Environment
- Physiological Limits
- Psychological Stress
- Onboard Safety

## Performance Degradation

- Acceleration Disturbances
- Effluent Release
- Repetitive Duty Cycles




**SPACE PLATFORM**

3-141


ORIGINAL PAGE IS  
OF POOR QUALITY

# SPACE PLATFORM SYSTEM DESIGN CONCEPT

VFT332



# CANDIDATES FOR EVA ACTIVATION



ORIGINAL PAGE IS  
OF POOR QUALITY

- Latches/Supports Required for Ascent/Descent Only
- Costs — EVA Versus Mechanisms

## EVA VERSUS MECHANISMS


- Initial Survey Found 15 Candidate Mechanisms That Could be Done by an EVA Crewman
- Survey Criteria:
  - Low Activation Cycles
  - No Free-Flight Activation Requirement
  - EVA Activation is Safe
- Candidates:
  - Forward Launch Supports (1 Total)
  - Solar Array Launch Latches (2 Total)
  - Radiator Latches (3 Total)
  - +Y and -Y Berthing Ports (4 Total)
  - Aft Berthing Port (3 Total)
  - Ku Band Antenna (2 Total)




# PAYLOAD BERTHING PORT (X-AXIS)

VGB362

3-145




**Remotely Actuated  
Deployment Mechanism**



**Manually Actuated (EVA)  
Deployment Process**

ORIGINAL PAGE IS  
OF POOR QUALITY

ORIGINAL PAGE IS  
OF POOR QUALITY



3-146

## EVA VS MECHANISMS

VGB353

### ■ Reduction of Automatic Mechanisms

● Forward Launch Support	\$133K
● Solar Array Launch Latches	1051K
● Radiator Launch Restraints	401K
● + Y and -Y Berthing Port Mechanisms	266K
● Aft Berthing Port Mechanisms	344K
● Antenna Launch Latch	211K

<b>TOTAL COSTS FOR 15 MECHANISMS = \$2406K</b>
--

- Manual Activation to Perform the Functions of the Above-  
Stated Mechanisms Involves 2 EVA Crewman Approximately  
2.5 Hours Which is Well Within the Capability of  
EVA Operations

EVA Costs (Per EVA Crewman) = \$60K-100K, Depending  
on EVA Support Equipment\*

\$60K X 2 Crewman = \$120K

<b>\$100K X 2 CREWMAN = \$200K</b>
------------------------------------

\*Per MMU Users Guide, Martin Marietta Report MCR-78-517  
(Contract NAS9-14593)

## **CRITERIA FOR SELECTING COMMERCIAL MISSIONS**

VGB376

- **High Market Value**
- **High Value Per Pound**
- **Not Labor Intensive**
- **Requires Unique Properties of Space**
- **Low Probability of Rapid Technological Obsolescence**


# CANDIDATE PHARMACEUTICAL PRODUCTS

## 12 TYPICAL

VGB325

Typical Products	Beneficial Medical Application	Function/Status	Annual Patients (USA)
$\alpha_1$ Antitrypsin	Emphysema	Research Quantities Only Now	100,000
Antihemophilic Factors VIII and IX	Hemophilia	100% Terminal by Age 40	20,000
Beta Cells	Diabetes	Possible Single-Dose Cure	600,000
Epidermal Growth Factors	Burns	Replacement Skin Grafting	150,000
Erythropoietin	Anemia	Replacement Transplants/Transfusions	1,600,000
Immune Serum	Viral Infections	EOS Provides Higher Purity	185,000
Interferon	Viral Infections	Potential May Be Unlimited	> 10,000,000
Granulocyte Stimulating Factor	Wounds	Research Quantities Only Now	2,000,000
Lymphocytes	Antibody Production	Replace Antibiotics/Chemotherapy	600,000
Pituitary Cells	Dwarfism	Currently Not Curable	850,000
Transfer Factor	Leprosy/Multiple Sclerosis	Potential for Other Applications	550,000
Urokinase	Blood Clots	Low Development Costs	1,000,000

# ELECTROPHORESIS OPERATIONS IN SPACE



3-150

## Flight Dates Under Joint Endeavor Agreement

STS 4	JUN	1982
STS 6	APR	1983
STS 7	JUNE	1983
STS 8	AUG	1983
STS 14	JUN	1984
STS 19	OCT	1984

## Results From First STS Flights

1. 700 Times Increase in Yield
2. Quantitatively Repeatable Separation
3. Validated Design Concepts
4. Value of Manned Participation Confirmed

ORIGINAL PAGE IS  
OF POOR QUALITY

# STS-4 EOS OPERATIONS SUMMARY

VGB351

	28 June 1982	30 June 1982
<b>Raw Parameters</b>		
Total Operating Time	6.5 Hours	8 Hours
Total Number of CPU Operator Calls	27	28
Scheduled Calls	19	22
Unscheduled Calls	8	6
Total Number of Keyboard Inputs Required	99	83
Scheduled Calls	48	72
Unscheduled Calls	51	11
<b>Averaged parameters</b>		
Operator Calls/Hour	4	3
Scheduled Calls	3	3
Unscheduled Calls	1	1
Keyboard Inputs/Hour	15	10
Scheduled Calls	3	3
Unscheduled Calls	6	2
Operator Call Response Time	27 Sec	43.7 Sec

**Manned Presence Essential to Reduce Risk of Failure**






# TYPICAL SPACE PHARMACEUTICAL PILOT PLANT

(Manned Involvement: Circled Letters)


VFL135N



ORIGINAL PAGE IS  
OF POOR QUALITY

# TYPICAL TIMELINE PHARMACEUTICAL PILOT PLANT AND CREW OPERATIONS

VFL136N



- (A) Thaws Cell Mixture and Suspends in Electrophoresis Buffer Solution
- (B) Introduces Cell Suspension Into Electrophoresis Unit and Collects Separated Products
- (C) Discards Unwanted Products. Centrifuges Wanted Cells a Number of Times — Resuspending Cells in Fresh Wash Water Between Centrifugations
- (D) Prepares Cell Cultures on Growth Medium in Culture Plates
- (E) Transfers Cell Colonies to Production Medium and, After Approximately 30 Days, Removes Cells by Centrifugation
- (F) Separates Pharmaceutical From Production Medium Via Successive Processes (e.g., Liquid Chromatography, Dialysis, and Ultrafiltration)
- (G) Lyophilizes Pure Pharmaceutical and Stores

# ATTRIBUTES OF A MANNED SPACE STATION

VGB708


- **Schedule Compression — Reduced Cost and Risk**
- **Combines Best Features of Unmanned Free-Flyer and Sortie Mission, e.g.,**
  - Onboard Step-by-Step Development Sequence
  - Less Automation
  - Reduced Cost — No Free-Flyer Support Subsystems, Fewer Shuttle Launches
  - Common Support Equipment
  - Unlimited Data Gathering — Test Conduct Time — Flexibility
  - Infrequent Event — Seasonal Coverage
- **Flight Crew Capabilities —**  
**Modifications/Repair/Replacement/Assembly**
  - Visual Observations
  - Real-Time Sensor Adjustments
  - Analyzing Data
  - Pointing Control
  - Targets of Opportunity
  - Failure Diagnosis/Repair
  - EVA for Structural Assembly — Equipment Adjustments
  - Iterative Operations
  - Learning Curve Benefits
- **Contribution of Man in Space is Historical Fact**

**Man Responds Creatively as  
Unanticipated Events or  
Problems Arise**



VGG338

# STUDY METHODOLOGY



**Study Goal** -- Rational Methodology For  
Optimizing Human Role in Space  
**Criteria** -- Performance -- Cost -- Risk

ORIGINAL PAGE 16  
OF POOR QUALITY



VGG372

# THURIS STUDY SCHEDULE


Study Tasks	Study Months												Total Man-Months
	1	2	3	4	5	6	7	8	9	10	11	12	
1.0 Human Qualifications	1	1											2
2.0 Specific Project Assessments	2	2	2	2	2	2	2						14
2.1 Project Analysis													
2.2 Mission Time Lines													
2.3 Support Requirements													
2.4 Econometrics													
2.5 Evaluation													
3.0 Technology Requirements								2					2
4.0 Human Roles in Space									2				2
Study Documentation										2	1	1	4
Totals (Contract Funds)	3	3	2	2	2	2	2	2	2	2	1	1	24
Milestones	ATP				Midterm Briefing					Final Briefing		Final Reports	

ORIGINAL PAGE IS  
OF POOR QUALITY



# TASK I — HUMAN QUALIFICATIONS FOR SPACE ACTIVITIES

VGG343



ORIGINAL PAGE IS  
OF POOR QUALITY





## TYPICAL LIST OF BASIC HUMAN CAPABILITIES

VGG345

### A. Sensory/Perceptual

- Visual acuity
- Detection and discrimination of brightness
- Color detection and discrimination
- Depth perception at close range
- Static depth perception at a distance
- Peripheral visual detection and discrimination
- Visual accommodation
- Detection and discrimination of tone
- Detection and discrimination of sound intensity
- Localization of sound
- Detection of tone duration
- Auditory detection and discrimination of motion
- Discrimination of tone patterns
- Detection of light touch
- Tactile recognition
- Discrimination of texture
- Detection and discrimination of force against limb
- Recognition of location of limb
- Detection and discrimination of movement of limb
- Detection and discrimination of angular acceleration
- Detection and discrimination of linear acceleration
- Detection and discrimination of vibration
- Detection of heat and cold
- Perception of pain
- Olfaction

### B. Cognitive

- Decision-making
- Problem solving (invention)
- Association (long- and short-term memory)
- Deduction
- Induction
- Guided performance
- Learned procedure
- Perceptual set
- Reading
- Speaking
- Writing
- Speech perception
- Recording
- Time perception
- Assessment of volume of space
- Discrimination of complex pattern
- Complex visual generalization and discrimination

### C. Psychomotor

- Arm/hand/finger control of force
- Arm/hand/finger control of speed of motion (including reaction time)
- Leg control of force
- Control of mass in motion (loop behavior)
- Damped tracking (visual)
- Visual-motor tracking

### D. Motor

- Arm/hand/finger manipulation
- Body positioning



VGL395

# HUMAN CAPABILITY

CATEGORY – SENSORY/PERCEPTUAL CAPABILITIES SENSORY MODALITY – VISION				
HUMAN CAPABILITY	DEFINITION	CHARACTERISTICS	LIMITING FACTORS	REFERENCES
BRIGHTNESS DETECTION AND DISCRIMINATION (CONT)			<ul style="list-style-type: none"> <li>– REGION OF RETINA STIMULATED</li> <li>– LEVEL OF ILLUMINATION ON TEST</li> </ul>	
COLOR DISCRIMINATION	<p>HUE DISCRIMINATION – THE ABILITY TO DETECT THE SMALLEST DIFFERENCE IN WAVELENGTH OF TWO TEST FIELDS</p> <p>BRIGHTNESS DISCRIMINATION – DEFINED ABOVE</p> <p>SATURATION DISCRIMINATION – THE ABILITY TO DETECT SMALL DIFFERENCES IN THE PERCENTAGE OF WHITE LIGHT IN TWO FIELDS OF IDENTICAL HUES</p>	<p>BLUE – 2.5 nm</p> <p>GREEN – 1.0 nm</p> <p>YELLOW – 3.3 nm</p> <p>ORANGE – 1.5 nm</p> <p>RED – 20.0 nm</p> <p>TOO DIFFICULT TO MEASURE FOR ACCURATE THRESHOLDS</p>	<ul style="list-style-type: none"> <li>• COLOR OF LIGHT SOURCE</li> <li>• COLOR OF LIGHT REFLECTED FROM NEARBY SURFACES</li> <li>• LEVEL OF ILLUMINATION</li> <li>• SURFACE REFLECTIVITY CHARACTERISTICS</li> </ul>	1, 6, 11, 15, 17
DEPTH PERCEPTION AND DISCRIMINATION	THE ESTIMATE OF THE DISTANCE OF AN OBJECT FROM THE OBSERVER, OR THE RELATIVE DISTANCE OF TWO OR MORE OBJECTS, OR THE DIFFERENCE IN PARALLAX CORRESPONDING TO THE MINIMUM DISTANCE TWO OBJECTS CAN BE DISPLACED ALONG THE LINE OF SIGHT AND STILL BE RECOGNIZED AS BEING AT DIFFERENT DISTANCES	<p>JUDGMENT OF ABSOLUTE DISTANCE IS VERY INACCURATE</p> <p>JUDGMENT OF RELATIVE DISTANCE IS VERY ACCURATE</p> <p>ANGULAR DIFFERENCES AS SMALL AS 2 sec OF PARALLAX CAN BE DETECTED</p> <p>EFFECTIVE USE OF UNAIDED STEREOPSIS (BINOCULAR DISPARITY) IN DEPTH PERCEPTION LIMITED TO A DISTANCE OF 15 TO 20 ft. BEYOND 20 ft, JUDGMENT OF DEPTH OR DISTANCE IS PRIMARILY DEPENDENT ON MONOCULAR CUES</p>	<ul style="list-style-type: none"> <li>• DISTANCE OF OBJECTS FROM THE EYE</li> <li>• ABSENCE OF OBJECTS OF KNOWN SIZE FOR COMPARISON</li> <li>• ATMOSPHERIC CONDITIONS</li> <li>• ILLUMINATION INTENSITY</li> <li>• STIMULUS SIZE</li> <li>• MONOCULAR VERSUS BINOCULAR CUES</li> </ul>	6, 13, 17, 18





# LIMITING FACTORS

VGL578

Stress Factor: Space Adaptation Syndrome (Exposure to Weightlessness)							
Human Capabilities Impacted	Duration of Exposure						
	Less Than 3 Hours	3-12 Hours	12-24 Hours	24-48 Hours	48-72 Hours	72-96 Hours	More Than 96 Hours
Threat to Life or Consciousness	None	None	None	Neg	Neg	Neg	None
Visual Acuity	None	Mod	Neg	Neg	Neg	None	None
Depth Perception	None	Mod	Neg	Neg	Neg	None	None
Visual Accommodation	None	Mod	Mod	Neg	Neg	None	None
Tactual Discrimination	None	Mod	Mod	Neg	Neg	None	None
Discrimination of Angular Acceleration	Neg	Mod	Sig	Sig	Sig	Sig	Sig
Cognition	None	Sig	Sig	Mod	Neg	Neg	None
Memory	None	Neg	Neg	None	None	None	None
Evaluation	None	Mod	Sig	Mod	Neg	None	None
Arm/Hand/Finger/Control of Force and Speed of Motion	Mod	Sig	Sig	Sig	Mod	Neg	None
Visual-Motor Tracking	Mod	Sig	Sig	Mod	Neg	Neg	None
Arm/Hand/Finger Manipulation	None	Sig	Sig	Mod	Mod	Neg	None
Body Positioning	Mod	Sig	Sig	Mod	Mod	Neg	None

Impact Code  
(Decrease in Observed Capability)

None (None)  
Negligible (Neg)  
Moderate (Mod)  
Significant (Sig)



# MANNED SPACEFLIGHT EXPERIENCE

VGL398

MISSION ACTIVITY	GENERIC ACTIVITIES INCLUDED	COMMENTS	DOCUMENT
<ul style="list-style-type: none"> <li>• OVERRIDE CONTROL ACTIVATED TO OPEN SHUTTER ON STAR TRACKER</li> </ul>	<ul style="list-style-type: none"> <li>• IDENTIFY ABNORMALITIES</li> <li>• ANALYZE DATA</li> <li>• DEFINE PROCEDURES/SCHEDULES</li> <li>• IMPLEMENT PROCEDURES/SCHEDULES</li> <li>• MEDIATIONAL PROCESSING</li> </ul>	<ul style="list-style-type: none"> <li>• STAR TRACKER SHUTTERS NOT CYCLING OPEN AND CLOSED AS EXPECTED</li> <li>• CREW ANALYZED PROBLEM, SHUTTER NOT RESPONDING TO AUTO CONTROL</li> <li>• MANUAL OVERRIDE OF SHUTTER BY CREW SOLVED PROBLEM</li> </ul>	<p>STS-1 ORBITER MISSION REPORT JSC 17378 AUGUST 1981</p>
<ul style="list-style-type: none"> <li>• RESET OPEN RMS TV CIRCUIT BREAKER</li> </ul>	<ul style="list-style-type: none"> <li>• ACTIVATE/INITIATE SYSTEM OPERATION</li> <li>• OPERATE SYSTEM</li> <li>• INSPECT/OBSERVE</li> <li>• CONNECT ELECTRICAL INTERFACE</li> <li>• INSPECT/OBSERVE</li> <li>• ANALYZE DATA</li> </ul>	<ul style="list-style-type: none"> <li>• DURING DAY 2 RMS OPERATIONS, THE RMS WRIST/ELBOW TV CAMERA CIRCUIT BREAKER OPENED</li> <li>• CREW RESET BREAKER</li> <li>• RESETTING BREAKER DID NOT SOLVE PROBLEM</li> <li>• TROUBLESHOOTING ISOLATED PROBLEM TO EXCESSIVE CURRENT DRAW BY ELBOW TV CAMERA</li> </ul>	<p>STS-2 ORBITER MISSION REPORT JSC 17959 FEBRUARY 1982</p>
<ul style="list-style-type: none"> <li>• METRIC CAMERA (GERMAN EXPERIMENT) FAILED ON STS-9/SL-2</li> <li>• SECOND CASSETTE JAMMED ON 25TH FRAME OF 400</li> <li>• DATA LINK BETWEEN JSC, CAMERA FIRM IN GERMANY, AND FLIGHT CREW SET UP</li> <li>• JSC GROUND CREW DEVISED, FIXED, AND WALKED FLIGHT CREW THROUGH PROCEDURES TO REPAIR JAM</li> <li>• CAMERA PUT BACK ON LINE BY FLIGHT CREW</li> </ul>	<ul style="list-style-type: none"> <li>• IDENTIFY ABNORMALITIES</li> <li>• DEACTIVATE/TERMINATE SYSTEM OPERATION</li> <li>• RELEASE LATCH</li> <li>• REMOVE/OPEN COVERING</li> <li>• INSPECT/OBSERVE</li> <li>• COMMUNICATE INFORMATION</li> <li>• CORRELATE DATA</li> <li>• GATHER TOOLS/EQUIPMENT</li> <li>• RESOLVE ABNORMALITIES</li> <li>• REPLACE/CLOSE COVERING</li> <li>• CLOSE LATCH</li> <li>• ACTIVATE/INITIATE SYSTEM OPERATION</li> <li>• REPLACE TOOLS/EQUIPMENT</li> </ul>	<ul style="list-style-type: none"> <li>• STS-9/SL-1</li> <li>• METRIC CAMERA (GERMAN) SECOND FILM CASSETTE JAMMED</li> <li>• JSC GROUND LINKED TO ZEISS CAMERA IN GERMANY AND TO STS-9/SL-1 CREW</li> <li>• REPAIR PROCEDURES WORKED OUT IN REAL TIME AT JSC</li> <li>• RELAYED TO CREW TO EFFECT REPAIR</li> </ul>	<p>AVIATION WEEK AND SPACE TECHNOLOGY DECEMBER 19, 1983</p>
<ul style="list-style-type: none"> <li>• SOYUZ 23 (OCT 1976) AUTOMATIC DOCKING FRUSTRATED</li> <li>• SOYUZ 24 (FEB 1977) MANUAL DOCKING ACHIEVED</li> </ul>	<ul style="list-style-type: none"> <li>• ADJUST/ALIGN ELEMENTS</li> <li>• CONFIRM/VERIFY PROCEDURES/SCHEDULES</li> <li>• CORRELATE DATA</li> <li>• DETECT CHANGE IN STATE OR CONDITION</li> <li>• TRACKING (CONTINUOUS ADJUSTMENT)</li> <li>• POSITION MODULE</li> <li>• INSPECT/OBSERVE</li> </ul>	<ul style="list-style-type: none"> <li>• SOYUZ 24 DOCKED MANUALLY WITH SALYUT 5</li> <li>• SOYUZ 23 WAS "FRUSTRATED" (FAILED) WITH ITS AUTOMATIC DOCKING SYSTEM IN EARLIER ATTEMPT</li> </ul>	<p>SPACEFLIGHT VOL 19, NO. 5 MAY 1977</p>

3-162



# BENEFIT OF MAN'S PARTICIPATION IN MISSION ACTIVITIES

VGL577.1

Life Science Mission Activities	Recommended Man/Machine Category	Evaluation of the Benefit of Man's Participation			Assessment of Onboard Participation	Skill Type and Level Required for Man's Participation	Reasons for Conclusions Regarding Benefits of Man's Participation
		Equipment Can Be Eliminated	Performance of Activity Is Improved	Probability of Mission Success is Improved			
Monitor Rat Colony	Supported	●	●	●	Beneficial	Biological Technician	Man Onboard Can Treat Sickness and Remedy Malfunctions
Replenish Supplies	Manual	●	—	●	Beneficial	Minimal Training	Equipment Mass and Volume Significantly Increased by Automation
Remove and Process Urine Samples	Supported,	●	—	●	Beneficial	Biological Technician	Increase in Equipment Mass and Complexity If Samples Automatically Processed
Measure Mass of Rat	Augmented	●	●	●	Essential	Minimal Training	Extremely Difficult to Design Intra-Habitat Mass Measurement System
Acquire, Process, and Store Rat Blood Samples	Augmented	—	●	●	Essential	Biological Technician	No Feasible Method Is Available for Blood Sample Acquisition Without Man
Sacrifice Rats and Acquire Tissue Samples	Supported	—	●	●	Essential	Skilled Scientist/ Technician	Exposure of Rats in Habitats to Lethal Chemical Preservative Not Realistic Alternative

3-163



VGG352

## TASK 2 — SPECIFIC PROJECT ASSESSMENT

### SUBTASKS

2.1 — SELECTED PROJECT ANALYSIS

2.2 — TIME LINES

- PROGRAM
- PROJECT
- MISSION
- SEQUENCE

2.3 — HUMAN SUPPORT REQUIREMENTS

2.4 — ECONOMIC OF HUMAN ACTIVITIES

2.5 — EVALUATION

### PRODUCTS

Activity Work Sheets

Hardware Description Sheets

Human Performance and Cost Data Summary Sheet

MDAC Costing Data Bank


3-164

ORIGINAL PAGE IS  
OF POOR QUALITY



VGL917

# SPACE PLATFORM PROJECT ANALYSIS





## GENERIC SPACE ACTIVITIES

1. Activate/Initiate System Operation
2. Adjust/Align Elements
3. Allocate/Assign/Distribute
4. Analyze/Compute Data
5. Apply Biomedical Sensor
6. Communicate Information
7. Confirm/Verify  
Procedures/Schedules/Operations
8. Connect/Disconnect Electrical Interface
9. Connect/Disconnect Fluid Interface
10. Correlate Data
11. Deactivate/Terminate System Operation
12. Decode Data
13. Define  
Procedures/Schedules/Operations
14. Deploy Appendage
15. Detect Change in State or Condition
16. Display Data
17. Encode Data
18. Extract Data
19. Gather Tools/Equipment
20. Handle/Inspect/Examine Living  
Organisms
21. Identify Abnormalities
22. Implement Procedures/Schedules
23. Inspect/Observe
24. Measure (Scale) Physical Dimensions
25. Mediational Processing
26. Perform Fine Motor Manipulations
27. Plot Data
28. Position Module
29. Release/Secure Mechanical Interface
30. Remove/Open Covering
31. Remove Biomedical Sensor
32. Remove Module
33. Replace/Close Covering
34. Replace/Clean Surface Coatings
35. Replace Tools/Equipment
36. Replenish Materials
37. Retract Appendage
38. Store/Record Data
39. Tracking (Continuous Adjustment)
40. Transport Loaded
41. Transport Unloaded



## GENERIC SPACE ACTIVITIES (CONT)

VGL919

Activities	Source					
	AXAF	(1) Skylab	(2) Space Platform	Space Station	(3) Arm's Study (MIT)	Life Sciences Laboratory
1. Activate/Initiate System Ops	●	●	●	●	●	●
2. Adjust/Align Elements		●		●	●	●
3. Allocate/Assign/Distribute		●	●	●	●	●
4. Analyze/Compute Data		●	●	●	●	●
5. Apply Biomedical Sensor		●		●	●	●
6. Communicate Information	●	●	●	●	●	●
7. Confirm/Verify Proced/Sched/Ops		●	●	●	●	●
8. Connect/Disconnect Elec Interface		●	●	●	●	●
9. Connect/Disconnect Fluid Interface		●	●	●	●	
10. Correlate Data		●	●	●	●	●
11. Deactivate/Terminate Sys Ops	●	●	●	●	●	●
12. Decode Data			●	●	●	
13. Define Proced/Sched/Ops		●	●	●	●	●
14. Deploy Appendage	●	●	●	●	●	
15. Detect Change in State or Cond		●		●	●	●
16. Display Data		●	●	●	●	●
17. Encode Data			●	●	●	
18. Extract Data			●	●	●	●
19. Gather Tools/Equipment	●	●	●	●	●	●
20. Handle/Inspect/Examine						●
21. Identify Abnormalities		●	●	●	●	●

(1) Includes EREP and ATM Activities

(2) Includes Activities Derived From the Analysis of Space Platform GroundSystem Data Management Study

(3) Includes 330 Generic Functional Elements Derived From the Geosynchronous Platform, Advanced X-Ray Astrophysics Facility, Teleoperator Maneuvering System and Space Station

ORIGINAL PAGE IS  
OF POOR QUALITY



# GENERIC SPACE ACTIVITIES

VGL918

3-168

Activities	Source					
	AXAF	(1) Skylab	(2) Space Platform	Space Station	(3) Arm Study (MIT)	Life Sciences Laboratory
22. Implement Proc/Sched		•	•	•	•	•
23. Inspect/Observe		•	•	•	•	•
24. Measure (Scale)		•			•	
25. Mediatonal Processing		•		•		•
26. Perform: Fine Motor Manip		•		•		•
27. Plot Data		•	•	•		•
28. Position Module	•	•	•	•	•	•
29. Release/Secure Mech Interface	•	•	•	•	•	•
30. Remove/Open Covering		•	•		•	•
31. Remove Biomedical Sensor		•		•	•	•
32. Remove Module	•	•	•	•	•	•
33. Replace/Close Covering		•	•		•	•
34. Replace/Clean Surf. Coat.	•		•			•
35. Replace Tools/Equipment	•	•	•	•	•	•
36. Replenish Materials	•	•		•	•	•
37. Retract Appendage	•	•	•	•	•	
38. Store/Record Data		•	•	•	•	•
39. Tracking (Cont Adjust.)				•	•	•
40. Transport Loaded	•	•	•	•	•	•
41. Transport Unloaded	•	•	•	•	•	

(1) Includes EREP and ATM Activities

(2) Includes Activities Derived From the Analysis of Space Platform GroundSystem Data Management Study

(3) Includes 330 Generic Functional Elements Derived From the Geosynchronous Platform, Advanced X-Ray Astrophysics Facility, Teleoperator Maneuvering System and Space Station





## CATEGORIES OF MAN-MACHINE INTERACTION

VGL403


3-169

<b>MANUAL</b>	Unaided IVA/EVA, With Simple (Unpowered) Hand Tools
<b>SUPPORTED</b>	Requires use of Supporting Machinery or Facilities to Accomplish Assigned Tasks (e.g., Manned Maneuvering Units and Foot Restraint Devices)
<b>AUGMENTED</b>	Amplification of Human Sensory-Motor Capabilities (Powered Tools, Exo-Skeletons, etc)
<b>TELEOPERATED</b>	Use of Remotely Controlled Sensors and Actuators Allowing the Human Presence to Be Removed From the Work Site (Remote Manipulator Systems, Teleoperators, Telefactors)
<b>SUPERVISED</b>	Replacement of Direct Manual Control of System Operation With Computer Directed Functions Although Maintaining Humans in Supervisory Control From <u>Ground-Based</u> or <u>Orbital Based</u> Work Stations
<b>INDEPENDENT</b>	Basically Independent Self Actuating, Self-Healing Operations but Requiring Human Intervention Occasionally (Automation and Artificial Intelligence)



## DEPLOY APPENDAGE

VGL393



### \*Skill Level

Normal Skills (Norm) — Task Falls Within the Realm of Standard Training/Basic Knowledge

Specialized Skills (Spec) — Task Requires Special Training or Specific Knowledge of the Activity



## REFERENCE SOURCES

- ① **McDonnell Douglas Astronautics Company, Alternative System Design Concept Study (Space Platform/Power System), Contract NAS8-33955, DR Numbers 1-16, July, 1982**
- ② **Space Platform Ground System Study — Final Report, 7/21/82, Ford Aerospace and Communications Corporation. (Subcontract to MDAC Under NAS8-33955)**
- ③ **Space Station Program Description Document — Book Number 6, Appendix B, Operations Studies, Second Level White Pages, 8/83, Space Station Operations Working Group, NASA-KSC**
- ⑦ **Space Maintenance and Contingency Operations Simulation Neutral Buoyancy Testing (NB-51) — Final Report, MDC H0190, MDAC-HB, 5/83**
- ⑧ **McDonnell Douglas Astronautics Company Engineering Estimate**
- ⑨ **National Aeronautics and Space Administration, Johnson Space Center, Mission Planning and Analysis Division, The 25-Kilowatt Power System — Baseline Reference Mission, JSC 17066, February 1981**



# COST FACTOR ASSIGNMENT TO MAN-MACHINE INTERACTION CATEGORIES

VGL401

Cost Factors	Categories of Man-Machine Interaction					
	Manual	Supported	Augmented	Teleoperated	Supervised	Independent
1. Prorated Facility Costs	●	●	●	●	●	●
2. Prorated Transp Costs	●	●	●	●	●	
3. Orbital Supt Equip Costs	●	●	●	●	●	
4. Automated Equip Costs						●
5. Gnd Supt Equip Costs				●	●	●
6. Gnd Supt Operations				●	●	●
7. Training Requirements	●	●	●	●	●	
8. Software Support Costs			●	●	●	●
9. Crew Rotation Rates	●	●	●	●	●	
10. Duty Cycles	●	●	●	●	●	
11. Operation Times	●	●	●	●	●	●
12. Logistics Requirements	●	●	●	●	●	
13. Emergency Provisioning	●	●	●	●	●	
14. Hazardous Ops Provisioning	●	●	●			

3-172



## TASK 3 — TECHNOLOGY REQUIREMENTS

VGG363

- Technology Gaps

Human Support  
Requirements  
From Task 2.3

Technology Gaps

Currently  
Planned  
Technology  
Developments

- Technology Risk  
Assessment

Risk Assessment  
Data Sheets

- Technology Plan

Technology Requirements  
Forecasting/Planning  
Sheets



## TASK 4 — ROLE ALLOCATIONS

VGG339

Generic Activity	Failure Effect*	Categories of Man-Machine Interactions																	
		Manual			Supported			Augmented			Tele-operated			Supervised			Independent		
		\$	T	C	\$	T	C	\$	T	C	\$	T	C	\$	T	C	\$	T	C
A — Deploy Appendage	1	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
B — Position Module	2	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
C — Connect Electrical Interface	1	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—

\*Failure Effect Rating

- 1 = Mission Loss
- 2 = Minimal Data Return
- 3 = Significant Data Return
- 4 = Minor Effect

- \$ — Cost Per Unit of Time (From Task 2)
- T — Estimated Time For Activity (From Task 2)
- C — Confidence of Estimate (Risk) — (From Task 3)

Select Lowest Expected Cost Path

- Compute  $(\$)(T)/(C)$
- Test:  $T \leq T_{max}$ ,  
 $C \geq C_{min}$

ORIGINAL PAGE IS  
OF POOR QUALITY



## STUDY ACCOMPLISHMENTS TO DATE

106 Reference Documents Reviewed to Date

### Task 1 — Completed

- Documentation of Human Capabilities/Limitations
- Historical Precedents and Operational Experiences

3-175

### Task 2 — In Process

- Six Space Project Areas Reviewed
- Generic List of 41 Basic Activities Developed
- Timeline Profiles and Mission Impact Factors Established for 20 of 41 Activities
- Preliminary Listing of Human Support Equipment Completed
- Early Start on Economic Assessment of Human Activities in Space
- Fourteen Factors Impacting Costs Identified
- Philosophy for Allocating Costs Established

Tasks 3 and 4 — No Work Scheduled as yet per Study Plan

THURSDAY

		Page
Overview	M. Cohen	4-1 to 4-27
A Preliminary Human Factors Planning and Design Outline of Parameters Related to Space Station Windows and CCTV Monitoring	R. Haines	4-28 to 4-40
View graphs re SS Windows	R. Haines	4-41 to 4-59
Johnson Space Center Configurations	J. Lewis	4-60 to 4-72
Man Machine Trade-Off Study	A. Feinberg	4-73 to 4-82
Some Ideas and Questions Regarding Space Station Design	S. S. Kolnick	4-83 to 4-91
Underseas Habitat Design	T. Taylor and J. Spencer	4-92 to 4-107
Considerations for SS Interior Architecture	B. Griffin	4-108 to 4-170
ECLSS Module Concept	C. Poythress	4-171 to 4-184
Habitability Sleep Accommodations	H. Fisher	4-186 to 4-197
Design of Confined Environments	M. Kalil	4-198
Customer and Mission Influences on Space Station Architecture	F. Runge	4-199 to 4-215



SEMINAR ON  
SPACE STATION HUMAN PRODUCTIVITY

OVERVIEW:  
HUMAN FACTORS ISSUES IN  
SPACE STATION ARCHITECTURE

MARC M. COHEN, ARCHITECT  
SPACE HUMAN FACTORS OFFICE, LHS  
NASA-AMES RESEARCH CENTER  
MAIL STOP 239-2  
MOFFETT FIELD, CA. 94035  
(415) 965-5385 FTS 448-5385

MARCH 1, 1984

ORIGINAL PAGE IS  
OF POOR QUALITY

85-29558

# SPACE STATION PROGRAM STATUS

"NO DESIGN DECISIONS  
HAVE BEEN MADE"

3/1/84

Hans Mark 2/10/84

TWO YEARS OF INTENSIVE STUDY  
1984 - 1985

TARGET FIRST LAUNCH DATE: 1991

JOHNSON SPACE CENTER (JSC):  
LEAD CENTER FOR DEVELOPMENT

AMES RESEARCH CENTER (ARC):

- SPACE HUMAN FACTORS OFFICE FORMED (9/83)
- AERO-SPACE HUMAN FACTORS DIVISION  
FORMED IN REORGANIZATION OF MVSORD  
(2/84)

## SPACE STATION PROGRAM ASSUMPTIONS

1. ALL PARTS OF STATION WILL BE LAUNCHED  
IN SHUTTLE PAYLOAD BAY -  
~14'-0" MAX. O.D. X ~45' MAX. LENGTH.
2. STATION WILL FLY IN LOW EARTH ORBIT,  
(LEO) ~200-300 MILE ALTITUDE AT  
LOW INCLINATION, ~28.5°
3. SOLAR PHOTOVOLTAIC POWER, ~75 KW.
4. ZERO-GRAVITY (NO ARTIFICIAL G.).
5. BUDGET FOR INITIAL OPERATING  
CAPABILITY (I.O.C.) IS \$8.0 BILLION  
OVER ~8 YEARS, AND INCLUDES  
2 UNMANNED PLATFORMS, SVCE. STRUCT.  
EVA, MMLIS & OMS/TMS

## CONCEPT DEVELOPMENT GROUP I.O.C. MODEL:

### 1. AUTONOMY:

90 DAYS WITHOUT STS REVISIT  
5 DAYS W/O ROUTINE GROUND SUPPORT  
24 HOURS W/O ANY COMM. FROM GROUND

### 2. CREW:

6-8 PEOPLE ON 90 DAY TOURS  
MIXTURE OF PILOT, MISSION & PAYLOAD TYPES

### 3. COMMAND & CONTROL:

COMPLETELY DISTRIBUTED TO EACH MODULE  
NO "BRIDGE"

### 4. SAFETY:

"SINGLE PERCEIVED LEVEL", WITH DISTR.  
SAFE HAVENS TO SUPPORT ENTIRE CREW  
FOR 21 DAYS.

# 1) SPACE HUMAN FACTORS

- FOR WORKING & LIVING ENVIRONMENTS
- "MAXIMIZE HUMAN PRODUCTIVITY":
  - CREW PERFORMANCE
  - IVA TIME AVAILABLE FOR PAYLOADS
  - ROUTINE EVA → 1,000 HOURS/YEAR
- NEW SPACE MISSION CHARACTERISTICS:
  - LONG DURATION, REPEATED TOURS OF DUTY
  - PERMANENT HABITATION WITH AUTONOMY
  - HIGH LEVELS OF AUTOMATION, MAN/MACHINE INTERACTION & USE OF ROBOTICS
- COMMERCIALIZATION:
  - COTTAGE INDUSTRY OR MASS PRODUCTION?
  - DIVERSE ACTIVITIES

## 2) ARCHITECTURE


"Architecture is a social art. It becomes an instrument of fate because it not only caters to requirement but also shapes and conditions our responses. It can be called reflective because it mirrors a program of conduct and living. At the same time this art of a planned environment does more, it also programs our daily conduct and our entire civilized life. It modifies and often breaks earlier established habit."

- Richard Neutra, SURVIVAL THROUGH DESIGN, (Oxford University Press) 1954. Page 314.

### 3) VOLUME

- MOST CRITICAL SINGLE H.F. ISSUE:
  - MOST CONSTRAINED BY EXTERNAL LIMITS.
  - AFFECTS ENTIRE HABITABILITY BASELINE.
  - CELENTANO CURVES.
- EFFORTS TO REDUCE COSTS BY MINIMISING VOLUME PRESENT A FALSE ECONOMY.
- EFFECTS OF INADEQUATE VOLUME:
  - FORCE MINIATURIZATION OF MANY ITEMS.
  - PRECLUDE MUCH "OFF-THE-SHELF" HARDWARE.
  - IMPEDE, IMPAIR OR PREVENT ON-ORBIT MAINTENANCE.
  - DRIVE UP DESIGN, ENGINEERING, FABRICATION & INTEGRATION COSTS BEYOND THE INITIAL SAVINGS.
  - DIMINISH CREW PERFORMANCE & COMFORT.

# J. T. CELENTANO: HABITABLE VOLUME REQUIREMENTS PER PERSON




NASA-Ames Research Center  
Space Human Factors Office




## 4) REFERENCE ORIENTATION

- ONE POINT  
(SOVIET EVA PROTOCOL)
- TWO POINT  
(LOCAL VERTICAL IN SKYLAB OWS, SPACELAB)
- THREE POINT (2-D)  
(RAFT TYPE STATION ASSEMBLY)
- FOUR POINT (3-D)  
("DELTA" CONFIGURATION)
- PLANAR (S.O.C. TYPE) STATION OPTIONS


# PLANAR SPACE STATION REFERENCE ORIENTATION OPTIONS




1 SHORT AXIS UP



2 FLOORS ALL COPLANAR




3 LONG AXIS UP  
(ORIGINAL S.O.C., J.S.C.)




4 UP AWAY FROM CENTER

NASA-Ames Research Center  
Space Human Factors Office

4-11



ONE POINT  
REFERENCE ORIENTATION




REPORTED SOVIET EVA PROTOCOL  
FOR TETHERED OPERATIONS


NASA-Ames Research Center  
Space Human Factors Office

ORIGINAL PAGE IS  
OF POOR QUALITY


IN-BETWEEN



**TWO POINT  
REFERENCE ORIENTATION**



**SPACELAB**




**SKYLAB**


**"LOCAL VERTICAL"  
IN SKYLAB AND  
SPACELAB**

NASA—Ames Research Center  
Space Human Factors Office

4-13




THREE POINT  
REFERENCE ORIENTATION




"VERTICAL RAFT"  
SPACE STATION

NASA-Ames Research Center  
Space Human Factors Office




FOUR POINT  
REFERENCE ORIENTATION

"BALONEY SLICE"



"HOT DOG"






JSC "DELTA"  
CONFIGURATION

NASA-Ames Research Center  
Space Human Factors Office

## 5) CIRCULATION

- SKYLAB EXPERIENCE SHOWS 3 ASPECTS:
  1. CONNECTION BETWEEN VOLUMES
  2. PENETRATION THROUGH VOLUMES
  3. DIVISION OR SEPERATION OF VOLUMES
- BIOLOGICAL ANALOGIES -  
TRADITION IN CITY PLANNING
  - SCALELESSNESS & COMPLEXITY
  - FIGURE/GROUND AMBIGUITY
  - CENTER/END VS CENTER/PARTS CIRCULATION
- FIVE CIRCULATION CONDITIONS - DEFINITIONS
  1. ACCESS
  2. MULTIPLE ACCESS
  3. EGRESS
  4. DUAL EGRESS
  5. DUAL REMOTE EGRESS


# SKYLAB CIRCULATION CHARACTERISTICS




NASA—Ames Research Center  
Space Human Factors Office




## ACCESS AND EGRESS DEFINITIONS




(a) ACCESS




(b) MULTIPLE ACCESS



(c) EGRESS



(d) DUAL EGRESS



(e) DUAL REMOTE EGRESS

NASA-Ames Research Center  
Space Human Factors Office

## 6) PRIVACY

- MANDATORY FOR "STAYING SANE IN SPACE"
- INDIVIDUAL CONTROL (PERSONAL DOMAIN)  
VITRUVIUS'S DEFINITION: "INVITATION"
- COMMUNITY CONTROL BY  
"LOCKS" & SEPERATIONS BETWEEN DOMAINS
  1. ENTRY LOCK
  2. DIRECT EVA ACCESS TO EXTERIOR
  3. BUFFER BETWEEN PRIVATE DOMAINS
  4. LOCK TO PRIVATE CREW QUARTERS
  5. LOCK TO COMMON AREAS
  6. EXTERIOR SEPERATIONS & CLEARANCES
    - INFLUENCE ON INTERIOR FUNCTIONS

## 7) GROUP GATHERING PLACES

### 1. WARDROOM

- GALLEY?
- DINING
- RECREATION / ENTERTAINMENT
- WORK AREA

4-19

### 2. GROUP WORK STATIONS

- STS RMS & AFT PILOT STATION
- NEED FOR OFFICE ON SKYLAB
- LABORATORY MODULES

### 3. EXERCISE / HEALTH FACILITY

### 4. SMALL GROUP / CONFERENCE / DEN

- DOUBLE AS SOLAR STORM  
RADIATION SHELTER?

## 8) VISUAL SYSTEMS 1

- WINDOWS FOR WORK
  - RENDEZ-VOUS & DOCKING
  - CELESTIAL OBSERVATION
  - EARTH OBSERVATION
- WINDOWS FOR ENTERTAINMENT
  - MOST POPULAR PASTIME ON SKYLAB WAS WATCHING EARTH SLIP BY.
- WINDOW LOCATION, TYPE, SIZE, SHAPE & OPTICAL QUALITY - CRITICAL
- CLOSED CIRCUIT T.V. & VIDEO
  - TO WHAT EXTENT CAN THEY SUBSTITUTE FOR WINDOWS?
- WINDOWS ADMIT UNWANTED RADIATION

# VISUAL SYSTEMS 2

- LIGHTING:

- SPECIFIC TASK LIGHTING
- AMBIENT BACKGROUND LIGHTING

- ARTIFICIAL LIGHTING:

- SOME STUDIES SHOW LONG TERM EXPOSURE CONTRIBUTES TO FATIGUE & IRRITABILITY.
- USE OF SUNLIGHT FOR INTERIOR ILLUMINATION

- EXTERIOR ILLUMINATION:

- SUPPORT EVA WORK CONTINUOUSLY THROUGH NIGHTSIDE?
- EVA CONTROL OF LUMINAIRES?

## 9) VIBROACOUSTICS

- SKYLAB WAS SO QUIET, THE SLIGHTEST NOISE WOULD AWAKEN SLEEPING CREWMEN, FORCING SINGLE SHIFT OPERATION.
- SHUTTLE FLIGHT DECK IS SO LOUD, HEADSETS MUST BE WORN FOR CONVERSATION.
- COUNTERMEASURES:
  - ISOLATION OR ATTENUATION AT SOURCE
  - ABSORPANT SURFACES
  - SOUND BARRIERS/BULKHEADS BETWEEN COMPARTMENTS IN A MODULE
  - POSITIVE ISOLATION BETWEEN MODULES.
- AUDIO SYSTEMS

## 10) STRUCTURES: SHELLS

- MODULE PRESSURE SHELL CONSTRUCTION CAN INFLUENCE HABITABILITY AND H.F.
  - RIBBED VS. SMOOTH INTERIOR WALL
    - CONNECTIONS FOR INTERIOR STRUCTURE
    - WINDOW FRAMING, SIZE, SHAPE, LOCATION
    - DUST & CONTAMINANT ACCUMULATION
- END CAP GEOMETRY
  - SUPPORT BERTHING PORTS, MECHANISMS, WINDOWS, TANKS
  - METHOD OF FABRICATION
    - SHEAR SPUN SECTION
    - TRAPAZOIDAL GORES
    - HEXAGONAL GORES
  - FORM: ELLIPTICAL, CONICAL OR SPHERICAL

# 11) MECHANISMS

- BERTHING MECHANISM IMPORTANCE CANNOT BE IGNORED, IT IS PROFOUND.
- CURRENT BERTHING MECH. CONCEPT WAS DEVELOPED AT JSC FOR APOLLO/SOYUZ (ASTP):
  - SINGLE-VECTOR, SIMULTANEOUS ALIGNMENT
  - WORKED WELL FOR APOLLO

## BLT

- SPACE STATION MECHANISM MUST PERFORM MORE & DIFFERENT FUNCTIONS:
  - GEOMETRIC FLEXIBILITY
  - 15-20 VARIED UTILITY CONNECTIONS
  - SYSTEM OF BERTHING LOGIC
  - MAINTENANCE & UPGRADES BETWEEN PORTS



# 12 UTILITIES

- DISTRIBUTION & CONNECTION WILL BE THE MOST DIFFICULT INTERIOR DESIGN & PHYSICAL SYSTEM INTEGRATION PROBLEM.
- CASE STUDY OF PLUMBING JOINTS (POTENTIAL LEAK & MAINTENANCE POINTS)
  - MANUAL CHANNEL: 2 JOINT UNITS/PIECES
  - REMOTE ACTUATED: 5 JOINT UNITS/PIECES
- LDR CASE STUDY (MDAC) 3-D TRUSSES
  - ASSEMBLED (MANUAL) EVA
  - DEPLOYED (AUTOMATED)
- REMOTE/AUTOMATIC CONNECTIONS MAY BE APPROPRIATE ONLY FOR FREQUENT OR HAZARDOUS UNITS OR MODULES OR OPERATIONS

14-25


ORIGINAL PAGE IS  
OF POOR QUALITY

## UTILITY CONNECTION CASE STUDY

### RESULTS OF TRIANGULAR-TETRAHEDRAL SPACE STATION STUDY:


#### MANUAL CHANNEL CONNECTION:

2 JOINT UNITS/PIECES – PREASSEMBLED  
CHANNEL INSTALLED BY HAND



#### REMOTE ACTUATED CONNECTION:

5 JOINT UNITS/PIECES – PREINSTALLED  
UTILITIES DEPLOYED AUTOMATICALLY



NASA—Ames Research Center  
Space Human Factors Office

# 13) FUNCTION

- DEFINITION OF FUNCTION
- CLARITY OF FUNCTION
- ORGANIZATION OF FUNCTIONS
- DO FUNCTIONS EQUATE TO MODULES?
- CAN FUNCTION DICTATE GEOMETRY?

**A Preliminary Human Factors Planning and Design  
Outline of Parameters Related to Space Station Windows and CCTV Monitoring\***

**Richard F. Haines  
Aero-Space Human Factors Research Division  
Ames Research Center - NASA  
Moffett Field, CA 94035**

**Abstract**

This paper presents a preliminary discussion of parameters considered to be important in designing windows for space station from a human factors point of view. The following window parameters are discussed: number, frontal area and shape, location in relation to the configuration of station modules, field of view angles, ambient interior illumination control, closed circuit TV operations, and preliminary design specifications. Not discussed are such topics as mechanical strength or weight, installation, breakage threat, abrasion resistance, etc. Space station windows should not require any break-throughs in new optical technology.

---

\* Paper presented at Space Station Human Productivity working group meeting, February 27 - March 2, 1984, Ames Research Center-NASA, Moffett Field, CA. 94035.

### Introduction

This paper presents an outline with commentary on selected aspects of space station windows and remote television monitoring. The fundamental question may be asked at the outset:

#### *Are Windows Needed?*

Of course this question has to do with the issue of whether the crew can carry out their duties as well by means of remotely controlled TV cameras as they can by viewing through windows. This is a complex question which has been discussed for years. The literature which compares human visual capabilities with those of closed circuit television hardware appears to favor human vision when everything is considered. This literature is not reviewed here. It is instructive to note that windows have been included on every previous manned space flight of both the Soviet Union and the United States. Astronauts Truly and Crippen remarked about the value of space vehicle windows. They state, "A wealth of scientific information was gleaned from the hand held photography of the heavens and the earth taken from these six (Skylab) windows. However, quite often there was not a window available to view a desired objective.... Every attempt should be made to provide spacecraft of the future with enough windows of good optical quality to always offer a view of earth and space." A review of many post-flight debriefings of the American missions and other material has convinced this writer of the critical importance of windows.

Their major functions are listed here:

1. Permits outside visual observations.
  - a) rendezvous/docking with other objects
  - b) space station build-up/repair/(future) modification
  - c) emergency/rescue operations
  - d) earth surface experiments/monitoring
  - e) celestial experiments
  - f) experiment hardware moving and stowage using remote manipulators
2. Permits limited visual observations from outside to inside.  
For instance in the event of a communication system failure gestures/non-verbal communication would still be possible.
3. Can make it possible to "see through" a module from outside.
4. Allows natural sunlight to enter for possible use.
5. Contributes to general habitability of the living/working environment by virtue of the natural beauty of the heavens and earth viewed from orbital altitude and by the ability of a window to permit the viewer ready "visual escape" from the relatively small and confining habitat.
6. Contributes to the mental health of the crew by providing immediate visual and "psychological" access with the earth.

7. Can contribute to the physical health of the crew by providing access to natural solar radiation.

### Subject Outline

#### *Primary Design Issues* (Discussed here)

- 1.1 Number of windows per module
- 1.2 Frontal area and shape of each window
- 1.3 Location of each window in each module in relation to station configuration
- 1.4 Field of view angles of each window (function of 1.2 and 1.3)
- 1.5 Ambient interior illumination control
- 1.6 Operations better suited for CCTV than windows
- 1.7 Preliminary design specifications

#### *Secondary Design Issues* (Not discussed here)

- 2.1 Optical characteristics of each window to permit execution of each required function
- 3.1 Solar radiation filtering requirements (UV, visible, IR)
- 4.1 Maintenance requirements (cleaning/polishing interior & exterior surfaces)
- 5.1 Internal heat balance considerations
- 6.1 Internal "habitability" considerations (need for visual escape, crew reassurance to the real world, shorter day/night cycle and circadian entrainment, etc.)
- 7.1 Visual accommodation considerations over time
- 8.1 Stimulus to human creativity

### *1.1 Number of Windows Per Module*

In order to determine the required number of windows per module from a human factors design point of view one should take the following factors into account. Not considered in this paper are such considerations as the mechanical strength or weight of glass, specific means for installing it into the space station, leakage-related problems, or other threat impact issues. Also, factors such as the abrasion-resistance of glass is of importance here only to the extent that periodic maintenance must be planned in order to restore the windows to some acceptable condition. Clearly, the more windows there are the more such maintenance will be required. Finally, it is assumed that the optical quality of each window will be adequate to support the particular task(s) that will be carried out using the window. The host of problems associated with poor optical design will not be discussed here.

- 1.1.1 Established need for external visibility during space station build-up period. Certain configurations of modules of a completed space station may block the external field of view from a given window so that another window would be called for in that module. Because of weight, strength, and other penalties, it is possible that a temporary CCTV might be used in place of a window during the construction phase.
- 1.1.2 Established need for field of view (FOV) overlap from two or more windows. Certain operations may require simultaneous multi-crew coordination from different windows. Can it be demonstrated that both crewmen will be enhanced in their ability to perform the required tasks because of this simultaneous viewing capability?
- 1.1.3 Established need for having "blind spots" only in non-critical areas. CCTV monitoring could be used to provide "fill-in" surveillance in these areas.
- 1.1.4 Established need for admitting solar radiation into the space station over a sufficiently large area (total) area. Certain experiments as well as the crew may require natural sunlight inside the space station.

### *1.2 Frontal Area and Shape of Each Window*

As with the other window design characteristics discussed here, window area and shape have been determined mainly on the basis of structural engineering constraints rather than by human factors related needs. A particularly strong case must be made by the human factors design professional if he intends to depart from so-called "standard" window shapes and sizes.

As used here, the term "area" refers to the physical dimensions of the window's transparent surface. The perceived shape of any window is determined by eye distance and head orientation relative to the window (cf. Figs. 7-9).

Of course an upper limit will be reached in window area set by strength and other considerations. There is a need to find creative solutions in re-

gard to enlarging or minifying window area visual effects. Can lenses (or fiber optics) be used in this way, perhaps to expand a patch of sunlight once it has entered a smaller window? Should windows be made of non-flat material such as the bubble canopys used on WW-II bomber and fighter aircraft?

A wide variety of window shapes have been used to date in America's manned space vehicles. The Mercury, Gemini, and Apollo vehicles all had small, irregularly shaped windows which provided only minimal external visibility. The Skylab vehicle had round windows. The astronaut could literally touch his nose to the glass which permitted a relatively wide external field of view (Figs. 2-5). The shuttle vehicle had forward windows remarkably similar in shape to those in today's commercial airplanes. At the top rear of the crew compartment are two square windows 19.75" on a side (with small radius corners) and at the rear bulkhead are two horizontally oriented rectangular windows measuring 14.25" wide. Their vertical dimension nearest the vehicle's centerline is 10.75" and farthest from the centerline is 9". They are recessed over 3" from the surrounding wall surface. To the author's knowledge no one has specifically analyzed the influence that this wide variety of windows may have had on how adequately the crew carried out their assigned tasks (Fig. 10). Anthropometric studies were conducted for the shuttle's rear work station windows in terms of eye to window distance to aid in planning for location of surrounding structure.

Before proceeding it is necessary to comment on the Design Eye Point (DEP) for a space station window. The DEP is the location of the two eyes relative to the window which will provide a desired external visibility envelope when looking through the window. This design approach was borrowed from airplane cockpit design. In the case of the space station's windows, the DEP must take into account not only eye to glass separation distance but also head-body orientation since the viewer will be in zero gravity conditions and may or may not have body restraint available. There will, therefore, need to be an azimuthal reference ( $A_z$ ) included which will represent the angle between the local vertical of the window ( $0^\circ$ ) and the longitudinal axis of the head with  $0^\circ$  at the top and measuring in the clockwise direction. Why will this  $A_z$  parameter be needed? Because the monocular and binocular visual field of the viewer may be larger or smaller than the FOV of the window depending upon head orientation and eye to window separation distance (see Figs. 11-15). It may be possible to maximize the total external visual field through a window by specifying a certain head orientation.

The following factors are considered relevant to designing the frontal area and shape of space station windows. .

- 1.2.1 Number of persons per window. Can a need be shown for two or more viewers to look out of the same window at the same time? Of course window area and shape are closely related. A circular window with an area of one square meter will have a diameter of only 56.4 cm which will not permit more than one viewer (centered), but a rectangular window of the same area (but 20 cm by 500 cm) could accommodate as many as six viewers side by side. How each of the viewers is oriented relative to one another also will determine how many people can use the same window simultaneously.



1.2.2 Eye to window surface distance. Obviously, the nearer the viewer can get to the window the larger will be his external field of view (angle) (cf. Figs. 11-15). The nominal eye to window surface distance for the aft bulkhead window in shuttle was 55 cm (22 inches). Field of view plots for an eye distance of only 10.4 inches showed that the maximum angular field of view width out this window for the 50 % man (binocular viewing) was about 62° (monocular) and about 80° (binocularly) (See Fig. 8). Moving back farther would reduce this angle significantly. Future anthropometric design considerations should accommodate a crew ranging in size from the 5th percentile female to the 95th percentile male.

Calculations have shown that the outer edges of a docking vehicle may well disappear outside the window's field of view at a certain separation distance even with the eyes located very near the window's surface (see Figs. 1,6). If this happens it will be necessary to provide additional range and range-rate dynamic cues for the astronaut to use. Such cues might include carefully planned surface patterns and other detail of known size that provide orientation and texture information about the vehicle being approached.

Another important consideration is placement of wall-mounted equipment and other structure near each window. It is known that the volumetric work-envelope requirements of the body in weightlessness differs from those in a one-g environment. Provision should be made to permit the viewer to locate his eyes near the window for extended periods of time without neck muscle strain.

1.2.3 Maximum field of view needed from the window. Certain tasks involving external visibility through windows will call for wider visual fields than others. Certain windows may need to be "dedicated" to specific functions with all of their field of view, optical transmission, and other characteristics pre-established to support the required function(s).

An ultra-wide field of view may be desirable in future space stations in situations in which visual judgments need to be made of the "structural" continuity of a very long module. Such a module may be only partially visible when viewed through a narrow window but which would be totally visible when viewed through a wide angle window.

Several comments are in order concerning the shape of the windows. It is likely that most windows will be used for a wide variety of purposes and that shape of the aperture will not be particularly important. However, it is possible that during the approach, docking, and other close-proximity operations with another vehicle or module window outline shape could be important. Consider a round window. Roll attitude of a distant approaching vehicle could not be readily determined within such a window shape without

an additional reticle, head up display, or other aid. In addition, the viewer's body orientation would be harder to determine when viewing through a round window. A square or rectangular window outline would provide such attitude information.

If it is found that crew "self orientation" to a local vertical is needed, then correctly shaping and orienting all windows alike could help to provide these verticality cues just as wall-to-wall intersection lines do in the one-g (earth) environment.

- 1.2.4 Established need for high optical quality. Much the same argument as given above (1.2.3) applies here. For example, if celestial observations will be carried out it may be justified to specify an "astronomy" window with all of the necessary optical characteristics.
- 1.2.5 Window thickness (depth) requirements. The thicker is the total window assembly the smaller will be the available external field of view for a given eye to window separation distance. Also relevant here are the total number of panes used in each window. Generally, the more panes the lower is the total light transmission and the greater is the possibility of multiple reflections (sometimes known as the "string-of-pearls" effect).
- 1.2.6 Established need for internal module ionizing radiation shielding. Unless the window assembly provides adequate cosmic radiation protection itself (at least comparable with surrounding walls), the fewer windows the better (all else equal).
- 1.2.7 Established criticality of maintaining clean windows. The larger the windows the greater will be the required maintenance (time/energy) "costs." In addition, certain shaped windows may require special cleaning implements. For example, a window having a small radius corner may prevent some implements from reaching all the way to the window frame. Such considerations may justify a limited number of space station window sizes and shapes.
- 1.2.8 Possibility/probability of needing to replace windows on-orbit. Windows may be damaged (cracked, scratched, unable to maintain an internal pressure over time). The frontal area of a becomes available. It also may be necessary to replace an existing window(s) as new technology makes improvements available.
- 1.2.9 Possibility of reflection of sunlight into a window from a near-by surface. Certain space station surface contours and sun angle orientations may produce very high intensity reflections into a window. Such reflected light could produce multiple reflections within multiple window panes, temporary visual impairment from so-called "flash blindness", and could alter the

heat load inside the station.

Since the human pupil of the eye requires from two to four seconds to contract completely to very high brightness scenes, an unexpected solar reflection could leave the viewer visually incapacitated for some period of time (see section 1.5).

### *1.3 Location of Each Window in Each Module in Relation to Overall Station Configuration*

In general, much the same considerations given above with regard to the number, size, and shape of the space station windows applies here as well. This issue is complex and calls for a careful prioritization of crew duties. There likely will be competition for wall space. Whether a window is installed rather than a cabinet or equipment should be dictated by a careful consideration of the long-term needs of the space station as well as a thorough knowledge of the capabilities and limitations of human vision and CCTV. Thus, while one might justify having no windows at all over the short-term, it is becoming increasingly obvious that having the ability to look out is very important. It is suggested that having this capability will become even more meaningful the longer the crew is on-board for psychological and social reasons.

A general design guideline should be kept in mind when considering the placement of each window in relation to the overall space station configuration, namely, the window designer must take into account all that is known about the capabilities and limitations of the human visual system. Take the perception of space for instance. There are a number of cues to distance and orientation present in most viewing situations (accommodation; convergence; light and shading, shadows, surface texture and gradients, motion parallax, flow fields, perspective transformations, occlusion of the farther object by the nearer, edge and corner configurations, redundancy, absolute size, etc.). The very high contrast environment of space will eliminate some of these cues while the relatively great viewing distances will eliminate or reduce others. The point is that window placement should attempt to plan for what cues will be available from the earth/sky background as well as from the other modules of the space station which will provide potentially useful distance ranging and translation rate cues.

Not discussed here are various engineering design factors such as module rib-spacing, radius of curvature of the walls, weight penalty, or other such subjects. The following general factors are presented to help plan for where to locate each window in a module.

1.3.1 Space station build-up sequence and module shape, number, and size. Window placement in each module may be partially dictated by the need to use each window during the construction phase of the space station. It is possible that CCTV may perform the desired viewing functions better from temporary locations than providing fixed windows at locations which may become "non-functional" or of reduced utility later when the space station is completed.

1.3.2 Module internal layout design. Windows must be located with regard to their proximity to internal equipment that

may require human monitoring and to fixed walls and/or other structure. Human anthropometric measurements as well as full scale mock-ups should define the necessary maximal and minimal separation distances.

If it appears that natural sunlight can be used for general interior illumination purposes an approach might be to locate a relatively large window at the end of the module and orient the module with the window pointing toward the sun. The shaft of light running the length of the module could then be "tapped" by inserting a reflecting (diffuse) surface at any location desired.

- 1.3.3 Necessity for sunlight at certain internal locations. It is conceivable that certain on-board tasks would benefit by being illuminated by natural sunlight. Window placement should take this possibility into account.

The opposite situation also exists, namely, those areas within the space station that must be shielded from sunlight such as sleeping areas.

- 1.3.4 Personal privacy needs should be considered. Window placement should consider the needs of the crew's personal privacy in "staterooms" and "heads." If a stateroom has a window it should be capable of being temporarily shuttered (see Section 1.5).

- 1.3.5 External visibility from multiple windows simultaneously. It may be desirable to use full visual field human vision (e.g., during the final stages of a docking/berthing operation). If a single window will not permit this wide a single field of view perhaps the use of two (or more) adjacent windows would suffice.

#### *1.4 Field of View Angles of Each Window*

The angular width and height of each window is determined by window size and shape and the eye to window distance. Laboratory research has shown the importance of having stable visual references within the observer's field of view during those times when he must judge precise absolute and differential motions. For the final stages of docking, for example, a special purpose alignment system such as is used on the shuttle (COAS) plays an important stabilization role. However, if the astronaut can hold his head in a constant position relative to the window frame, the fixed frame will serve the same purpose without the need for additional (input) power or special optical display hardware.

The field of view of each window may be effectively varied by moving the position of the eyes relative to the window. Computerized plots made for the deployment of payloads on shuttle using the remote manipulator arm provided valuable insight into how these fields of view change with head movement.

The recommended minimal window field of view width is 120° arc since this will provide for full binocular visual field stimulation. That is, the region

of the visual field that is mediated by the right eye will be fully overlapped by that region of the visual field that is mediated by the left eye. If significant head rotation is anticipated (rather than just eyeball rotation within the eye socket), then this minimal horizontal angle should be increased accordingly.

- 1.4.1 Optimal eye location behind a window to yield maximum field of view with minimal head movement. It can be shown that for a given size and shape window, there is an optical location for the eyes in terms of minimizing head movements yet keeping the target in sight.
- 1.4.2 Provision for allowing the eyes to be positioned very near the window's surface. Despite possible problems of window surface scratching and abrasion and moisture condensation from the crew's breath, it is strongly recommended that the area surrounding each window be designed with minimal interference for the shoulders and upper torso to permit him to come up close to the windows' surface when necessary.

### 1.5 Ambient Interior Illumination Control

There is a rather extensive literature which shows the critical importance of providing adequate illumination to support the performance of various tasks. This is no less the case on the space station. The availability of full sunlight makes possible the application of "light pipe" technology to bring sunlight to a desired interior location directly rather than via photovoltaic cells transduction. Direct solar radiation at mean solar distance =  $1.99 (+/- .02) \text{ cal cm}^{-2} \text{ min}^{-1}$ . The mean luminance of the solar disc viewed from orbital altitude =  $2.02 \times 10^5 \text{ stilb}$  ( $= 5.88 \times 10^8 \text{ foot Lamberts}$ ). Solar illuminance at mean solar distance (outside earth's atmosphere) =  $1.37 \times 10^5 \text{ lux}$  ( $\text{lumen m}^{-2}$ ). The lack of a local light-scattering atmosphere surrounding the space station produces an extremely high contrast between the blackness of space and the solar disc or objects illuminated by sunlight. This high contrast may call for special optical filtering at the windows, particularly for operations which must be carried out over long periods of time. Neutral density optical coatings, crossed polarizing filters, photochromic filters, and other kinds of light-controlling means are presently available. Several preliminary planning factors are given below.

- 1.5.1 Established need for having natural (full spectrum) sunlight available inside the space station. It is possible that various biological, medical, physical, and psychological experiments will require natural sunlight. Permanent windows having special glass will need to be installed to support these experiments. It is suggested that each module have at least one such window which transmits as wide a wavelength band as possible but that a "snap-on" spectral blocking filter also is provided for these particular windows.

- 1.5.2 Established utility of sunlight in health maintenance of the crew. It is known that calcium loss from the bone in weightlessness continues to be a major problem. It is also known that vitamin D from certain wavelengths of natural sunlight facilitate the absorption of calcium by the gastrointestinal tract. It may be justified to require periodic "sunlight therapy" on space station. If so, special optical glass will be required for the windows.
- 1.5.3 Established validity of using natural sunlight inside the space station to supplement or replace artificial illuminants. It is possible that on-board power generation requirements might be reduced through the creative use of fiber optics and/or reflective surfaces to redirect sunlight into and through the interior of the space station.
- 1.5.4 Established validity of using sunlight to enhance the habitability of the space station's living and working areas. Most people enjoy looking out of windows at out-of-door scenes. A careful review of in-flight voice communications from earlier space flights has shown the importance of having windows for reasons other than to support experiments.
- 1.5.5 Established need for having a test-bed for evaluating new means for controlling sunlight. It is conceivable that new technology will be developed for controlling ambient illumination for terrestrial applications. Having windows on space station will make testing of this new technology possible as long as the windows possess adequate transmission in the IR, visible, and UV wavelength bands.

#### *1.6 Operations Better Suited for CCTV Than Windows*

Justifications commonly given for using closed circuit TV monitoring include: operating environments which may be hostile to the human, operations which call for mobility and/or surveillance in small areas too restricted for fer. Experience gained from recent shuttle flights has proven the utility of remotely aimed and controlled TV cameras. The remote manipulator (cherry picker) arm was able to be positioned precisely at full extension by means of a TV camera attached to its end.

A prudent approach to the matter of how best to provide for the visualization of external space station operations would seem to be to provide a carefully integrated combination of CCTV and windows. Computer-aided 3-D perspective views of the completed space station for each vantage of concern should be produced so as to determine whether a window or CCTV camera is the best solution. Following are some general factors to consider in deciding whether CCTV should be employed in place of permanent windows on space station.

- 1.6.1 Necessity of having a "video" record of activities for later analysis. The CCTV camera's output may be stored on-board the space station and/or transmitted to earth.
- 1.6.2 Requirement for operating in the space environment over prolonged periods of time. While an astronaut could visually monitor external operations through a window, a properly positioned CCTV camera could also. Energy, weight, and volume tradeoff studies should be performed to justify use of either alternative. This factor also includes those physical characteristics of the space environment that are harmful to man (ionizing radiation, low temperature, low pressure) but which may be designed against for the CCTV system.
- 1.6.3 Requirement for "seeing" into very small and poorly lit areas. A properly designed CCTV system with its own illumination source(s) can permit visual access into volumes far smaller than that of the suited astronaut.
- 1.6.4 Operations where image magnification (zoom) are required. High quality optical magnifying lenses are now available with which to achieve wide ranges of field of view and magnification with minimal distortion and light loss. It should be noted, however, that range and range rate cues will be either missing altogether or severely distorted by a zoom system unless additional information is provided within the field of view.
- 1.6.5 Requirement to "see" ongoing operations but where physical impact is possible. It is best to sacrifice a TV camera (if absolute necessary) and not a person.
- 1.6.6 Requirement for a very long optical baseline. Certain future on-orbit operations may require ultra-large baselines as during the construction of very large antenna or solar cell arrays. Use of inertially stabilized CCTV systems positioned relative to each other (with appropriate retroreflective auto-alignment systems) over large separation distances could play a useful role here. It is difficult to see how the space station could be configured to provide this type of function no matter where the windows were placed.

### *1.7 Preliminary Design Specifications*

FOV (width;  $A_z = 0^\circ$ ) .....  $120^\circ$   
 (Height;  $A_z = 0^\circ$ ) .....  $80^\circ$

Shape (general) ..... Rectangular or

	Square
Transmission (general purpose viewing) .....	.80% (400 - 725 nm)
(skin photo-therapy) .....	t.b.d.
("full spectrum" applications) .....	approx. 340-850 nm
Design Eye Point (separation distance) .....	12" (mean)
( $A_z = 0^\circ$ )	
(min., max. distance) .....	1"; task dep.
Line of Sight (angular) Deviation .....	0.5 mr (note 1)
Optical Quality (general) .....	optical grade A
	(no bubbles)
Protective Shield (outside) .....	if possible
(inside) .....	yes
Light Shade (complete light cut-off capability?) .....	yes
(variable neutral density capability?) .....	yes (0 - 100%)
(colored filters available?) .....	t.b.d.

---

Note. 1. This deviation requirement should apply for all head positions and over the total FOV. The 0.5 mr maximum allowable radial error should be computed as the root-mean-square of the azimuth and elevation component errors.

#### Summary

While it may be concluded that windows on space station will be required to support a wide variety of work and leisure time activities, their specific design should take into account at least those human factors issues addressed above. It also should be pointed out that in order to not overlook critical "interaction" effects which are liable to occur whenever humans interact with other humans and with equipment each of the above factors also should take into account the following:

- work vs. leisure time activities
- small vs. large interior volume availability
- long vs. short term occupancy
- inflexible vs. flexible interior configurability
- major vs. minor physiological stressor(s) present
- major vs. minor psychological stressor(s) present


The importance of providing for optimal human vision in space flight has been adequately demonstrated over the past twenty five years. Now is the time to plan for the overall best design for the windows on space station.



ORIGINAL PAGE IS  
OF POOR QUALITY





(Bottom) Significant increases in available field of view can be obtained by decreasing the eye to window separation distance. At some vehicle to window separation distance ( $d_1$ ), its edges will not be visible and other depth cueing will be needed.



Viewgraph 1  
R. F. Haines

ORIGINAL PAGE IS  
OF POOR QUALITY








Figure 4.


Space Shuttle aft work  
station vertical section  
illustrating overhead window  
viewing by a small crewman.

## Reference:

Zero-G workstation design,  
NASA-JSC, Report No.  
09962, June 1976.

Viewgraph H  
R. F. Haines  
Feb. 21, 1984


ORIGINAL PAGE IS  
OF POOR QUALITY






42.381 50 SHEETS 5 SQUARE  
42.382 100 SHEETS 5 SQUARE  
42.389 200 SHEETS 5 SQUARE

Eye to Rendezvous Vehicle Distance (feet)



AITOFF'S EQUAL AREA PROJECTION OF THE SPHERE

RADIUS OF PROJECTED SPHERE EQUALS ONE DECIMETER  
AFT WINDOW FIELD-OF-VIEW



Space Shuttle

Viewgraph B  
R. F. Haines  
Feb. 21, 1984

ORIGINAL PAGE IS  
OF POOR QUALITY

# AITOFF'S EQUAL AREA PROJECTION OF THE SPHERE

RADIUS OF PROJECTED SPHERE EQUALS ONE DECIMETER  
AFT WINDOW FIELD-OF-VIEW

EYE POINT  $Y = 13.75$

NOMINAL EYE

$X = 565$

$Y = 115$

$Z = 484$

81r-4

Figure 8.

Field of view plot for binocular viewing.  
50% man, eye distance = 10.44", eye height =  
65.34" for the Space Shuttle's aft bulkhead  
window.


Space Shuttle

Viewgraph C  
R. F. Haines  
Feb. 21, 1984



AITOFF'S EQUAL AREA PROJECTION OF THE SPHERE

RADIUS OF PROJECTED SPHERE EQUALS ONE DECIMETER  
AFT WINDOW FIELD-OF-VIEW



Viewgraph D  
R. F. Haines  
Feb. 21, 1984


ORIGINAL PAGE IS  
OF POOR QUALITY

3000

# AITOFF'S EQUAL AREA PROJECTION OF THE SPHERE

RADIUS OF PROJECTED SPHERE EQUALS ONE DECIMETER

Space Shuttle  
Rear Bulkhead Window



Viewgraph A  
R. F. Haines  
Feb. 21, 1984

ORIGINAL PAGE 15  
OF POOR QUALITY




Figure 11.

Total binocular and monocular field of view of the human. The intersection of the horizontal and vertical lines is the line of sight. Each tick = 20°. The central area is the binocular visual field where both eyes receive corresponding images.

Viewgraph  
R. F. Haines  
February 21, 1984





Figure 12.  
Field of view for two  
viewing distances and a 12"  
diameter round window relative  
to the binocular visual field.

Viewgraph  
R. F. Haines  
February 21, 1984



Viewgraph  
 R. F. Haines  
 February 21, 1984




Figure 14.  
Field of view for two viewing distances  
and a 24" diameter round window relative  
to the binocular visual field.

Viewgraph  
R. F. Haines  
February 21, 1984





Figure 15.  
Field of view for a 3" eye to window viewing  
distance and a 24" diameter round window  
relative to the binocular visual field.

Viewgraph  
R. F. Haines  
February 21, 1984

# BOEING CONCEPT - OVERALL CONFIGURATION

Figure 16.  
Illustration of plane cutting two  
parallel cylindrical modules.




Viewgraph  
R. F. Haines  
February 21, 1984

ORIGINAL PAGE IS  
OF POOR QUALITY



# EXTERNAL VISIBILITY OVERLAP

(Each Circle Represents Module Section)



To minimize blind areas:

- Increase field of view angle per window
- Decrease window to window spacing
- Both of the above

Note: Field of view angle is not directly related to window area.

Figure 17.  
Diagram to illustrate overlapping fields of view for various window angular widths and spacings. Note that the two factors may be traded off with each other to minimize blind areas (cross-hatched).

Viewgraph  
R. F. Haines  
February 16, 1984

ORIGINAL PAGE IS  
OF POOR QUALITY

# WINDOW FIELDS OF VIEW FOR IN-LINE MODULES

(Each Circle Represents a Module Section)

## Key Variables:

$D$  = Intermodule spacing

$a$  = window orientation angle off axis

$r$  = module radius

$f$  = field of view half-angle

=  $3r$


=  $30^\circ$

=  $r$

=  $60^\circ$

Figure 18.

Diagram of four in-line modules each having two windows  $180^\circ$  apart as shown. Four design variables are also indicated. Closed circuit TV may be useful to "see" into otherwise blind areas.



ORIGINAL PAGE IS  
OF POOR QUALITY

# WINDOW FIELDS OF VIEW FOR IN-LINE MODULES


( Each Circle Represents a Module Section)

## Key Variables:

D = intermodule spacing	= $3r$
a = window orientation angle off axis	= $45^\circ$
r = module radius	= $r$
f = field of view half-angle	= $60^\circ$

Figure 19.

Diagram of four in-line modules each having two windows  $180^\circ$  apart as shown. Compare this field of view configuration with that of Figure 18.



Viewgraph  
R. F. Haines  
February 16, 1984

SEMINAR ON SPACE STATION HUMAN PRODUCTIVITY

HUMAN FACTORS ISSUES IN SPACE STATION ARCHITECTURE

March 1, 1984

JOHNSON SPACE CENTER CONFIGURATIONS

Jim Lewis

Crew Station Design Section, SP-22

Man-Machine Analysis Branch

Man-Systems Division

Johnson Space Center (JSC)

Houston, Texas 77058

(713) 483-4161

FTS 525-4161

Pair (1) - Lab. 1)  
(2) - Lab. 2)

## HABITABLE 11Y

## DECLARATIONS

[illegible]

ORIGINAL PAGE IS  
OF POOR QUALITY

**N85-29560**

ORIGINAL PAGE IS  
OF POOR QUALITY




# RIGHT SIDE VIEW HABMOD #1

PRIVATE QUARTERS

CDMS

HEALTH MAINT/MED

EATING AREA



ORIGINAL PAGE IS  
OF POOR QUALITY


4-63

MOD 012



PLAID

LEFT SIDE VIEW HARMOD #1



ORIGINAL FILED IN  
OF ROOM QUALITY

4-64


MOD 012





PLAID

# TOP VIEW HABMOD #1



4-65


ORIGINAL PAGE IS  
OF POOR QUALITY

MOD 012

# RIGHT SIDE VIEW HARMOD #2



PLAID



4-66

ORIGINAL PAGE IS  
OF POOR QUALITY


MOD 014

# LEFT SIDE VIEW HARMOD #2



PLAID

GALLEY      EATING AREA      STOW      PRIVATE QUARTERS



ORIGINAL PAGE IS  
OF POOR QUALITY


4-67

MOD 014


TOP VIEW HABMOD #2



PLAID




MOD 014



ORIGINAL PAGE IS  
OF POOR QUALITY


Figure 4.10-1. Conceptual 48-hour Space Station Timeline



ORIGINAL PAGE IS  
OF POOR QUALITY

Figure 4.10-2. Conceptual 48-hour Space Station Timeline





ORIGINAL FIG 18  
OF POOR QUALITY

Figure 4.10-4. Conceptual 48-hour Space Station Timeline



SPACE STATION AUTOMATION ASSESSMENT

MAN-MACHINE TRADEOFF STUDY

4-73

PASADENA, CALIFORNIA 91109

ABE FEINBERG  
WAYNE ZIMMERMAN

MARCH 1, 1984

N85-29561

## CONTENTS

PURPOSE AND SCOPE OF STUDY

BACKGROUND

APPROACH

SELECTION OF MODULES

CRITERIA/ATTRIBUTES

RELIABILITY ILLUSTRATION

AUTONOMY EVALUATION

4-74

AF/WFZ 1  
3/1/84

## BACKGROUND

- o APPLICATION OF ADVANCED SPACE TECHNOLOGY INVOLVED THE PRIVATE SECTOR (E.G., BIOMEDICINE, SOLAR POWER PLANTS, ALTERNATE ENERGY SOURCES, ETC.).
- o NEW TECHNOLOGY APPLICATIONS REQUIRED A BETTER UNDERSTANDING OF ACTUAL HUMAN TASKS/INTERFACES.
- o THERE WAS A NEED TO SYSTEMATICALLY DEFINE HUMAN INTERFACES.
- o FOR THOSE AREAS WHERE AUTOMATION LOOKED PROMISING, THERE WAS A NEED TO ESTABLISH A SOUND MEANS OF ASSESSING HUMAN/MACHINE TRADEOFFS (I.E., SYSTEM EFFICIENCY TRADEOFFS).
- o DOE RESEARCH RELATED TO REMOVING WORKERS FROM HAZARDOUS ENVIRONMENTS - SPECIFICALLY UNDERGROUND COAL MINING.
- o SPACE STATION EFFORT COMMENCED JANUARY 1984.

4-75

AF/WFZ 2  
3/1/84

## BASIC APPROACH

- o ESTABLISH TASK PROBLEM AREAS IN NEW TECHNOLOGY VIA INTERVIEWS OR ACTUAL INDUSTRIAL ENGINEERING STUDIES (E.G., INTERVIEWS WITH OPERATORS, OR IDENTIFYING HIGH TASK TIME DRIVERS).
- o DEVELOP LIST OF POTENTIAL AUTOMATION CANDIDATES.
- o PERFORM TASK AND SYSTEM CRITICAL PATH ANALYSES, SUPERIMPOSE POTENTIAL AUTOMATION CANDIDATES, AND ASSIGN ATTRIBUTES TO ASSESS IMPACTS FOR EACH AREA (E.G., COST, TASK EFFICIENCY IMPROVEMENT, SAFETY IMPROVEMENT, ETC.).
- o CONFIRM IMPACTS OF ATTRIBUTES BY TALKING TO EXPERTS.
- o DEVELOP CONCEPTUAL DESIGNS AND COSTS NECESSARY TO IMPLEMENT AUTOMATION CANDIDATES.
- o ASSESS COST BENEFITS (I.E., WEIGH THE COST OF AUTOMATING AGAINST THE BENEFITS GAINED).
- o RANK AUTOMATION CANDIDATES AS A FUNCTION OF MOST FAVORABLE RESPONSE TO ATTRIBUTES AND OVERALL COST BENEFITS.

4-76

WFZ/AF 3  
3/1/84

## PROCESS

- o IDENTIFY KEY SPACE STATION MODULES
- o DEVELOP MOVING BASELINE FOR DETERMINING SPACE STATION COMPONENT AUTOMATION OPTIONS
- o PERFORM TASK ASSESSMENT
- o DEVELOP ATTRIBUTES FOR ASSESSING COSTS AND BENEFITS OF ASSIGNING TASKS TO TECHNOLOGIES
- o PREPARE LIST OF POTENTIAL TRADEOFFS

4-77

AF WFZ 4  
3/1/84

SELECTION OF KEY MODULES FOR FY 1984 TRADEOFF STUDY

<u>MODULE</u>	<u>LEVEL OF INTEREST</u>
UTILITY	HIGHEST
DOCKING	HIGHEST
LOGISTICS	HIGH
LABORATORY	HIGH
HABITAT	MODERATE
REMOTE ARM	MODERATE

4-78

AF/WFZ 5  
3/1/84

CRITERIA/ATTRIBUTES FOR TASKS AND TECHNOLOGY ASSIGNMENTS  
(TENTATIVE)

SAFETY

MISSION AND OPERATIONS TIME

PAYLOAD

POWER

RELIABILITY


R&D TIME

COST

4-79


AF/WFZ 6  
3/1/84

EXAMPLE: AUTONOMY IMPACT ON RELIABILITY





# AUTONOMY EVALUATION



JHS/AS/WFZ 8  
3/1/84

SCHEDULE

<u>TASK</u>	<u>SCHEDULED COMPLETION</u>
IDENTIFY KEY MODULES	COMPLETED
MOVING BASELINE	3/31/84
TASK ASSESSMENT	4/30/84
DEVELOP ATTRIBUTES	5/31/84
LIST POTENTIAL MAN/MACHINE TRADEOFFS	7/31/84
PREPARE REPORT	9/30/84

4-82

AF/WFZ 9  
3/1/84

February 28, 1984

SOME IDEAS AND QUESTIONS REGARDING SPACE STATION DESIGN

FOR HUMAN USE

Sharon Skolnick, B.I.D., M.Ed.

As a designer and writer, I appreciate the creative thinking of the late Buckminster Fuller, who once referred to the earth as 'a spaceship on a gravity leash.' When astronaut Bruce McCandless recently separated from his umbilical cord and floated free, it seemed like a birth-- as though the gravity leash had been dropped and a new, human planet had been born.

If the earth is a spaceship, we are all astronauts. Fragile, tough, self-regulating and cyclically operating, we jump on and off of our planet all of the time, without needing to be rooted like plants. But too many people forget how interwoven with earth we are, how consistently we need not only food, warmth and a roof, but nurturing, meaning, spiritual sustenance, love, and human touch-- and humor.

What has struck me over and over when I hear reports from the scientists and pilots who have reached outer space is the laughter: the jokes these people crack, and the stunned, poetic reaction to the beauty they see, the whole earth in space. And how philosophical and inspired many of them become. This in spite of living in cramped tin cans with levers and buttons and flashing lights.

To optimize a long term outer space environment, I think we need to research and draw upon what is really human and humane; what individual

Raymond Loewy, William Snaith Associates, Industrial Designers in New York City. I was the only woman on the product design team. Though the others may have seen my colorful banners, multilevel strap-in tables, hanging plants and grow-lights as "feminine" and "untechnical", I am a female human and I addressed my design skills and analytical thought to the humanity of the passengers, the spirit of fun and play in a new kind of space. It is exciting to be able to present the idea now, 15 years later, when humanism and high tech are starting to interface.

Just because we are entering the realm of science fiction doesn't mean we need to stick with set designs, or send people out to live in a Greyhound bus station. On the other hand, the appointments of a luxury ocean liner, all polished woods and gleaming brass and palm trees, may be inappropriate where minimal weight has to do maximum work.

I think we need nests in the trees for a high flyers: private organic spaces if the outer shell is vast and cylindrical and people are floating; or else group gathering areas of large dimensions if the general milieu is tight little spaces. We need touches of whimsy, of softness, and lots of places for the individual to put or choose personal objects and images, to make the station homey for that person.

The human animal is not a machine. Maybe we need to study the animals' environments too.

Some specific suggestions my friends and I have come up with to humanize a space environment include:

-- Natural, not plastic, materials. Natural fabrics on the walls, with banks of subtly colored lights the passenger can change at will, since color is so

persons require and desire to keep them healthy, happy, productive and secure. What colors, shapes, spaces, what kinds of order or clutter make us feel good, therefore becoming more stable, optimistic and efficient.

I believe two places to look for applicable answers are the indigenous cultures of planet earth, shelter design and living patterns of native people: Plains and Southwest Indians, nomadic Semitics and Asians, and Polynesian sailors who spent long months on the high seas with their families, their thatched shelters, their domestic animals and some coconut trees.

That's one place to look, because people who can make a human environment from available materials in an economic, ergonomic way, while at the same time keeping their spiritual energies focused through meaningful ritual and reverence, have much to teach the high tech world.

The other place with some answers may be the prisons. What does not make for a human environment? What is oppressive, dulling, psychologically upsetting of balance, dehumanizing? How to avoid those traps on a mini-planet orbiting in space may let us know, ultimately, how to stop torturing human beings in various kinds of institutions on earth. It looks like environmental research for space could have some global repercussions as well, if it could be approached from an ethically high place.

Obviously the answers are not all going to come from the engineers and ergonomics experts and corporate white males over 50, or we wouldn't be here today.

When I designed a three-dimensional weightless cafeteria for the space station set to go into orbit in 1985, the year was 1969 and the place was

psychologically important for peace of mind. Pattern templates to create light patterns at will.

-- A lot of plant material and grow-lights, some plants growing in earth, so the smell and feel of earth is present. A few uncaged, well-behaved animals, shuttle-pets: birds; dogs; cats; turtles; fish...

-- Use of natural wood for built-in furnishings.

-- Muted, rear screen still-picture projection from a large library of paintings, textiles, sculptures and photographs, chosen by the individual or group to express current interests, ease tensions and share cultural images of personal value. One person might need to see a beach, another a Manhattan urban scene, while a third might feel good in the presence of a punk painting or old masterpiece.

-- A huge rear screen hemisphere might be used for total environmental effect: redwood forest or desert, as well as for movies, video and educational images for group conferences.


-- Ultimately, I can see the space station becoming its own little planet, with green plants growing on the outside surface under a greenhouse-like atmospheric outer shell. Why not grow food locally?

These little offshoots of earth could be wonderful, healthful spas for healing of mind/body/spirit as well as commercial and scientific pursuits. To achieve and sustain that kind of reality, I think the aims not only have to be of the highest human kind, but the accessibility of the station needs to be universal as well. This should not be a haven for the elite, but should be a sanctuary and thrill for all kinds of people: women, men, elders, kids, the

handicapped, all cultures, all colors, all opinions.

That's what earth is, after all-- or could be.

I hope your consultants are indigenous people and healers and artists, people with a respect for nature's cycles and ancient human wisdom. This is a great opportunity to create a truly wholistic place, the fruit of global knowledge of what is good for human beings gathered in one revolving, evolving sphere. This is a great chance. I hope you take advantage of it, and I thank you for hearing my thoughts.



WEIGHTLESS CAFETERIA  
 - AFTER A DESIGN FOR SKYLAB  
 by SHARON SKOLNICK, 1969,  
 RAYMOND LOEWY / J.H. SMITH ASSOC.  
 © 1984 VISIONARY GRAPHICS

ORIGINAL PAGE IS  
 OF POOR QUALITY








Figure 2-2.- Cutaway view of modules and launch configuration.

ORIGINAL PAGE IS  
OF POOR QUALITY




Figure 10-4.- Wardroom arrangement.




Figure 10-7.- Sleep compartment arrangement.

N85-29563

SPACE STATION  
HUMAN PRODUCTIVITY WORKING GROUP  
February 27 - March 2, 1984  
Ames Research Center  
Building 239 Room B39


HUMAN PRODUCTIVITY EXPERIENCE  
AND  
UNDERSEA HABITAT DESIGN

BY

Thomas C. Taylor

John S. Spencer

## ***Prudhoe Bay Operations***





### **LESSONS LEARNED**

- FINANCIAL DRIVER
- HABITATION
- RISK REDUCTION
- TRANSPORTATION
- EQUIPMENT
- MARKET DEVELOPMENT
- OTHER ELEMENTS

ORIGINAL PAGE IS  
OF POOR QUALITY

North  
Slope  
Alaska:



## HABITATION LESSONS LEARNED

- GOOD DESIGN PAYS DIVIDENDS
- DESIGN MUST GO BEYOND  
HUMAN FACTORS CONSIDERATION
- FOOD IS IMPORTANT MORALE FACTOR
- PRIVACY IMPORTANT
- HUMAN PRODUCTIVITY SUCCESS CAN BE  
MEASURED BY CONSTRUCTION OPERATIONS
- NEGATIVE SOCIAL  
INDICATORS ALSO VISIBLE

ORIGINAL PAGE IS  
OF POOR QUALITY

## INTERIOR DESIGN COMPARISON - ALASKA CONSTRUCTION CAMPS

Actual Observed Experience  
1975 - 1978

### WELL DESIGNED INTERIOR

- Good lighting
- Acoustical provisions
- Group gathering locations
- Exercise and recreation Facilities provided

### EFFECTS


- Pleasant and positive overall Feeling from surroundings
- Inhabitants changed work Clothes before dinner
- Several security staff For 600 inhabitants
- Room doors without locks
- Interior sprinkler system added
- Food served cafeteria style

### MARGINAL HUMAN FACTORS DESIGN

- Poor lighting
- No acoustical provisions
- Group meetings in rooms
- Exercise and recreation Facilities limited

### EFFECTS

- Cramped feeling
- Inhabitants usually ate In work clothes
- Approximately 1 uniformed Security staff for each 30 inhabitants
- Room doors with locks
- Inhabitants slept with Arctic Parka over feet and near boots
- Food with portions served by staff
- Noticeably more drugs, gambling, Alcohol, and camp damage problems
- Some cases of arson




# **HABITATION MODULE**


**SECTION A-A**  
1/4"=1'-0"

1981 SHDA

HABITATION SPACE  
FOR SIX ASTRONAUTS  
FROM 3 TO 6 MONTHS -  
SHUTTLE CREW LAY-  
OVER OR EMERGENCY  
HABITATION.



SLEEPING VOLUME



ORIGINAL PAGE 18  
OF POOR QUALITY

Unloading Area Control  
Trained's  
Command Center  
1981  
Space Station Control




# DESIGN STUDY

## HABITABILITY CRITERIA



by Carol J. Amato


		PSYCHOLOGICAL/ BIOLOGICAL	CULTURAL	SOCIAL	GENERAL PHYSICAL
Single Nationality Crews	4-97	Nature of Mission Duration Motivation Mobility Sense of Orientation Adaptability Flexibility Sensory Stimulation Variability Personal Identification Personal Turf Change and Surprise Environmental Enhancement Growth and Change Sense of Security Work/Free Schedules Presence of Family View of Outside Escape Procedures Known Need to "Get Away" Living Things (pets, etc) Room for Job Advancement Solipsism Effect Shimanigasi Syndrome	Crew Characteristics Which Language Dominates? Holistic Medicine Approach Cultural Self- Evolution Colonist Superiority Complex Toward Terrans Hierarchical vs. Egalitarian Pacifism vs. Militarism	Social Areas Activity Arrangement Loner vs. Social Personalities Male/Female Roles Required Social Interaction Sports (Indi- vidual and Group) Arts Entertainment Age Distribution a Must	Safety Ease of Movement Comfort Volume/ Person/ Activity Gravity Situation Life Support Ease of Main- tenance Exercise
		Multi- National Crews	Architectural Preferences Aesthetic Values and Choice of Surroundings Living Things (Pets, Plants) Variation of Routine	Basic Anthropological Knowledge of Other Cultures as a Re- quirement Decision-making Process	
		MILITARY PERSONNEL (ADDITIONAL CONSIDERATIONS)			
		CULTURAL REFERENCES			
		World View      Ethnic Cooking      Religious Practices      Officers vs. Enlisted Sex Practices      Family Structure      Marriage Practices      (No hierarchy?) Political Orientation      Hygiene Habits      Male/Female Roles      Violence as Good Economic Orientation      Kinship and Descent Patterns      Military Wife Syndrome Pacifism Vs. Militarism      Concept of Private Ownership Child-Raising Practices      Attitudes on Sickness and Death			

ORIGINAL PAGE IS  
OF POOR QUALITY



AFT CARGO CARRIER MODEL





HABITATION  
MODULE

MAIN AREA


MECHANICAL DUCT  
DISTRIBUTION PATTERN

SCALE:  $1/4" = 1'-0"$



KEY

## UTILITY CONSIDERATIONS



HABITATION  
MODULE

SERVICE/MECHANICAL AREA  
EQUIPMENT-DUCT DISTRIBUTION


SCALE:  $1/4" = 1'-0"$



KEY

1981 SHDA

ORIGINAL PAGE IS  
OF POOR QUALITY



4-101

# Western Regional Undersea Laboratory

## • the program

On July 1, 1980, the Institute for Marine and Coastal Studies at USC signed a cooperative agreement with the National Underseas Research Project Office of NOAA for funding to initiate a long-term underwater scientific research program at Santa Catalina Island, California, utilizing saturation diving and an underwater habitat.

## • saturation diving

Saturation diving allows extended periods at the work site without intermediate decompression times. Non-work periods are spent in an underwater structure anchored to the bottom near the work site, which serves as both home and laboratory. The WRUL program is designed to give mission times of up to 14 days. Missions will commence and end on dry land beside an on-site, fully staffed hyperbaric chamber.

## • time frame

The first operational mission is expected to start in late 1982. It is anticipated there will be 12 to 16 missions per year. Interested researchers should submit their proposals 6 months in advance of the start date to allow for the peer review process.

Announcement of the Initiation of a University of Southern California (USC)/National Oceanic and Atmospheric Administration (NOAA) cooperative undersea research program at the USC Catalina Marine Science Center (CMSC).

## • objectives

The primary goal of the WRUL Program is to expand marine research in the Pacific region of the U.S. The program will support basic and applied marine science by making available a saturation diving facility in temperate waters. Additionally, the location of the habitat within a preserve under the control of the university administration allows, indeed promotes, long term studies. The WRUL staff and facilities will be made available to those research projects that qualify through the peer review process.

Possible areas of investigation include:

- Marine fisheries
- Marine ecology
- Oceanography
- Marine pollution
- Sea floor properties and processes
- Human physiology
- Nautical archaeology
- Marine geology
- Energy resources

The proposed WRUL system will be guided in its design and operation by a philosophy of safety (with ABS certification), simplicity of operation, and utilization of existing facilities, all within a modest operating budget.

## the habitat

- Size - 8 meters long by 3 meters diameter
- Depth range - 16 to 50 meters sea water
- Mission crew - 4
- Support via shore umbilical
- Excursion range:
  - Horizontal - 100 m untethered, 300 m tethered
  - Vertical - 8 to 80 meters sea water
- One large observation port
- Breathing gas - air or nitrox (reduced O2 percentage)
- Mission duration - 5 to 14 days
- Contains wet and dry laboratory space
- Flexible configuration to meet investigator requirements





# UNDERSEA HABITAT STUDY

Crew Size: 4-5  
Mission Length: 2 weeks

HABITABILITY CRITERIA  
USC UNDERSEA LABORATORY

by Carol J. Amato

## PSYCHOLOGICAL/BIOLOGICAL

## CULTURAL

## GENERAL PHYSICAL

Nature of Mission  
Duration  
Motivation  
Mobility  
Sense of Orientation  
Adaptability

Crew Characteristics  
Basic Knowledge of  
Cultural Habits of  
Other Crew Members

Safety  
Ease of Movement  
Comfort  
Volume/Person/Activity  
Life Support  
Ease of Maintenance

### CULTURAL DIFFERENCES

World View  
Dietary Habits  
Hygiene Habits  
Political Orientation  
Religious Practices


### SOCIAL

Social Areas  
Activity Arrangement  
Loner Vs. Social Personalities  
Male/Female Roles  
Required Social Interaction  
Entertainment

4-104


Flexibility  
Sensory Stimulation  
Variability  
Personal Identification  
Personal Turf  
Change & Surprise  
Environmental Enhancement  
Sense of Security  
Work/Free Schedules  
View of Outside  
Escape Procedures Known  
Need to "Get Away"  
Living Things (fish tank)  
Aesthetic Values  
Variation of Routine





STORY BOARD OF SEA HABITAT EXPERIENCE

ORIGINAL PAGE 16  
OF POOR QUALITY



STORY BOARD OF SEA HABITAT EXPERIENCE

## PUBLICATIONS

List of Publications - The following publications are available upon request from the author, Thomas C. Taylor, Taylor & Associates, Inc., P.O. Box 1547, Wrightwood, CA 92397, (619-249-6882).

- \* 1. Taylor, T.C. (1980), "Commercial Operations for the External Tank in Orbit," Eighteenth Goddard Memorial Symposium, Washington, D.C., AAS 80-89, March 1980.
2. Taylor, T.C. (1980), "SPS Primary Structure by Another Method," Presentation at the D.O.E. SPS Conference in Lincoln, NE, 17 April 1980.
3. Witek, N.J. and Taylor, T.C. (1980), "Global Benefits of the Space Enterprise Facility Using the External Tank," IAF Tokyo, Paper 80-IAA-46.
4. Witek, N.J. and Taylor, T.C. (1980), "The External Tank as a Large Space Structure Construction Base," IAF Tokyo, Paper IAF-80-A-41.
- \* 5. Taylor, T.C. (1981), "A Commercial Construction Base using the External Tank," 2nd AIAA Conf. on Large Space Platforms, Feb. 2-4, 1981, AIAA-81-0460.
- \* 6. Tewell, J.F., Anderson, J.W. and Taylor, T.C. (1981), "Platform Operations Using the External Tank," 2nd Conf. on Large Space Platforms, San Diego, CA, Feb. 2-4, 1981, AIAA-81-0461.
- \* 7. Taylor, T.C. (1981), "A Modest Habitation Facility in Low Earth Orbit," Fifth Princeton/AIAA/SSI Conf. on Space Manufacturing, May 18-21, 1981, Paper No. 53.
- \* 8. Taylor, T.C. (1981), "A Modest Habitation Facility in Low Earth Orbit," Rome IAF, IAF-81-40.
9. Taylor, T.C. (1981), "Future Potential Uses of Spacelab for Manned Orbital Facilities," Rome IAF, IAA-81-227.
10. Taylor, T.C. (1982), "Orbital Facility Operations Through an Assured Market Sceario," Paris IAF, IAF-82-33.
11. Mobley, T.B. and Taylor, T.C. (1982), "The ET in Orbit as a Space System Material Resource," Paris IAF, IAF-82-392.
12. Mitchell, P.M. and Taylor, T.C. (1984), "Low Cost Science and Astronomy Platforms in Orbit," AIAA 22nd Aerospace Sciences Meeting, Reno, NV, Jan. 9-12, 1984.

## \* COMMERCIAL HUMAN PRODUCTIVITY RELATED

**N85-29564**

**Considerations for Space Station  
Interior Architecture**


**Brand Griffin**



Space  
Station

NASA  
SS-1121

## Neutral Body Postures



4-109


ORIGINAL PAGE IS  
OF POOR QUALITY



Space  
Station

NASA  
SS-1124

## Contrasting Environments



ORIGINAL PAGE IS  
OF POOR QUALITY




Space  
Station

## Acceleration Gradient

SS-1112 NASA

Variable:  
Anthropometric Envelope  
(Nominal)

Acceleration



Implications:

1. Location of controls.
2. Intravehicular and extravehicular garment fit.
3. Angular speed of limbs.

4-111

ORIGINAL PAGE IS  
OF POOR QUALITY




Space  
Station

NASA

35-1003

## Anatomical Change in Zero-G



ORIGINAL PAGE 75  
OF 80. R QUALITY






Space  
Station

NASA

85-1114

# Male Angular Relationships

## Ventral View



4-113




Space  
Station

NASA

88-1113

# Male Angular Relationships

## Profile View



4-114

ORIGINAL PAGE 16  
OF POOR QUALITY




Space  
Station

NASA

SS-1111

## Center of Mass (Segmental Method)



NOTE: Proportional to fluid shift and duration of exposure to zero-g, the c.g. will move in the +y direction.

4-115


ORIGINAL PAGE IS  
OF POOR QUALITY



Space  
Station

NASA  
SS-1123

## Neutral Body Posture Muscular Considerations



ORIGINAL PAGE 15  
OF POOR QUALITY

4-116

C-7



Space  
Station

## Neutral Body Posture/Skeleton

NASA

SS-1122



ORIGINAL PAGE 16  
OF POOR QUALITY

4-117




Space  
Station

NASA

SS-1133

## Zero-G Change to the Vertebrae Column






Space  
Station

## Neutral Body Posture/Pulmonary

NASA  
SS-1127



ORIGINAL PAGE IS  
OF POOR QUALITY



Space  
Station

## Neutral Body Posture/Cardiovascular

NASA  
SS-1130



4-120






Space  
Station

NASA  
SS-1125

## Neutral Body Posture/Vision



ORIGINAL PAGE IS  
OF POOR QUALITY




Space  
Station

## Neutral Body Posture/Orientation

NASA

SS-1131



4-122



Space  
Station

NASA

SS-1126

## Neutral Body Posture and EVA Suit Fit



ORIGINAL PAGE IS  
OF POOR QUALITY




NASA

88-1116

Space  
Station

# Nominal Dimensions of Male Neutral Body Posture Envelope by Percentile Groups Ventral Views





NASA

DS-1110

Space  
StationMale and Female N.B.P. Arranged by Height  
from Projected Astronaut Populations

PERCENTILE	5%
N.B.P.	54
1-6	60.0



PERCENTILE	10%
N.B.P.	54
1-6	60.8



PERCENTILE	25%
N.B.P.	56
1-6	62.5



PERCENTILE	50%
N.B.P.	58
1-6	64.1



PERCENTILE	75%
N.B.P.	59
1-6	65.8



PERCENTILE	5%
N.B.P.	60
1-6	66.2



PERCENTILE	90%
N.B.P.	61
1-6	67.2



PERCENTILE	10%
N.B.P.	61
1-6	67.3



PERCENTILE	95%
N.B.P.	61
1-6	68



PERCENTILE	25%
N.B.P.	62
1-6	68.5



PERCENTILE	50%
N.B.P.	63
1-6	70.2



PERCENTILE	75%
N.B.P.	64
1-6	71.6



PERCENTILE	90%
N.B.P.	66
1-6	73.0



PERCENTILE	95%
N.B.P.	67
1-6	74.3

4-125

ORIGINAL PAGE IS  
OF POOR QUALITY




Space  
Station

## Comparitive Orientation Analyzers

NASA  
BB-1100

4-126



Reduction in number of  
afferent impulses used  
for orientation.

1. No otolith functions.
2. No cutaneous (proprioceptive--must be imposed).


Tunnel Vision  
reduces field  
of sight.



NASA  
DS-1107

Space  
Station

## Work Station Diagram for the Dynamic Zero-G Envelope



Feet Restrained

ORIGINAL PAGE IS  
OF POOR QUALITY




Space  
Station

NASA

88-1186

## Dynamic Zero-G Envelope



NOMINAL LIMITS OF MOVEMENT FROM  
RESTRAINED FOOT POSITION

	5%	10%	25%	MALE				5%	10%	25%	FEMALE			
				50%	75%	90%	95%				50%	75%	90%	95%
a"	58	53	60	62	75	64	65	53	53	55	57	58	59	61
b"	65	66	67	69	70	71	72	59	59	61	63	64	66	67






Space  
Station

## Quantifying Work from Neutral Body Datum

NASA

SS-1132

RADIAL SWING  
ABOUT A JOINT



ORTHAGONAL 3D  
GRID

INDIVIDUAL MUSCLES

4-129

ORIGINAL PAGE IS  
OF POOR QUALITY



Space  
Station


NASA

SS-1108

# Zero-G Activity Analysis (Donning and Doffing IVA Wear)

Work diagram - graphic portrayal  
of individual muscle work superim-  
posed on H.B.P.

Profile, unit extreme  
posture exhibited for  
that activity



Normal view - 3D  
representation of  
activity

Body description by  
major muscle groups

MUSCLE	WORK	TIME
Head-neck		
Shoulder		
Back		
Stomach		
Sides		
Upper Arms		
Lower Arms		
Brain		
Buttocks		
Upper Leg		
Lower Leg		
Ankle-foot		

RESTRAINT  
☐ Free ☐ 1 pt ☐ 2 pt ☐ 3 pt  
 STUN, body  
 OXYGEN  
 CARBON DIOXIDE  
 STUN, content  
 FREQUENCY  
 ORIENTATION  
☐ ☐ ☐ ☐  
 opt read from 1g

Work exerted by muscle  
groups for that activity -  
calibration based on  
measurement through cybex  
isokinetic dynamometer, infrared  
photography, EMG or photogrammetry

Time each muscle  
group is working

Desired restraint  
necessary for effi-  
cient performance.

Heat produced by  
activity

Quantity of  $O_2$  con-  
sumed

Quantity of  $CO_2$  pro-  
duced

Heat produced by  
equipment and other  
crewmembers within  
the immediate vicinity

No. of times the  
activity is performed  
in 24 hour period

Orientation required  
for that activity

ORIGINAL PAGE 19  
OF POOR QUALITY




Space  
Station

## Shuttle Center of Gravity

NASA

SS-004



4-131





ORIGINAL PAGE IS  
OF POOR QUALITY



Space  
Station

## Module Length

NASA  
SS-1100






Space  
Station

NASA

SS-000

## Module Sizing Rationale Incremental Architecture



ORIGINAL PAGE IS  
OF POOR QUALITY

**SPACE  
OPERATIONS  
CENTER**

**NASA**  
SOC-1404


BOEING PROPRIETARY

# Delivery Options

TWIN PRESS VESSELS




SINGLE LAUNCH SPACE STA.



COMMAND/CONTROL MODULE



CREW QUARTERS





4-134

**SPACE  
OPERATIONS  
CENTER**

**NASA**  
SQC-1476

## External View Alternative Module






4-135

ORIGINAL PAGE IS  
OF POOR QUALITY

**SPACE  
OPERATIONS  
CENTER**

**NASA**  
SOC-1487

# Command/Control Module







**SPACE  
OPERATIONS  
CENTER**

**NASA**  
SOC-1483

# Crew Quarters Module




4-137

ORIGINAL PAGE IS  
OF POOR QUALITY


**SPACE  
OPERATIONS  
CENTER**

**NASA**  
80C-1434

## Crew Quarters Mechanical Zone



MECHANICAL PLANNING ZONE




**SPACE  
OPERATIONS  
CENTER**

**NASA**  
SOC-1479


## Command/Control Mechanical Zone

CLOTHES WASH  
(BELOW)



EVA SUIT RECONDITIONING  
ADJACENT TO MECH. ZONE

MECHANICAL PLANNING ZONE




4-139

ORIGINAL PAGE IS  
OF POOR QUALITY

**SPACE  
OPERATIONS  
CENTER**

**NASA**  
SOC-1433

# Comparative Mechanical Zone Placement



**NASA**  
80C-1488

## 4-144




ORIGINAL PAGE IS  
OF POOR QUALITY

# SPACE OPERATIONS CENTER


## Open Space, Command/Control Module

NASA  
SOC-1430




CREW QUARTERS

COMMAND/CONTROL



OPEN SPACE






COMMAND/CONTROL MODULE

4-142

# SPACE OPERATIONS CENTER

NASA  
SOC-1438

## Privacy Gradient




4-143

ORIGINAL PAGE IS  
OF POOR QUALITY

# SPACE OPERATIONS CENTER

NASA  
DOC-1431

## Redundancy



CREW QUARTERS

COMMAND/CONTROL

ORIGINAL PAGE 15  
OF POOR QUALITY








Space  
Station

# Space Station Common Module (Active)

NASA  
SS-1108





ORIGINAL PAGE IS  
OF POOR QUALITY

4-145

**LARGE  
SPACE  
SYSTEMS**

L38-834

## Habitable Service Module Weight Distribution




ORIGINAL PAGE IS  
OF POOR QUALITY

**LARGE  
SPACE  
SYSTEMS**


L88-833

**Habitable Service Module, Interior Layout  
(2 Man Configuration)**


SECTION VIEW



PLAN VIEW



INBOARD PROFILE VIEW





ORIGINAL PAGE IS  
OF POOR QUALITY

4-147

**LARGE  
SPACE  
SYSTEMS**


LSS-038

# Hygiene/EVA Suit Storage Zone



4-148

ORIGINAL PAGE 16  
OF POOR QUALITY




ORIGINAL PAGE IS  
OF POOR QUALITY



Space  
Station

## Hybrid Module/Interior-Exterior

4-150




**LARGE  
SPACE  
SYSTEMS**

LS-944


**Mission Derived Build-up Sequence**

CREW OF 2




1988

CREW OF 2




1989

CREW OF 8




1992

CREW OF 12



1994

SS-005



4-152

*Space Station Module to Module Interface*






Space  
Station

## Berthing Interface Unified Architecture

NASA

88-708



4-153

ORIGINAL PAGE 15  
OF POOR QUALITY




Space  
Station

## Module Sizing Rationale Unified Architecture

NASA

SS-708

4-154






**Space  
Station**

## On-Orbit Subsystem Accessibility

**NASA**

SS-706

4-155



ORIGINAL PAGE IS  
OF POOR QUALITY




Space  
Station

NASA

SS-710

## Unified Module Shown in Command/Control Layout






**Space  
Station**

## Transverse Section Unified Architecture

**NASA**

SS-711



4-157

ORIGINAL PAGE IS  
OF POOR QUALITY




Space  
Station

NASA

SS-712

## Section View of Crew Quarters and Command/Control Modules

4-158






Space  
Station

NASA

## Cutaway View of Unified Space Station Architecture

85-646




ORIGINAL PAGE IS  
OF POOR QUALITY

# SPACE OPERATIONS CENTER

NASA  
SOC-1488

## Adjacency Matrix

4-160



-  CLOSE PROXIMITY
-  MODERATE PROXIMITY
-  SEPARATION
-  NO PREFERENCE









Space  
Station

# Space Station Common Module (Quiet)

NASA

SS-1101



ORIGINAL PAGE IS  
OF POOR QUALITY




Space  
Station

## Space Station Common Module

NASA

SS-1102



ACTIVE

QUIET

4-162




Space  
Station

NASA

SS-1104

## Common Module Elements






4-163

ORIGINAL PAGE'S  
OF POOR QUALITY

**SPACE  
OPERATIONS  
CENTER**

**NASA**  
DOC-1424

**Interior, Single Launch Space Station**






49-164

SPACE  
OPERATIONS  
CENTER

NASA  
DOC 1428

## Reduced Diameter Single Launch Space Station



4-165

ORIGINAL PAGE 15  
OF POOR QUALITY

# SPACE OPERATIONS CENTER

NASA

ROC-1672

## Habitable Service Module Evolution

DECREASING INITIAL COST

EMERGENCY  
EQUIPMENT  
ADDED

SECOND  
REPACKAGING

SOC REFERENCE  
SERVICE MODULE

FIRST ATTEMPT  
REPACKAGING

CREW PROVISIONS  
ADDED TO PERMIT  
EMERGENCY  
SURVIVAL

3.5-METER DIAMETER  
ACCOMMODATES  
THREE PEOPLE WITH  
SIMPLIFIED DEPLOYMENT

DESIGNED TO SUPPORT  
FUNCTION WITH A  
HABITABLE MODULE;  
NOT A "SAFE HAVEN"

TWO-DIAMETER  
DESIGN ACCOMMO-  
DATES TWO PEOPLE  
BUT DEPLOYMENT  
IS COMPLEX

ORIGINAL PAGE IS  
OF POOR QUALITY

47%

4-166




Space  
Station

## Docking and Berthing Ports

NASA

SS-1118

ASSUMING A "GIVEN" DESIGN FOR A DOCKING PORT:



**SMALL PORT PERMITS LARGER DIAMETER MODULE BUT MAY  
MAKE DOCKING/BERTHING MORE DIFFICULT.**

**LARGE PORT PERMITS EASIER DOCKING/BERTHING BUT REDUCES  
DIAMETER OF MODULE.**

**PORT DESIGN NEEDS TO BE ESTABLISHED EARLY IN PROGRAM**

4-167

ORIGINAL PAGE IS  
OF POOR QUALITY




Space  
Station

NASA

SS-1105

## Surface Area Comparison for Two Space Station Modules



4-168






Space  
Station

## IVA Circulation


NASA  
SS-1120

4-169



### AXIAL CIRCULATION

- RACE TRACK—ALL AREAS ARE PASS THROUGH
- BRANCHED—CAN ARRANGE PRIVACY ALONG AXIS AWAY FROM CORE



### TRANSVERSE CIRCULATION

- MINIMUM INTERRUPTION TO ACTIVITIES IN MODULE
- BETTER PRIVACY GRADIENT (CONTROLLED ACCESS)

ORIGINAL PAGE IS  
OF POOR QUALITY.




Space  
Station

NASA  
SS-1119

## Volumetric Efficiency

4-170



ORIGINAL PAGE IS  
OF POOR QUALITY


HUMAN FACTORS IN SPACE STATION ARCHITECTURE:

THE ECLSS MODULE CONCEPT

Prepared for: Space Station Human Productivity Working Group  
1 March 1984

1 N85-29565


# INITIAL ETCLS MODULE WITH AIRLOCK




# POTENTIAL ECLS MODULE EQUIPMENT GROUPING (ECS/Hygiene/Laundry)



# POTENTIAL ECLS MODULE EQUIPMENT GROUPING (ECS/EVA Support)



# POTENTIAL ECLS MODULE EQUIPMENT GROUPING (ECS/Hygiene/Laundry/EVA Support)



# **NOISE IS REDUCED**

## **Sources of Noise in the Primary Vehicle Module**

### **Distributed ECLS**


- **Ventilation fans**
- **Process air fans**
- **Fluid pumps**
- **Compressors**
- **Water processor**
- **Toilets**
- **Shower**
- **Trash compactor**
- **Clothes washer/dryer**
- **EMU operations**
- **Valves**

### **ECLS Module**

- **Ventilation fans**




## AN ECLS MODULE PROVIDES OPERATIONAL FLEXIBILITY



**Scenario: Temporary animal experiments**

# **“CLOSED LOOP” ETCLS MODULE**



## MODULE-TO-MODULE BULKHEAD INTERFACES

4-179

- Air
- Oxygen
- Nitrogen
- Carbon dioxide
- Coolant water
- Potable water
- Condensate
- Wash water
- Wastewater
- Power bus
- Data bus


# **COMMON BULKHEAD DESIGN CONSIDERATIONS**

## **Advantages/disadvantages**

- **Space Station**
  - **Design**
  - **Configuration**
- **Facility/facility services**
- **GSE**

## **AN ECLS MODULE PROVIDES OPERATIONAL FLEXIBILITY**


4-181



**Scenario: Return to earth for retrofit/refurbishment**


# ECLS MANAGEMENT BECOMES MORE EFFECTIVE

## Distributed ECLS



- Costly, complex management

## ECLS Module



- Simple, direct management

## SEPARATE ECLS MODULE ADVANTAGES/DISADVANTAGES

8401B010

- + CENTRALIZED ECLS BENEFITS
  - ECLS BECOMES NON-ISSUE FOR OTHER MODULES
  - LESS ECLS EQUIPMENT/COST
  - REDUCED LOGISTICS MODULE ECLS WEIGHT/VOLUME
  - FACILITATES TWO BATHROOMS
- + MOVABLE/RETURNABLE/GROWABLE/ISOLATABLE
- + FACILITATES NASA PROCUREMENT
- + ISOLATES NOISE
- + FACILITATES TWO AIRLOCKS
- + FACILITATES RETAINING TWO SEGMENT COMMON MODULE
- + USES COMMON STRUCTURE - SINGLE SEGMENT
- + FACILITATES SHUTTLE MANIFESTING AND SPACE STATION ASSEMBLY
- ? PROBABLY AN INITIAL LAUNCH PENALTY
- ? COST ADVANTAGE/DISADVANTAGE - PROBABLY EQUAL FOR IOC  
ADVANTAGE FOR GROWTH STATION

## IMPACT OF THE ECLS MODULE ON HUMAN PRODUCTIVITY

- o MANAGEMENT OF ECLS IMPLEMENTATION BECOMES MORE EFFICIENT
- o OPERATIONAL CHECKS AT KSC ARE SIMPLIFIED AND DRAMATICALLY REDUCED
- o RETROFIT/REFURB MAY BE MORE EASILY PERFORMED ON THE GROUND BY EXPERTS
- o INTERRELATED FUNCTIONS ARE LOCATED TOGETHER
- o INTERMITTENT NOISES AND ODORS ARE ISOLATED
- o LESS HARDWARE SIMPLIFIES MAINTENANCE
- o ON-ORBIT SERVICING DOESN'T INTERFERE WITH PRODUCTIVE ACTIVITIES



# HABITABILITY SLEEP ACCOMMODATIONS

PRESENTATION TO  
SPACE STATION TASK FORCE


1 MARCH 1984

H. T. FISHER, SUPERVISOR

4-185

N85-29566

## SELECTED STATION INFLUENCING FACTORS






## WARDROOM - GENERAL REQUIREMENTS

WARDROOM  
HABITABILITY  
GENERIC  
FUNCTIONS



- A. SLEEPING ACCOMMODATIONS
- B. REST PLACE
- C. ENTERTAINMENT EXTENSION
- D. DRESSING AREA
- E. PERSONAL ITEM STOWAGE
- F. BODY RESTRAINT OPTION
- G. COMMUNICATIONS
- H. TOTAL PRIVACY
- I. EXTERNAL VIEWING
- J. GROOMING PROVISIONS
- K. WRITING WORK AREA
- L. SOUND ISOLATION

# SLEEP QUARTERS CONCEPT A




ORIGINAL PAGE IS  
OF POOR QUALITY

# SLEEP QUARTERS CONCEPT B




CIRCULAR SLEEP MODULE




ORIGINAL PAGE 19  
OF POOR QUALITY


## SLEEP QUARTERS CONCEPT



## SLEEP COMPARTMENT—BUNK AREA DETAILS




CONNECTED  
CAROUSEL SLEEP  
MODULE




ORIGINAL PAGE IS  
OF POOR QUALITY

## SLEEP BUNK—PLAN VIEW






## SLEEP BUNK—PLAN VIEW






# SLEEP/REST VOLUMETRIC FOR 5th TO 95th%tile FEMALES/MALES\*




\* BASED ON NASA PUB 1024

# VERTICAL VS HORIZONTAL WARDROOM



ORIGINAL PAGE IS  
OF POOR QUALITY

## WARDROOM SUB-MODULE - "MODULARITY"



- A. WARDROOM IS SUB-MODULE ASSEMBLY
- B. ASSEMBLY IS STAND-ALONE UNIT
  - PERMITS PARALLEL MFG
  - FLEXIBILITY IN SCHED. INSTALLATION
- C. ASSEMBLY IS SIMPLE BARREL CONFIGURATION
  - EIGHT (8) SEGMENTS
  - INDIVIDUAL SEGMENT MANUFACTURING
- D. UTILITIES I/F RING
  - SIMPLE I/F TO UTILITIES
  - 360° POTENTIAL I/F TO RING
  - RING ACCEPTS:
    - ECLSS PLENUM DUCTING (LOOP)
    - SIGNAL/DATA LINES (IN/OUT)
    - POWER CABLES
  - STAND-ALONE UNIT - BOLTS ON
  - INDIVIDUAL MANUFACTURING

## TOP TOP-TIER ADVANTAGES OF THE SARA' CONCEPT

- A. OVER 100 CU FT PER CREWPERSON
- B. HORIZONTAL (EARTH-LIKE) SLEEP/REST ACCOMMODATIONS
- C. SINGLE WARDROOM CAN OPEN TO ADJACENT WARDROOM
  - DOUBLES 'OPEN AREA'
  - ADJACENT WARDROOM ALWAYS VACANT ASSUMING:
    - 2 OR 3 SHIFT OPS OR
    - LESS THAN 8 CREW (e.g., 4)
  - PERMITS 2 PEOPLE TO FACE ONE-ANOTHER IF OTHER WARDROOM TEMPORARILY USED
- D. ADDED 'OPEN AREA' FURTHER AVAILABLE AS EACH WARDROOM FACES:
  - OPEN CORRIDOR 60 IN DIAMETER
  - OPPOSITE WARDROOM (NOT BEING USED) - OPEN AREA
- E. WARDROOM SUB-ASSEMBLY (8 WARDROOMS ) ONLY 91 IN LONG (OVERALL)
  - SEVEN (7) FT. INTERNAL
  - ONE (1) IN. END PLATES + INSULATION
  - FOUR (4) IN. FOR UTILITIES I/F RING
- F. SIMPLIFIED SUB-ASSEMBLY MODULAR CONCEPT
  - FABRICATION
  - INSTALLATION
- G. PORTHOLES ARE ALL IN ONE NARROW CIRCUMFERENTIAL 'RING SEGMENT' - STRUCTURAL ADVANTAGE
- H. LESS LENGTH USED (X AXIS) THAN VERTICAL 'BUNKS'
  - SAVES 20% OF SHORT MODULE LENGTH!

\* SLEEP AND REST ACCOMMODATIONS

DESIGN OF CONFINED ENVIRONMENTS

PRESENTATION MADE AT AMES RESEARCH CENTER  
MOFFIT FIELD, CALIFORNIA

MARCH 1, 1984

I. DESIGN VOCABULARY AND HISTORY

- A. THE REPETITION OF FORMS IN RELATIONSHIP TO LAND BASED STRUCTURES AND SPACE BOUND OBJECTS
- B. THE COMPOSITION OF SHELTER AND ITS QUALITIES IN REGARD TO HUMAN NEEDS

II. PROTOTYPE FOR EXPERIMENTATION OF LIVING/HOME ENVIRONMENT

- A. DESIGN PHILOSOPHY
  - 1.DETERMINING BASIC HABITABILITY NEEDS
  - 2.CREATING A FORM THAT RETAINS THE BASIC NEEDS WITHIN A STRUCTURE THAT UTILIZES CURRENT TECHNOLOGY
- A. DESIGN CONCEPT - FLOOR PLANE
  - 1.MODULES AND THEIR ABILITIES TO REVEAL, CONCEAL OR TRANSFORM TO MEET THE NEEDS OF HABITABILITY
  - 2.ELECTRONICS AND THEIR CAPACITY TO MANIPULATE THE ENVIRONMENT TO THE FUNCTIONS AND THE COMFORTS OF THE USER


III.PROTOTYPE FOR EXPERIMENTATION OF WORK/OFFICE ENVIRONMENT

PROJECT RETAINS DESIGN PHILOSOPHY AND SYSTEMS AS DESCRIBED ABOVE AND EXPANDS TO ENCOMPASS FUNCTIONALITY OF EXECUTIVE RESPONSIBILITIES IN REGARD TO COMMUNICATIONS, CONFERENCE, ACCESS TO INFORMATION AND CREATIVE PRODUCTION.

VGM068

ORIGINAL PAGE 15  
OF POOR QUALITY

N85-29567



# CUSTOMER AND MISSION INFLUENCES ON SPACE STATION ARCHITECTURE

4-199

Fritz Runge

# ARCHITECTURAL CONSIDERATIONS IN A SPACE STATION

VFV802

- **Uses (Missions)**      **Science, Applications, Commerce, Defense**  
(Integrated and Isolated)
- **Occupants**      **Scientists, Engineers, and Technicians**
- **Activities**      **Interior: Habitation, Control, Research, Production,**  
Maintenance, Logistics with IVA  
**Exterior: Berthing, Sensing, Assembly/Checkout,**  
Maintenance, and Logistics with EVA
- **Interfaces**      **Shuttle, Attached Payloads, Free-Flight Payloads,**  
and Long- and Short-Range Excursion Vehicles
- **Utilities**      **Atmosphere, Water, Power, Data, Communications,**  
Thermal
- **Locomotion**      **Orientation, Reboost, Manipulation, Excursion**
- **Environments**      **Exterior: Low Earth Orbit and Operations**  
**Interior: Life Sustaining and Protecting**  
Stage and Payload Storage
- **Technology/Cost**      **Budget-Dependent: Development vs Operations**



# DEVELOPMENT OF SPACE STATION ARCHITECTURE

VGB597

Objective

- Definition of User and Payload Needs
- Development of Mission Scenario

Approach

- Profiling of User and System Functions
- Characterization of Interfaces
- Preliminary Grouping of Functions

Solution

- Packaging of Functions Into Modules
- Design of System and User Accommodations

Evaluation

- Analysis of Mission Accomplishment

# MANNED PLATFORM ACTIVITY SPECTRUM

VGM113

(Science) (Technology) (Commercial)  
(National and International)

## Interior


- Payload Operations
  - Life Science
  - Material Processing Applications
  - Technology Demonstrations
- Control Center(s) for:
  - Interior Operations
  - Exterior Operations/Accessories
  - Exterior Payloads
  - Maneuvering Vehicles
- Habitation/Recreation
- Maintenance/Logistics
- Traffic (Daily Routine and Periodic
- Safe Haven
- Exterior Viewing
  - Operations
  - Sight-Seeing

## Exterior

- Attached Payload Operations
  - Science Instruments
  - Applications Instruments
  - Large Space Systems
  - Development of:
    - Technology (Prototypes, Performance Measurement)
    - Operations (Assembly, Alignment, EVA)
  - Assembly Accessories
  - Hi-Alt-Vehicle Buildup/Stowage/
  - Launch Spacecraft Servicing
- Attached/Detached Payload Operations (Tended/Tethered/Teleoperated)
  - Material-Processing
  - Free Flyers
  - Rendezvous Testing, Tow/Dock
  - Services and Low-G Payloads
  - Co-Orbiting Platform
- Sustaining Resource Installations
- Shuttle Interaction Operations


# BASIC SPACE STATION ELEMENTS

4-203

ORIGINAL PAGE IS  
OF POOR QUALITY

# INITIAL FUNCTIONAL GROUPING

4-204



# REQUIREMENTS FULFILLMENT CONGREGATION (HIGH-MODULARITY CONCEPT)

VFR079

- POWER (11 - 25 kW)
- COMM/DATA
- THERMAL RADIATION
- ATTITUDE CONTROL
- ALTITUDE REBOOST
- EXTERIOR PAYLOAD INSTALLATIONS

SUBSYSTEMS  
MODULE  
(SPACE PLATFORM)

- CENTRAL BUILDUP  
PORTS & PASSAGE
- UTILITIES DISTRIBUTION
- LIFE SUSTENANCE  
(90 DAYS)
- BASIC CHEN (2)  
ACCOMMODATIONS
- MINI-CONTROL  
CENTER
- SAFE HAVEN

CENTRAL  
SUPPORT AND  
BUILDUP MODULE

BASIC  
CHEW MODULE

- LOGISTICS
  - CREW SUPPLIES
  - PAYLOADS
  - PAYLOAD SUPPLIES
  - MANNED PLATFORM  
AND SPACE PLATFORM  
SPACES

INTERIOR ACCESS  
LOGISTICS  
MODULE

- EXPANDED  
CREW ACCOMODATIONS  
AND CONTROL CENTER

HABITAT MODULE

- EXPANDED EXTERIOR  
PAYLOAD INSTALLATION

EXTERIOR OPERATION  
MODULE

- EXPANDED INTERIOR  
PAYLOAD INSTALLATION

DEDICATED PRESSURE  
PAYLOAD MODULE

- SUBSYSTEM UPGRADES

IVA INSTALLED  
SUBSYSTEM MODULE

- LOGISTICS ASCENT
  - PLANNED
  - UNPLANNED

SHUTTLE (90 DAY CYCLE)  
EXPENDABLE  
LAUNCH VEHICLE

- EMERGENCY STATION  
ABANDONMENT

REENTRY CAPSULE

- EXTENDED REACH  
LOADING


PLATFORM MOUNTED  
REMOTE MANIPULATOR

4-205

ORIGINAL PAGE 16  
OF POOR QUALITY

# SPACE STATION ELEMENTS

VFX302



ORIGINAL PAGE IS  
OF POOR QUALITY

# CONFIGURATION ASPECTS OF PAYLOAD ACCOMMODATIONS

VGf312

## Payload Type

- Internal .....
  - Built-In
  - Transient
- External .....
  - Non-Viewing .....
  - Viewing
    - Stellar .....
    - Solar .....
    - Earth .....
  - Large Assembly .....
  - Periodically Serviceable .....
  - Small Reusable Stages .....
  - Large Reusable Stages .....
  - Large Propellant Storage .....

## Location Type

- Pressurized Module
- Any Berth
- Space-Directed
- Earth-Directed
- Large Free Volume
- Close-In Access Aids
- Possibly Enclosed
- Semi-Remote Berth
- Semi-Remote Berths
- (Near Station Centerline)

## Constraints

- Approach/Exit Movement Corridors
- Solar Array Shadowing
- Radiator Reflections
- Manipulator Access (Shuttle/Space Station)
- Multiple Orbiter Berthing Ports
- Interim Berthing During Assembly or Exchange

Exterior Payload Operations/Time Impact Configuration Significantly

4-207

ORIGINAL PAGE 18  
OF POOR QUALITY

# ARCHITECTURE OPTIONS FOR PAYLOAD ACCOMMODATIONS

VGM110

## **Laboratory Module(s)** (Interior Payloads)

- Lab Functions Only
- Lab and Crew Qtrs Hybrid
- Lab and Sta-Control Hybrid
- Dedicated Types
- General Purpose Types
- Short Module
- Long Module/Unpartitioned
- Long Module/Partitioned
- Some Long, Some Short
- Accessories:
  - Built-In Radiator
  - Scientific Airlock

## **Service Center** (Exterior Payloads)

- Integrate With Multiple Docking Adapter
- Separate Multi-Berth Unit (Trusswork) (Tunnel)
- One Unit/10 Berths (All-In-One)
- Two Units/5 Berths (i.e. Modular)
- Incorporates Big Manipulator
- Incorporates Radiators
- Articulating (For Broad Op's Flexibility)
- Central, Top or End-Mounted
- Rotating Berths For Maximum Viewing Payload, or Assembly Op's Flexibility
- Hangar Provisions (Pressurized/Unpressurized)



# SPECTRUM OF SERVICES SCENARIOS (RELATED TO SPACE STATION)

VG F194

## ■ User Types and Service Locations:

	<u>On Station</u>	<u>Off Station</u>
• Space Station Attached Payloads	✓	
• Free Flying Spacecraft	✓	Via TMS
• Teleoperator Maneuvering System	✓	Via TMS
• Space Platform	?	Via TMS
• Space Platform Attached Payloads	?	Via TMS
• Reusable Orbit Transfer Vehicles	✓	
• ROTV-Boosted Free-Flying Spacecraft	✓	
• ROTV-Boosted Servicer	✓	

# SPACE STATION SERVICE CENTER

## Objective

- Provide a Broad Range of Enabling and Sustaining Services to Resident and Transient Payloads

## Service Functions (in Graduated Capability/Time)

- |              |                 |                       |
|--------------|-----------------|-----------------------|
| ■ Berthing   | ■ Replenishment | ■ Stowage             |
| ■ Activation | ■ Enclosure     | ■ Checkout and Launch |
| ■ Deployment | ■ Replacement   | ■ Manipulation        |
| ■ Diagnosis  | ■ Modification  | ■ Maintenance         |
| ■ Alignment  | ■ Assembly      | ■ Surface Treatment   |

## Types of Payloads (Nasa, DoD, Commercial, Foreign)

- |                                   |   |
|-----------------------------------|---|
| ■ Self-Propelled Spacecraft       | ■ Palletized Payloads)<br>(Resident/Non-Resident) |
| ■ Propulsion-Staged Spacecraft    | ● Science   |
| ■ Teleoperator Maneuverer         | ● Earth Applications                              |
| ■ Orbit Transfer Vehicle(s)       | ● Technology                                      |
| ■ Reusable Orbit Transfer Vehicle | ■ Space Platforms (?)                             |

# SPACE STATION SERVICE CENTER (CONT.)

## Major Configuration Elements


- Servicing Control Centers (General and Dedicated)
- Articulated, Truss Beams(s) with Berthing Ports
- Power, Data and Communications Distribution
- Liquid, Gas Storage and Distribution Systems
- Manipulator(s): Major and Localized — Minor Types
- Enclosure(s): Permanent and Portable
- EVA Access/Assistance Equipment
- Interior Stowage (Replacement/Modification items)
- Exterior Stowage (Interim and Long Term Berthing)
- Tool and Supplies Stowage
- Diagnostic and Checkout Equipment
- Work Bench Areas
- Directed Lighting

## Configuration Constraints

- Extensive Crew Visibility of Operations
- Safe Rendezvous and Exit Flight Corridors
- Efficient Shuttle RMS Loading Access or Handover
- Extensive Payload (Berth) Separation for Viewing or Movement Freedom
- Minimal Solar Array Shadowing and Radiator Reflection


# ATTACHED PAYLOAD AND MULTI-SERVICE CENTER

4-212



ORIGINAL PAGE IS  
OF POOR QUALITY

# LARGE DIAMETER REFLECTOR ASSEMBLY



## Space Station Accommodations

- Large Span Mounting Beam. With Utilities and Articulation
- Long Reach Manipulator
- Interim Stowage Locations For Construction Elements
- Operational Viewing
- Internal Control Center
- EVA Crew Capabilities
- Possible Enclosure/Contamination Shield Provisions

# SPACE STATION MISSIONS

## EARLY SET (1991-93)

VGK162

### Missions Externally Attached to SS Base (Or Co-Orbiting Platform)

h12-h

SAA	0001	Cosmic Ray Nuclei
SAA	0002	Space Plasma Physics
SAA	0003	Solar Optical Telescope
SAA	0004	Shuttle IR Telescope Facility
SAA	0006	Starlab
SAA	0201	LIDAR Facility
SAA	0306	CELS Pallet
COM	1202	EOS Production Units
COM	1203	ECG Production Units
COM	1105	Communications Test Lab
TDM	2010	Materials Performance
TDM	2060	Deployment/Assembly/Construction
TDM	2070	Structural Dynamics
TDM	2080	Design Verification
TDM	2210	Large Space Antenna Technology
TDM	2260	Earth Observation Instrument
TDM	2310	Fluid Management Technology
TDM	2410	Attitude Control Technology
TDM	2420	Figure Control Technology
TDM	2460	Telepresence and EVA Technology
TDM	2470	Interactive Human Factors
TDM	2510	Environmental Effects Technology
TDM	2560	Satellite Servicing Technology
TDM	2570	OTV Servicing Technology

### Missions Accommodated Inside SS Laboratory Modules

SAA	0307	Life Science Laboratory
COM	1201	MPS Lab #1
TDM	2020	Materials Processing
TDM	2520	Habitation Technology
TDM	2530	Medical Technology
TDM	2580	On-Board Operations Technology

### Free-Flyer Missions Serviced At/By SS Base

SAA	0012	Space Telescope
SAA	0013	Gamma Ray Observatory
SAA	0014	X-Ray Timing
SAA	0016	Solar Max Mission
SAA	0017	AXAF
SAA	0019	Far UV Spectroscopy

### Planetary Missions Supported at SS Base


SAA	0102	Lunar Geochemical Orbiter
SAA	0105	Titan Probe

### Missions Supported By Polar Platform

SAA	0202	Earth Sciences Research
COM	1019	Stereo Multi-Linear Array

# CUSTOMER ACCOMMODATION CONSIDERATIONS IN ARCHITECTURE

VGM111



FRIDAY

		Page
Ames Mock-up Ideas	M. Cohen	5-1 to 5-3
Simulation for Human Factors Research	D. Nagel	5-4 to 5-7
EVA Orbital Servicing Equipment	H. Vykukal	5-8 to 5-10
SS Models, Mockups and Simulators	K. Miller	5-11 to 5-18
Mock-up and Human Productivity Studies	T. Fisher	5-19 to 5-38
Experiences with Neutral Buoyancy Testing Mockups	R. Dellacamera	5-39 to 5-47
Rockwell Experience Applications to Ames Space Station Mockup Habitability/Productivity Studies	J. Roebuck	5-48 to 5-64
Role of Mock-ups in the Development of Orbital Replaceable Units (ORU)	G. Johnson	5-65 to 5-90






AMES MOCK-UP IDEAS  
FOR SPACE HUMAN FACTORS RESEARCH

MARC M. COHEN

ARCHITECT

MARCH 2, 1984





# SPACE STATION MODULE END-CAP OPTIONS



ELLIPTICAL END-CAP (BOEING B26)  
W/ OFFSET PORT & OBSERVATION STATION

HEMISPHERICAL END-CAP (LOCKHEED)  
W/ SHEAR PULL CENTER & LONGITUDINAL GORED

CONICAL END-CAP (JSC)  
SINGLE SHEAR SPIN SECTION  
WITH SQUARE SEPERATE NECK SUPPORT




HYBRID CONICAL SECTION & HEMISPHERE  
AMES TRI-TET WITH HEXAGONAL GORED

HEMISPHERICAL WITH STRETCHED PORT  
AMES PLANAR-TRIANGULAR

DATE	BY	CHKD	APP'D
10/1/68	J. L. A.		
AMES RESEARCH CENTER SPACELAB CENTER			
SPACE STATION MODULE HYBRID END-CAP OPTION FACE AND OBSERVATION STATION			
SCALE	1/4" = 1'		
BY	J. L. A.		
CHKD			
APP'D			
ALPHABETICAL A			

ORIGINAL PAGE IS  
OF POOR QUALITY



1. REMOVE (1) 2" x 2" WOOD COUNTRY RAIL  
MOST WOODS OF TEMPORARY POLE
2. INSTALL STEEL PERMANENT EXHAUSTION ON  
LEFT SIDE TO SUPPORT BACK CHAIR  
W/ 2" x 2" BEAM & TO EXHAUST LARGER  
ROOMS
3. EXHAUST (2) SUPPLY AIR OUT FROM  
CENTER WALL TO OUTSIDE WALL
4. REMOVE 2" x 2" SUPPLY AIR OUT
5. REMOVE ALL (2) 2" x 2" EXHAUST  
RADIATING EAST/WEST
6. RELOCATE 2" x 2" SUPPLY HEADS  
ON REQ'D BY DUCT RELOCATION

[illegible]

N85-29568

SIMULATION FOR HUMAN FACTORS RESEARCH

DAVID NAGEL

AEROSPACE HUMAN FACTORS RESEARCH DIVISION

NASA-AMES

MARCH 2, 1984

A CENTRAL QUESTION: FIDELITY

#### VERY RECENT TRENDS IN AERONAUTICAL SIMULATION

- For Training: lower fidelity
- For R&D: greater fidelity (including full mission)

#### CRITERIA FOR TRAINING DEVICES:

##### TRAINING EFFECTIVENESS

- Usual Methods of Evaluation
  - Transfer of training (costly & rare!)
  - Judged effectiveness (generally fidelity - perhaps irrelevant)
- In Aviation, Little Empirical Support for Incremental Effectiveness of Hi VS Lo Fidelity (& Very High Cost)
- Increased Emphasis on Training System Effectiveness - Not Training Device Effectiveness
- Developing Strategy is to Concentrate on Low Cost Devices, & Improved "Instructors" & Curricula Using Advanced Instruction Notions  
  
(knowledge of results, adaptive systems, perceptual learning, S/R, & motivational principles, knowledge engr, ....)

## CRITERIA FOR R&D DEVICES:

### ABILITY TO GENERALIZE RESULTS

- Usual Methods of Evaluation
  - Engineering fidelity
  - Psychological fidelity
- In Aviation, Great Deal of Evidence Linking Fidelity to "Effectiveness"
- Problems
  - Engineering fidelity costly & sometimes extremely difficult to achieve.
  - Psychological fidelity is multidimensional (perceptual, cognitive, social, workload, ...)
  - Some necessary human measurement models don't exist.
  - Fidelity criteria typically are unknown, costly to determine (requires verification in flight, similar to transfer paradigms)

### AVIATION R&D SIMULATION

- Resulting Trend is to Rely on Empirical Results (re-effectiveness) and Increasing Task & Mission Fidelity

# FULL SYSTEM/FULL MISSION SIMULATION FOR HUMAN FACTORS RESEARCH

- In Aviation
  - Becoming increasingly indispensable tool for variety of human factors studies (operational problems, crew-system integration, ...)
- In Space
  - True full mission simulation very costly.
  - Fidelity of mockups should reflect a priori requirements for degree of confidence needed.
  - Full system (not mission), part system, & lower degrees of fidelity may be enough for many study areas.

VYKUKAL

AMES RESEARCH CENTER -- AERO-SPACE HUMAN FACTORS DIVISION


### AX-5 DESIGN OBJECTIVES

- PERFORMANCE
  - 14.7 PSI PRESSURE
  - HIGH MOBILITY
  - LOW TORQUE JOINTS
  - LOW LEAKAGE (<50SCC/MIN)
  - COMFORT
  - EASE OF DONNING/DOFFING
- MECHANICAL DESIGN
  - ALL HARD STRUCTURES
  - MULTIPLE WALL W/MATERIALS OPTIONS
  - [REDACTED]
  - [REDACTED]
  - DRY LUBRICANTS
  - TOTAL MODULARITY
  - LOW MAINTENANCE/LONG LIFE JOINTS
  - HAZARD PROTECTION
    - RADIATION
    - DEBRIS
    - PROPELLANTS
    - THERMAL
    - SHARP CORNERS
  - MANUFACTURING REPEATABILITY




ORIGINAL PAGE 18  
OF POOR QUALITY

FIRST VARIATION ON AX-5 DESIGN



ORIGINAL PAGE IS  
OF POOR QUALITY

SECOND VARIATION ON AX-5 DESIGN



LSS-1224

# **Space Station Models, Mockups, and Simulators**

by

**Keith H. Miller**

**Alan Osgood**

**Space Station Human Productivity Working Group Meeting  
NASA-Ames Research Center  
February 27–March 2, 1984**

5-11

**N85-29569**



**Space  
Station**

**NASA**

LSS-1225

- **Types of Boeing models, mockups and simulators**
- **Classes of models, mockups and simulators**
- **Use of models in 767 program**
- **Use of models, mockups, and simulators for Space Station Program**



**Space  
Station**

**NASA**

LSS-1226

## **Types of Boeing Models, Mockups, and Simulators**

---

- **Stationary work stations** — **Flight decks, E-3A multipurpose consoles, communications consoles, gunner stations etc.**
- **Larger work areas** — **Galleys, cargo handling, E-3A & E-4B mission crew areas, maintenance areas**
- **Leisure areas** — **Airplane passenger cabins, lavatories, E-3A & E-4B rest areas**
- **Complete facility** — **Airplane, office and production areas**



**Space  
Station**

## **Classes of Models, Mockups and Simulators**



LSS-1227

<u>Class</u>	<u>Use</u>	<u>Users</u>
<b>Models</b>		
1/100th-1/2.0th scale	- Compare variety of concepts	Staff and engineering
1/10-1/4th scale	- Area layout and access	
	- Personnel accommodation	
<b>Full scale mockups</b>	- Progressive development of design	Staff and engineering
<b>Class 1</b>	- Foam core, wood & paper of overall configuration	
<b>Class 2</b>	- Subsystems mockup (plumbing, wiring)	
<b>"Lighted" mockup</b>	- Lighting, display and control	Manufacturing
<b>Class 3</b>	- Real equipment & materials (not qualified)	
<b>Engineering simulators</b>	- Develop and test design and procedures	Engineering
<b>Developmental Configuration</b>	- Single task or subsystem	
	- Integrated tasks, and subsystems	
<b>Training devices</b>	- Train and test personnel	Training
<b>Part task trainers</b>	- Single task	
<b>Procedures trainers</b>	- Integrate tasks	
<b>Training simulators</b>	- Realistic situation	



**Space  
Station**

**NASA**

LSS-1228

## **Characteristics of Models**

---

- **Inexpensive side by side comparison of concepts and designs**
  - **Humans much better at comparative judgments than absolute judgments**
  - **Provides 3-D views and perspective**
  - **Easy to transport**
- **Used by technical staff, engineering, marketing research and public relations**
- **Range of model scales**
  - **1/100th–1/20th scale    –    Area layout and access**
  - **1/10th–1/4th scale        –    Component layout and personnel accommodation**
- **Evaluations of interior layouts and color schemes closely approximate evaluations of actual interiors**



**Space  
Station**

## **Use of Models for 767 Program**

**NASA**

LSS-1229

- **Verification of value of models for design evaluation**
- **Evaluation of alternative passenger cabin configurations**
- **Prediction of 767 market share in competitive markets**
- **Demonstration of 767 passenger appeal to airlines**





**Space  
Station**

**NASA**

LSS-1230

## **Computerized Human Factors Tools**

---

- **Analyses for anticipated user groups**
  - **Conducted before hardware built**
- **Anthropometry**
  - **Accessibility of controls**
- **Vision**
  - **Readability of displays**
  - **Vision through windows**
- **Timeline evaluation**



**Space  
Station**

**NASA**

LSS-1231

## **Approach for Space Station**

---

- **Maximize use of CAD/CAM**
  - **Concept development and evaluation**
  - **Early problem identification and resolution**
- **Maximize use of models**
  - **Comparison of alternative concepts**
  - **Initial development of procedures**
  - **Initial training**
- **Use partial mockups, subsystem simulators, and part task trainers to maximum utility**
- **Minimize demands on complete mockups, engineering simulators and training simulators**

FISHER

# **MOCKUPS AND HUMAN PRODUCTIVITY STUDIES**

Presentation To

**SPACE STATION**

**HUMAN PRODUCTIVITY WORKING GROUP MEETING**

**NASA AMES**

2 MARCH 1984

5-19

85-29570

**THE MAGIC OF MOCKUPS  
AND  
THE MYSTIQUE OF HUMAN PRODUCTIVITY**

Presentation To

**SPACE STATION**

**HUMAN PRODUCTIVITY WORKING GROUP MEETING**

**NASA AMES**

2 MARCH 1984

SPACE  
STATION



PROGRAMS

## OBJECTIVE

TO PRESENT IDEAS FOR GROUP CONSIDERATION/DISCUSSION

RELATIVE TO:

- MOCKUP CANDIDATES
- MOCKUP UTILIZATION
- MOCKUP DEVELOPMENT  
SCHEDULES/SEQUENCE



## NASA AMES\* SUGGESTED MOCKUP TOPICAL COVERAGE

---

1. VOLUME
2. ORIENTATION
3. CIRCULATION
4. PRIVACY
5. GROUP GATHERING
6. VISUAL SYSTEMS
7. LIGHTING
8. VIBRO/ACOUSTICS
9. FUNCTIONAL ORGANIZATION
10. OTHER

5-22

\* Mr. Marc Cohen - ARC


---

---




## MOCKUP CANDIDATES WHICH AID IN HUMAN PRODUCTIVITY INVESTIGATIONS AND ASSESSMENT

5-23



## MOCKUP CONSIDERATIONS







## MOCKUP CANDIDATES AND USES

### SAFE HAVEN ZONE(S)

1. ACTIVITY VOLUMETRICS
2. EMERGENCY ECLSS ITEMS & CONTROL/MONITOR
3. 'ZONE' VOLUMETRICS FOR UP TO X CREW
4. RESCUE INTERFACES
5. RESCUE DEVICES STOWAGE
6. EMERGENCY EQUIPMENT STOWAGE/ACCESS
7. COMMUNICATION PANEL/DEVICE LOCATION
8. VIEW PORT(?)
9. FOOD PREPARATION, STOWAGE & WASTE
10. HYGIENE CONDUCT & WASTE HANDLING
11. CONTAMINATION CONTROL
12. EMERGENCY SLEEP PROVISIONS
13. VENTILATION & ODOR CONTROL
14. PERSONNEL ACCOUTREMENTS
15. PRIVACY
16. GENERAL STOWAGE & ACCESS
17. EMERGENCY ITEM CHECK & ACCESS
18. MEDICAL & FIRST AID SUPPLIES/STOWAGE
19. OTHER

### GENERAL PURPOSE WORKSTATION(S)

1. DESIGN FOR O-G FEATURES/USE
2. RE-LOCATION POTENTIAL
3. BASIC STATION RECONFIGURABILITY
4. SIZE & LAYOUT
5. UTILIZATION VOLUMETRICS
6. ANTHROPOMETRIC UTILIZATION- POPULATION (?)
7. AMBIENT ILLUMINATION IMPACT
8. SEE-OVER VS DECK-TO-CEILING/OVERHEAD
9. MAINTENANCE ACCESS - OPTIONS
10. CABLE RUN(S) AND INTERFACES
11. COOLING/VENTILATION & DUCTING INTERFACES
12. MODULARITY & COMMONALITY
13. BASIC DISPLAY/CONTROL LAYOUT
14. INTRA-STATION D&C COMMONALITY
15. CREW USER EASE & SIMPLICITY
16. 'ISOLATION' FEATURES AS REQUIRED
17. STATION STATUS INDICATION
18. EMERGENCY WARNING & COMMUNICATION
19. OTHER



## MOCKUP CANDIDATES AND USES

### MAINT/SERVICING (PRESS.) AREA

### SLEEP QUARTERS AREA

1. ACTIVITY VOLUMETRICS
2. PACKAGE TRANSFER - IV TO EV OR EV TO IV
3. SPACECRAFT ELEMENT ENTRY/EXIT VOLUME
4. SPACECRAFT ORU ENTRY/EXIT VOLUME
5. INTERNAL LAYOUT/ARRANGEMENT/ARCHITECTURE
6. INTERFACE TO AIRLOCK
7. AREA SUB-ZONE LAYOUT
8. I/F TO SPARES/STOWED ITEMS
9. STOWED ITEM VOLUMETRICS
10. CREW WORK STATION(S)
11. CREW WORK STA. MAINTENANCE ACCESS
12. CONTAMINATION MANAGEMENT
13. EMERGENCY PROVISIONS & STOWAGE
14. UNIQUE WORK STATION FEATURES
15. TOOLS/AIDS STOWAGE/ACCESS & CLEANING
16. ITEM PROTECTION OR ISOLATION
17. SPECIAL ITEM HANDLING DEVICES/ITEMS
18. EQUIPMENT/ITEM/ORU TRANSFER DEVICES
- 19. EMERGENCY ECLSS PANEL ACCESS & WARNING
20. SAFE HAVEN INTEGRATION (?)
21. OTHER-MANY!



## MOCKUP CANDIDATES AND USES

### MULTIPLE DOCKING ADAPTER

#### 1. VOLUMETRICS

- PKG & MODULE PASS-THRU
- S/C ELEMENT PASS-THRU
- ACTIVITY VOLUMETRICS
- SUIT DON/DOFF VOLUME (8 CREW?)
- ITEM TRANSFER DEVICES VOLUME

#### 2. CREW FUNCTIONS

#### 3. INTERNAL ORIENTATION LAYOUTS

#### 4. INTERNAL ACCOUTREMENTS

#### 5. ILLUMINATION

#### 6. HATCH SWING & STOWAGE

#### 7. WINDOW LOCATIONS

#### 8. CONTROL PANEL LOCATIONS

#### 9. EMERGENCY PROVISIONS/DEVICES

#### 10. CONTAMINATION CONTROL TECHNIQUES

#### 11. EMERGENCY ECLSS

#### 12. OTHER

### AIRLOCK

#### 1. VOLUMETRICS

- PKG & MODULE PASS-THRU
- S/C ELEMENT PASS-THRU
- ACTIVITY VOLUMETRICS
- SUIT DON/DOFF VOLUME (8 CREW?)
- ITEM TRANSFER DEVICES VOLUME
- EVA TOOLS & AIDS STOWAGE

#### 2. CREW FUNCTIONS

#### 3. CREW TRANSFER - ABLE & INCAPACITATED

#### 4. INTERNAL ORIENTATION LAYOUTS

#### 5. INTERNAL ACCOUTREMENTS

#### 6. ILLUMINATION

#### 7. HATCH SWING & STOWAGE

#### 8. WINDOW LOCATIONS

#### 9. CONTROL PANEL LOCATIONS

#### 10. EMERGENCY PROVISIONS/DEVICES

#### 11. CONTAMINATION CONTROL TECHNIQUES

#### 12. EMERGENCY ECLSS

#### 13. ALTERNATE USES

- o HYPERBARIC CHAMBER & SUB-AIRLOCKS
- o SAFE HAVEN



## MOCKUP CANDIDATES AND USES

### HYGIENE STATION

1. ACTIVITY VOLUMETRICS
2. TOILET CONFIGURATION
3. CLEANSING FEATURES
  - SHOWER
  - WASH BOWL
4. ACCESS VOLUMETRICS
5. MAINTENANCE ACCESS VOLUME
6. CONTAMINATION CONTROL/CONTAINMENT
7. WASTE PRODUCT HANDLING
8. WASTE PRODUCT 'STOWAGE' & TRANSFER
9. WET ITEM HANDLING/MANAGEMENT
10. VENTILATION
11. VIBRO/ACOUSTICS (DIFFICULT IN M/U)
12. AESTHETICS
13. PRIVACY
14. COMFORT & CONVENIENCE
15. ARRANGEMENT ALTERNATIVES-GROWTH
16. ODOR CONTROL/MANAGEMENT
17. ITEM(S) STOWAGE - VARIOUS
18. OTHER

### FOOD STATION

1. ACTIVITY VOLUMETRICS
2. FOOD/DRINK PREPARATION ACCESS
  - EASE OF PREPARATION (FULL MEAL/SNACK)
  - MULTIPLE CREW ACCESS(?)
  - ZONE DIFFERENTIATION
  - OTHER
3. STATION ARRANGEMENT
4. AESTHETICS & PLEASANTNESS OF SURROUND
5. MULTIPLE CREW ACCOMODATIONS
6. EATING FACILITY ACCOUTREMENTS
7. CONTAMINATION CONTAINMENT/CONTROL
8. ODOR CONTROL & VENTILATION
9. COMFORT FEATURES
10. VIBRO/ACOUSTRICS (DIFFICULT IN M/U)
11. WASTE PRODUCT HANDLING
12. WASTE PRODUCT 'STOWAGE' & TRANSFER
13. FOOD STOWAGE VOLUME & ACCESS/LOGISTICS
14. WASTE COMPACTING(?)
15. BACTERIAL CONTROL/MANAGEMENT
16. GENERAL ITEMS STOWAGE/ACCESS
17. OTHER - MANY!



## MOCKUP CANDIDATES AND USES

### HABITATION ZONE(S)

1. ACTIVITY VOLUMETRICS
2. TRAFFIC PATTERNS & FLOWS
3. ORIENTATION
4. ENTRY/EXIT FROM 1 ZONE TO 2ND(TRANSITION)
5. ACCESS VOLUMETRICS
6. MAINTENANCE ACCESS VOLUMETRICS
7. TRANSLATION AIDS
8. UNIQUE CREW ACCOMODATION ACCOUTREMENTS
9. ILLUMINATION
10. EMERGENCY ECLSS PANEL ACCESS & WARNING
11. RECONFIGURABILITY
12. ATTRACTIVE 'FURNISHINGS' & DECOR
13. COLOR & AESTHETICS
14. WINDOW(S) &/OR VIEW PORTS
15. CONTAMINATION CONTROL/MANAGEMENT
16. SAFE HAVEN INTEGRATION(?)
17. BASIC STATION COMMUNICATIONS ACCESS
18. OTHER

### GROUP GATHERING AREA

1. ACTIVITY VOLUMETRICS
2. GROUP I/F AND INTERACTION LAYOUT
3. ACCOMMODATIONS/FURNISHINGS/ACCOUTREMENTS
4. BASIC LAYOUT/ARCHITECTURE & ORIENTATION
5. WINDOWS OR VIEW PORTS
6. ITEM STOWAGE, SET-UP & TEAR-DOWN
7. TRAFFIC PATTERNS & FLOWS
8. PARTITIONING/RE-PARTITIONING
9. ISOLATION/PRIVACY
10. AESTHETICS
11. ILLUMINATION
12. VIBRO/ACOUSTICS(DIFFICULT IN M/U)
13. VENTILATION
14. EMERGENCY ECLSS PANEL ACCESS
15. COMMUNICATION PANEL ACCESS & WARNING
16. MULTI-PURPOSE UTILIZATION FEATURES
17. OTHER



## MOCKUP CANDIDATES AND USES

### LABORATORIES

5-30


1. ACTIVITY
2. INTERNAL LAYOUT
3. LAMINAR FLOW WORK BENCH (TYP)
4. EXPERIMENTS INTEGRATION
5. EXPERIMENT RACKS INSTALL/LAYOUT
6. CONTAM. PROTECT/MGMT/ISOLATION
7. SAFETY PRECAUTIONS
8. EMERGENCY PROVISIONS
9. EQUIPMENT/SUPPLIES STOWAGE
10. SAMPLE CHANGEOUT FACILITIES
11. EXPERIMENT REPLENISHMENT
12. OBSERVATION PROVISIONS
13. ILLUMINATION LOCATION/INTENSITY
14. WORK STATION LAYOUT/LOCATION
15. CONTROL PANEL LOCATION/LAYOUT
16. BODY POSITION RESTRAINTS
17. TRANSLATION/TRANSFER DEVICES
18. MAINTENANCE ACCESS PROVISIONS
19. COMMUNICATIONS (STD/EMERGENCY)
20. INTERNAL ACCOUTREMENTS
21. EXTERNAL WINDOW ARRANGEMENT
22. RECONFIGURABILITY
23. UTILITIES INTERFACES
24. VIBRO/ACOUSTICS
25. PERTURBATIONS IMPACT
26. OTHER



## MOCKUP FIDELITY

	MATERIALS				
	SOFT FOAMCOR	FOAMCOR/ WOOD	WOOD GR FIBERGLASS	METAL	COMBINATIONS
1. GEN. PURPOSE MODULE SHELL					
• 9 FT. LENGTH			X	X	
• 18 FT. LENGTH			X	X	
2. SAFE HAVEN		X	X		USE ITEM 1 (REMOVE/REPLACE)
3. MAINT/SER PRESSURE VOL.		X			" " " " "
4. HYGIENE STATION	X	X	X	X	" " " " "
5. MULTIPLE DOCKING ADAPTER		X	X	X	
6. AIRLOCK		X	X		
7. GEN. PURPOSE WORK STATION	X	X			" " " " "
8. SLEEP QUARTERS	X	X			" " " " "
9. HABITABLE ZONES	X	X			" " " " "
10. GROUP GATHERING AREA	X	X			" " " " "
(11) LABORATORIES		X	X	X	UNIQUE

## INTERIOR PALLET MODULAR INSERTION/REPLACEMENT






## WHAT VALUE MOCKUPS

( PREACHING TO THE CHOIR )

5-33



ORIGINAL PAGE IS  
OF POOR QUALITY



## AESTHETIC CONCERNS IN HUMAN PRODUCTIVITY

---

5-34

1. CAN THE EFFECTIVENESS OF THE CREW BE INCREASED BY ENVIRONMENTAL FACTORS SUCH AS:
    - DECOR
    - MATERIALS SELECTION
    - ENVIRON. VARIABILITY
    - COMFORT
    - CLEANLINESS
    - FEELING OF SPATIAL FREEDOM
  2. IT IS THOUGHT THAT INTRODUCING AESTHETIC & COMFORT FACTORS INTO THE SPACE STATION ENVIRONMENT MAY RESULT IN:
    - INCREASED EFFICIENCY
    - POSITIVE ATTITUDE MAINTENANCE
    - INCREASED OUTPUT
    - FEWER ERRORS
  3. IT IS SUGGESTED THAT THE IMPACT OF THESE FACTORS ON HUMAN PRODUCTIVITY OVER A 90 DAY PERIOD IN A CONFINED ENVIRONMENT (E.G., MOCKUP/SIMULATOR) WARRANTS NEAR-TERM CONCENTRATED NASA STUDY
-



## GENERAL MOCKUP UTILIZATION

1. MANAGEMENT VISIBILITY IDENTIFICATION
2. 3-DIMENSIONAL "SOLID" REPRESENTATION
3. DESIGN VERIFICATION TOOL
4. CUSTOMER/CONTRACTOR COMM EVAL. TECHNIQUE
5. PUBLIC RELATIONS FACILITY
6. DESIGN ENGINEERING EVALUATION TOOL
7. FORM & FIT ANALYSES
8. ALTERNATE LAYOUT ASSESSMENTS
9. MAINTENANCE ACCESS EVALUATIONS
10. EQUIPMENT ARRANGEMENT STUDIES
11. CABLE RUN PATH ANALYSES
12. CABLE LAY-UP MOCKUP DEVELOPMENT
13. ILLUMINATION FIXTURE LOCATION STUDIES
14. LIGHTING (SPOT/FLOOD) EXAMINATION
15. ANTHROPOMETRIC ASSESSMENTS
16. MAN-MACHINE INTERACTION EVALUATIONS
17. MULTI-ACTIVITY INTERACTION ANALYSES
18. INSTALLATION/REMOVAL TASK STUDIES
19. LOGISTICS ITEM TRANSFER DEMONSTRATIONS
20. RE-CONFIGURE/SHAPING - INTERNAL
21. SUB-COMPARTMENT RE-ARRANGEMENT ANALYSES




## GENERAL MOCKUP UTILIZATION

(con't)

- 22. STOWAGE COMPARTMENT LAYOUT STUDIES
- 23. SUIT DON/DOFF VOLUMETRIC ANALYSES
- 24. EMERGENCY ITEM ACCESS
- 25. FUNCTION TIME-LINE ANALYSES
- 26. EMERGENCY PROCEDURE CONDUCT DEMOS
- 27. TRANSLATION AID ASSESSMENT
- 28. COLOR/DECOR EVALUATIONS
- 29. TRAFFIC FLOW EXAMINATION
- 30. HATCH SWING & STOWAGE STUDY
- 31. LAYOUT ORIENTATION EVALUATIONS
- 32. BODY ORIENTATION ASSESSMENTS
- 33. CREW ENTRY-EXIT ANALYSES (INTERNAL)
- 34. WINDOW/VIEW-PORT SIZING/LOCATION
- 35. FURNISHINGS ARRANGEMENT & LAYOUT
- 36. WORK STATION INSTALLATION EXAMINATION
- 37. CONTAM. MGMT. & TECHNIQUE HANDLING STUDY
- 38. SAFE HAVEN INTEGRATION EVALUATIONS
- 39. MAXIMUM CREW LOADING VOLUME ANALYSES
- 40. BODY POSITION/RESTRAINT DEVICE LOCATION
- 41. CREW FUNCTION SIMULATION
- 42. OTHER



## CANDIDATE DEVELOPMENT SCHEDULE



\* Potential Longer Duration Study



## CONCLUSIONS

1. MOCKUPS PIVOTAL TO INVESTIGATION, RESEARCH, DESIGN & INTEGRATION
2. CERTAIN ELEMENTS OF HUMAN PRODUCTIVITY CAN BE ASCERTAINED
3. EARLY MOCKUP DEVELOPMENT WILL SUBSTANTIALLY AID IN STATION REQTS. DEVELOPMENT AND CONFIGURATION EVOLUTION
4. PRIMARY VOLUMETRICS FOR BASIC INTERNAL STATION NOT YET ESTABLISHED
5. IT IS CRITICAL TO ESTABLISH (EARLY) SAID VOLUMETRIC REQTS. FOR THE STATION 'LEST ENGINEERING DOES IT FOR US' AND WE 'LOSE AGAIN!'
6. WILL THE MOCKUP STUDIES RESULT IN VOLUMETRIC ALLOCATIONS EXCEEDING THE CURRENT SPACE STATION CDG ESTIMATES/LIMITATIONS ?
7. A COMBINED INDUSTRY MOCKUP STUDY DATA BASE CAN'T BE IGNORED
  - 'OLE B.C.' MIGHT BECOME THE I/F BATTLE GROUND TO BRING THIS TO THE FORE
  - REASONABLE COOPERATION/INTERACTION BY THE COMBINED STATION INTERESTED AEROSPACE COMMUNITY COULD RESULT IN A STRONG POSITION
8. INDUSTRY DEVELOPED MOCKUPS USUALLY HAVE A DEGREE OF PROPRIETARY FEATURES WHICH MAKES OPEN SHARING DIFFICULT
9. NASA MOCKUP DEVELOPMENT & USE WILL PERMIT CERTAIN LONG-TERM INVESTIGATIONS TO BE UNDERTAKEN WHICH ARE VERY IMPORTANT TO THE PROGRAM

EXPERIENCES  
WITH  
NEUTRAL BUOYANCY TESTING  
MOCKUPS

PRESENTED TO:  
SPACE STATION  
HUMAN PRODUCTIVITY  
WORKING GROUP

MARCH 2, 1984

PRESENTED BY:  
BOB DELLACAMERA  
(714) 896-5224

NASA QUESTION:

CAN AN EVA CREWMAN REMOVE AND REPLACE ELECTRICAL CONNECTORS  
ON TIMING UNIT?



NB-51

SPACE PLATFORM CONTINGENCY OPERATIONS

QUICK LOOK TEST REPORT #1      DATE: AUGUST, 1982

NEUTRAL BUOYANCY SIMULATION

SPACE PLATFORM CONTINGENCY OPERATIONS


TASK 1. AFT PAYLOAD PORT DEPLOYMENT/RETRACTION

TASK 2. CONTROL MOMENT GYRO(CMG) REMOVAL/REPLACEMENT

TASK 3. MANUAL HAND CRANK APPENDAGE DEPLOYMENT

# SPACE PLATFORM NEUTRAL BUOYANCY MOCK-UP

VFW323



NB-51

SPACE MAINTENANCE AND CONTINGENCY OPERATIONS SIMULATION

QUICK LOOK TEST REPORT #2

DATE: NOVEMBER 1982

NEUTRAL BUOYANCY SIMULATION

SPACE MAINTENANCE AND CONTINGENCY OPERATIONS SIMULATION


TASK 1. SOLAR ARRAY WING EXCHANGE

TASK 2. COLD PLATE MOUNTED BLACK BOX EXCHANGE

- ADJUSTABLE FOOT RESTRAINT EVALUATION
- BATTERY INSTALLATION
- FLUID DISCONNECT MATE/DEMATE
- OVERCENTER LATCH/BLIND MATING ELECTRICAL CONNECTOR
- D-SERIES (RECTANGULAR), ELECTRICAL CONNECTOR DEMATE/MATE
- CIRCULAR CONNECTOR (STANDARD AND COAX) DEMATE/MATE

TASK 3. SOLAR ARRAY BLANKET BOX EXCHANGE

# SPACE PLATFORM NEUTRAL BUOYANCY MOCK-UP



ORIGINAL PAGE IS  
OF POOR QUALITY

NB-51

SPACE MAINTENANCE AND SERVICING SIMULATIONS

QUICK LOOK TEST REPORT #3      DATE: SEPTEMBER 1983

TASK ACTIVITIES:

TASK 1. MANUAL HAND CRANK APPENDAGE DEPLOYMENT

TASK 2. COLD PLATE MOUNTED ORU EXCHANGE

- SINGLE FOOT ADJUSTABLE FOOT RESTRAINT EVALUATION
- SMALL BOX (50 LB) OVER CENTER LATCH FASTENING CONCEPT
- MEDIUM BOX (150 LB) COARSE THREAD CAPTIVE FASTENERS
- LARGE BOX (250 LB) FINE THREAD CAPTIVE FASTENERS

TASK 3. CONNECTOR TOOLS/ADJUSTABLE FOOT RESTRAINT EVALUATIONS

TASK 4. CONTINGENCY OPERATIONS


- MANUAL APPENDAGE JETTISON
- FLUID TRANSFER SIMULATION

TASK 5. STRUCTURAL MODIFICATION - PAYLOAD PORT STRENGTHENING

TASK 6. SATELLITE GROWTH ACTIVITY

# SPACE PLATFORM NEUTRAL BUOYANCY MOCK-UP SEPTEMBER TEST SERIES

VEB969



5-46

ORIGINAL PAGE IS  
OF POOR QUALITY

## SUMMARY OF NEUTRAL BUOYANCY TESTING

### ● SIGNIFICANT RESULTS

- DEMONSTRATED EVA CREWMAN FINE MOTOR ACTIVITIES ARE ACHIEVABLE WHEN SIMPLE AIDS WHICH ENHANCE PERFORMANCE CAPABILITIES ARE PROVIDED.
- DISCOVERED THAT CERTAIN TASKS WERE ACCOMPLISHED WITH LESS EFFORT WHEN THE EVA CREWMAN WAS AFFORDED ADDITIONAL MOBILITY BY RESTRAINTS OTHER THAN FIXED FOOT RESTRAINT PLATFORMS.
- ILLUSTRATED MANUAL TRANSLATION OF LARGE MASS ITEMS IS FEASIBLE, BUT MECHANICAL AIDS SHOULD BE PROVIDED TO ASSIST EVA TRANSLATIONAL OPERATIONS.
- DURING THE INSTALLATION PROCESS OF REPLACEABLE UNITS, APPLICATION OF ALIGNMENT INDICATORS (I.E., PINS, PLACARDS, GUIDES, ETC.) PROVIDES SIGNIFICANT ASSISTANCE TO THE EVA CREWMAN. THIS IS ESPECIALLY EVIDENT AS MASS AND SIZE INCREASE.

N85-29572

---

ROCKWELL EXPERIENCE  
APPLICATIONS TO AMES SPACE STATION MOCKUP  
HABITABILITY/PRODUCTIVITY STUDIES

PRESENTATION TO NASA  
AMES RESEARCH CENTER  
MOFFET FIELD, CALIFORNIA

MARCH 2, 1984

J. A. ROEBUCK  
CREW/HABITATION GROUP  
SYSTEMS ENGINEERING  
SPACE STATION PROGRAM



## PURPOSE OF BRIEFING

---

- ASSIST NASA/AMES RESEARCH CENTER WITH PLANNING FOR SPACE STATION MOCKUP STUDIES
- REVIEW MOCKUP LESSONS FROM ROCKWELL SPACECRAFT STUDIES
  - APOLLO-LEM THROUGH SPACE SHUTTLE
  - EARLY SPACE STATION
- ILLUSTRATE TYPICAL AND UNIQUE MOCKUP TECHNOLOGY APPLICATIONS

## POTENTIAL USES FOR SPACE STATION MOCKUPS

---

- VERIFY REQUIREMENTS DURING DESIGN

-OR-

- DEVELOP NEW REQUIREMENTS (BEFORE IMMERSION AND PARABOLIC FLIGHTS)


<u>AREAS OF CONCERN</u>	<u>AGENCY</u>	
	<u>CONTRACTOR</u>	<u>NASA/AMES</u>
□ CONTROL/DISPLAY LAYOUTS, FORMATS	•	●
□ WORK STATION DESIGN—REACH, CLEARANCE, FORCE	•	•
□ ADEQUATE LIGHTING, MARKINGS, COLOR	•	●
□ REFINE REACH, VISION, CLEARANCE MODELS FOR DRAWINGS/ COMPUTER ANALYSIS	•	•
□ INGRESS/EGRESS PATHWAYS, AIDS	•	●
□ HABITABILITY/PRODUCTIVITY STUDIES (LONG TERM)	•	●
□ MAINTENANCE AND PARTS EXCHANGE	•	•
□ INTERFERENCES—CORRECTIONS	•	•
□ NEW DETAILS, COMPLEX SHAPE DEVELOPMENTS	•	•
□ WIRING AND DUCTING ROUTINGS DEVELOPMENT	•	•
□ EMERGENCY OPERATIONS (IVA & EVA)	•	•
▪ PUBLIC AWARENESS SUPPORT— DOCUMENTARY FILMS, VIDEO TAPES, TV INTERVIEWS & NEWS	•	●

## RECOMMENDATIONS—GENERAL

---

- DON'T GET FANCY TOO SOON
    - GROSS WORKSPACE, LOW FIDELITY FIRST
    - BUILD UP GRADUALLY, CAREFULLY
  - BE FLEXIBLE, VARY KEY DIMENSIONS
    - DON'T SETTLE FOR ONE EASY ANSWER—SEEK MINIMUMS
    - DEVELOP A FEW PARAMETRIC DATA POINTS
    - PROVIDE TILT & ROLL CAPABILITY (ZERO-G SIMULATION)
  - SEEK LARGE RANGE OF BODY SIZES & SKILLS IN SUBJECT SELECTION
  - MEASURE DISTANCE, TIME, ANGLES, FORCES
    - THINK ABOUT DESIGNER NEEDS—CAN SHAPES BE DRAWN?
  - EVALUATE VISIBILITY & LIGHTING—CAN INFORMATION BE READ, PARTS BE DISTINGUISHED?  
PROVIDE NUMBERS
  - EXERCISE THE SPACE; CHECK FOR
    - SAFETY—PROJECTIONS, HAZARDS
    - PRODUCTIVITY—CONVENIENCE, VOLUME, REACH, TIME
    - HABITABILITY—HOW LONG CAN YOU LIVE IN IT?
      - ON-DUTY TIME
      - OFF-DUTY TIME
-


ORIGINAL PAGE IS  
OF POOR QUALITY



CREW STATION REACH AND VISION VERIFICATION  
TESTING CONDUCTED IN WORKSPACE ANALYZER

REACH ENVELOPE MEASUREMENTS AND CLEARANCE EVALUATIONS

---




APOLLO COMMAND MODULE MOCKUP EXAMPLE

---

ORIGINAL PAGE IS  
OF POOR QUALITY


## PARALLEL PLANE GRIDS ON TRANSPARENCY FOR EYE POSITION MEASUREMENTS

### APOLLO COMMAND MODULE APPLICATION





## BACKGROUND GRID PARALLAX ERRORS

5-55



ORIGINAL PAGE IS  
OF POOR QUALITY

## LOW-PARALLAX GRID FRAME SYSTEM




### APPLICATION TO MOCKUP EVALUATION

- GRID ON FOME-COR
- MOUNTED WITH TAPE
- IN PLANES OF MAX. DIAMETERS

ORIGINAL PAGE IS  
OF POOR QUALITY




# Rotation Hand Controller Adjustment Range




5-57

ORIGINAL PAGE IS  
OF POOR QUALITY

# Ejection Seat Modifications for Shuttle Ascent Mode




# TRUNK LENGTH AND EYE-TO-SEAT CHANGES WITH BODY ATTITUDE



ORIGINAL PAGE IS  
OF POOR QUALITY

## TYPICAL VDT WORKSTATION "MEAN BODY POSTURE" IN EARTH NORMAL ENVIRONMENT


---



5-60

- SEAT/BACK ANGLES CONDITIONED BY BODY LOADS
- GRAVITY HOLDS ARMS DOWN AGAINST BODY, HANDS LOW - APPROXIMATELY TABLE HEIGHT
- HEAD NEAR VERTICAL FOR MINIMAL EFFORT
- LINE OF SIGHT SLIGHTLY BELOW HORIZON
- NATURAL SEPARATION OF CRT SCREEN AND KEYBOARD OR OTHER CONTROLS
- OPTIMAL WORK STATIONS NOT YET PROVIDED IN MOST INDUSTRY SETTINGS IN SPITE OF MANY STUDIES. FOR EXAMPLE:
  - TYPEWRITER KEYBOARD RECTANGULAR LAYOUT STANDARD (NOT OPTIMUM FOR WRIST ACTION)
  - INSUFFICIENT ADJUSTMENTS

## WEIGHTLESSNESS IMPACT ON VDT WORKSTATION DESIGN REQUIREMENTS



MESSAGE: RESEARCH NEEDED TO DEFINE LONG-TERM  
HUMAN-COMPUTER INTERFACES IN SPACE

- NEW PREFERRED ARM ANGLES
- NEW PREFERRED SHOULDER ANGLES
- NEW LINE OF SIGHT REFERENCE
- NEW LEG CLEARANCE REQUIREMENTS
- NEW RESTRAINTS TO BE DETERMINED
  - RESIST PUSH-OFF FORCES ON KEYS
  - NEW CONSTRAINTS ON REACH ENVELOPE
- PROBABLE REORIENTATION OF KEYBOARDS
- POTENTIAL CRT-KEYBOARD INTERFERENCE
- POSSIBLE NEED FOR FINGER GRIPS/GUIDES
- POSSIBLE LIGHTER LOADS ON KEYS/TOUCH  
SENSORS
  - LIGHT-PEN OPTION

# MOCKUP TILT & ROLL BENEFITS EVALUATION

★ ROCKWELL EXPERIENCE HAS VERIFIED VALUE OF 1-G MOCKUP ORIENTATION OPTIONS:

ORIENTATION & PROGRAM APPLICATIONS	BENEFIT
<ul style="list-style-type: none"> <li>• SIMULATE LAUNCH ATTITUDE (NOSE UPWARD)—APOLLO, SHUTTLE CREW COMPARTMENT</li> </ul>	<ul style="list-style-type: none"> <li>• BODY STRETCH: HEAD, HAND &amp; EYE POSITION ACCURACY</li> <li>• INGRESS/EGRESS SIMULATING UNUSUAL POSITION</li> </ul>
<ul style="list-style-type: none"> <li>• HORIZONTAL ATTITUDE SIMULATION OF TUNNEL TRANSFER, PARTS HANDLING, POST-LANDING ORBITER EGRESS—NORMAL AND EMERGENCY—APOLLO, SHUTTLE CREW COMPARTMENT, ASTP TRANSFER TUNNEL</li> </ul>	<ul style="list-style-type: none"> <li>• EASE OF HORIZONTAL MOVEMENT, MINIMIZE CONTACTS WITH FLOOR &amp; SIDES (ZERO-G SIM.)</li> <li>• CORRECT ATTITUDE FOR ORBITER EGRESS, RETURN FLIGHT</li> </ul>
<ul style="list-style-type: none"> <li>• 360° IN SAGITTAL PLANE—SIMULATION OF BODY MOTION IN STRAPS ON APOLLO COUCH—ROTATION TABLE</li> </ul>	<ul style="list-style-type: none"> <li>• FIRST APPROXIMATION OF HEAD AND KNEE MOTION (ONE-G)</li> </ul>
<ul style="list-style-type: none"> <li>• ROTARY SPACE STATION SIMULATION—MOCKUP LIVING QUARTERS ON END OF ARM</li> </ul>	<ul style="list-style-type: none"> <li>• EVALUATE CORIOLIS EFFECTS</li> <li>• EVALUATE VARIABLE G-FIELD EFFECTS</li> </ul>


5-62

## ZERO-G SIMULATION BODY SUPPORTS

---


- BODY SUPPORTS REQUIRED TO EXPLOIT DIFFERING MOCKUP ORIENTATIONS:

### TYPICAL SYSTEMS



- CABLE SUPPORT WITH BODY SANDWICH PANELS, COUNTER WEIGHTS
  - APOLLO TUNNEL TRANSFER: HATCH PROBE & DROGUE REMOVAL
  - EVA AND IVA SIMULATION

5-63



- HELIUM BALLOON AND PARACHUTE HARNESS
  - EVA SIMULATION

- NEGATOR SPRINGS, CABLES AND CUFFS ON ARMS
  - IVA SIMULATION OF WEIGHTLESSNESS

- AIR-BEARING SUPPORT FLOORS, COUNTER-BALANCED CHAIRS

## SUMMARY

---

- RECOMMENDED USAGES FOR AMES RESEARCH OFFERED
- BRIEF SAMPLE OF SPECIAL MOCKUP USAGE TECHNIQUES PRESENTED
- MOCKUP TECHNOLOGY INVOLVING HUMAN INTERFACES HAS IMPROVED DURING 20 YEARS OF SPACECRAFT EXPERIENCE—NOW AVAILABLE FOR SPACE STATION

✓ APOLLO-LEM	} SPACE STATION SYSTEMS
✓ LUNAR FLYER	
✓ EARLY SPACE STATION	
✓ SHUTTLE	
✓ APOLLO-SOYUZ TEST PROGRAM	

- KEY CONCERNS IN MOCKUP EVALUATIONS
  - COST-EFFECTIVE LEVELS OF FIDELITY
  - VARIABLE VOLUME & SHAPE CAPABILITY
  - MEASUREMENTS WHICH CAN BE USED FOR GRAPHIC ANALYSIS
    - ✓ LAYOUT DRAWINGS
    - ✓ COMPUTER MODELING
    - ✓ TIME DATA
  - ACCURATE, COST-EFFECTIVE MEASUREMENT METHODS AND SUBJECT SELECTION
    - ✓ PHOTOS—GRIDS
    - ✓ HAND MEASURES
    - ✓ VISUAL ALIGNMENT AIDS
    - ✓ DEFINE SUBJECT'S BODY DIMENSIONS & MOBILITY



---

Space Station

**The Role of Mock-Ups in the  
Development of Orbital  
Replaceable Units (ORU)**

5-65

Human Productivity Working Group  
Ames Research Center — NASA  
March 2, 1984

Gary A. Johnson  
Crew Systems

85-29573

---

## **Large Modular Orbital Replaceable Unit (ORU)**

5-66

## ORBITAL REPLACEABLE UNIT - ORU

---

- AN ORU IS ANY UNIT SPECIFICALLY DESIGNED FOR REPLACEMENT WHILE IN ORBIT
- TYPES:
  - COMPONENT (E.G., SOLAR ARRAYS, CMGS, INDIVIDUAL ELECTRONIC BOXES, ANTENNAS)
  - MODULAR - A COLLECTION OF RELATED UNITS IN SINGLE PACKAGE FOR TO OPTIMIZE MAINTAINABILITY (E.G., BATTERIES, THERMAL CONTROL PUMP PACKAGE, SELECTED GROUPS OF ELECTRONIC BLACK BOXES) - MAY HAVE INTEGRAL COLDPLATE
- NUMBER AND RATIO OF TYPES IS A FUNCTION OF THE PARTICULAR SPACECRAFT (I.E., SPACE STATION, SPACE PLATFORM, LEO FREE FLYER, GEO FREE FLYER)

## LARGE MODULAR ORU APPLICABILITY

---

- MAINTENANCE
- GROWTH
- UPGRADING
- ASSEMBLY

## LARGE ORU REPLACEMENT TESTS

---

### PURPOSE:

TO DEVELOP AND VALIDATE HARDWARE DESIGN AND OPERATIONS FOR ON-ORBIT REPLACEMENT OF LARGE MODULAR ORU'S. THESE TESTS WILL PROVIDE GENERIC DATA FOR ANY SPACECRAFT IN WHICH LARGE ORU'S ARE AN OPTION, SUCH AS SPACE STATIONS AND SPACE PLATFORMS

### TEST METHODS:

- O 1-G TESTS - SHIRTSLEEVE SUBJECTS WITH SIMPLE PENDULUM AND COUNTERBALANCE SUSPENSION - NO RMS (AT TRW)
- O NEUTRAL BUOYANCY TESTS - PRESSURE-SUITED SUBJECTS WITH PARTIAL SP FRAME, RMS, MFR, AND MMU (AT MSFC)

## LARGE ORU REPLACEMENT TESTS

---

### OBJECTIVES:

#### 1-G TESTS:

- 0 VERIFY MECHANICAL OPERATION OF ORU STRUCTURAL, FLUID AND ELECTRICAL CONNECTIONS
- 0 PRELIMINARY EVALUATION OF HANDLING, GUIDING, ACCESS FEATURES
- 0 DEVELOPMENT OF NEUTRAL BUOYANCY TEST PROCEDURES

#### NEUTRAL BUOYANCY TESTS:

- 0 DEVELOP AND VERIFY ORU/EVA/RMS/MFR/MMU INTERFACES
- 0 VERIFY HANDLING, INSERTION, AND REMOVAL OF LARGE HIGH DENSITY MODULES
- 0 VERIFY MANUAL OPERATION OF STRUCTURAL, FLUID AND ELECTRICAL ATTACHMENT MECHANISMS
- 0 VERIFY ACCESS, VISION, TORQUE, FEEDBACK, AND SAFETY PARAMETERS
- 0 OBTAIN TASK AND TASK ELEMENT TIMES
- 0 DEVELOP AND VERIFY BODY POSITIONS AND BODY RESTRAINTS
- 0 VERIFY COMPATIBILITY OF CREW SAFETY TETHERING AND EQUIPMENT TETHERING OPERATIONS WITH ORU OPERATIONS
- 0 VERIFY FUNCTION OF MODULE ALIGNMENT GUIDES
- 0 INVESTIGATE TEMPORARY PARKING OPERATIONS

## APPROACH USED TO DEVELOP ORU REPLACEMENT OPERATIONS


---

- o UTILIZE RESULTS FROM SPACE TELESCOPE AND OTHER PROGRAMS TO AVOID UNIQUE SOLUTIONS
- o ANALYSIS AND ENGINEERING LAYOUTS OF OPERATIONS/PROCEDURES
- o 1/20 SCALE MODEL EVALUATION
- o 1-G (UNSUITED) TESTS USING FULL SCALE FOAM-CORE MOCKUP OF ORU AND FRAME SEGMENT
- o 1-G (UNSUITED) TESTS USING FULL SCALE NEUTRAL BUOYANCY TEST UNIT
- o NEUTRAL BUOYANCY TESTS WITH SUITED SUBJECTS AT NASA/MSFC

5-71

# MODULAR ORU


5-72



SPACE TELESCOPE  
SCIENTIFIC INSTRUMENT  
800 POUNDS




HALF MODULE



SPACE PLATFORM  
ORU  
200 TO 1500 POUNDS




# PORT ORU REPLACEMENT



PROGRAM MANAGEMENT DIVISION


ORIGINAL PAGE IS  
OF POOR QUALITY

# MODULAR ORU MOCKUP



ORIGINAL PAGE IS  
OF POOR QUALITY

# MODULAR ORU AND ORU MOUNTING FRAME



ORIGINAL PAGE IS  
OF POOR QUALITY

ORU HARDWARE AND OPERATIONS  
DESIGN FEATURES


---

5-76

- 0 VISIBILITY/ACCESS COMPATIBLE WITH SUITED CREWMEN
- 0 ADAPTER PROVIDED FOR PORTABLE RMS GRAPPLE FIXTURE FOR MODULE TRANSFER
- 0 STANDARD NASA HANDHOLDS AND FOOT RESTRAINTS
- 0 SHARP CORNERS, EDGES AND PROTRUSIONS ELIMINATED
- 0 ALL LOOSE EQUIPMENT TETHERED
- 0 STANDARD MUSHROOM RATCHET WRENCH USED FOR ALL FASTENERS AND ACTUATORS  
(7/16" HEX - DOUBLE-PLUS HEIGHT)
- 0 "J"-HOOK FASTENERS (TEMPORARY RESTRAINT INHERENT)
- 0 NO ENGAGEMENT OF THREADED FASTENERS (BASELINE)
- 0 RUNNING FRICTION IN ALL TOOL OPERATED FASTENERS AND ACTUATORS
- 0 ALIGNMENT GUIDES FOR MODULE
- 0 STATUS (MATE/DEMATE) INDICATORS FOR FLUID AND ELECTRICAL CONNECTOR
- 0 OPERATION MARKINGS FOR ACTUATORS
- 0 ADAPTER PROVIDED FOR DOCKING MMU TO ORU WITH ROTATION JOINT FOR  
ADDRESSING TASKS

MODULAR ORU NEUTRAL BUOYANCY TEST UNIT

---




5-77

ORIGINAL PAGE IS  
OF POOR QUALITY

MODULAR ORU  
1-G PENDULUM TEST


---

5-78



INSTALLATION OF MODULAR ORU USING  
PORTABLE FOOT RESTRAINTS


---



ORIGINAL PAGE IS  
OF POOR QUALITY

REMOVAL OF MODULAR ORU USING MFR

---




5-80

ORIGINAL PAGE IS  
OF POOR QUALITY



# INSTALLATION OF ORU USING MMU


---



ORIGINAL PAGE IS  
OF POOR QUALITY

ROTATING MMU TO ADDRESS ORU FASTENERS


---



5-82

# MANNED MANEUVERING UNIT (MMU) WITH MODULAR ORU

---



5-83

ORIGINAL PAGE IS  
OF POOR QUALITY

## NEUTRAL BUOYANCY TEST RESULTS

---

5-84

- ALL THREE MODES (PFR, MFR, MMU) FEASIBLE FOR REPLACEMENT OF LARGE MODULES
- MFR MODE MOST EFFICIENT - WHERE RMS ACCESS IS AVAILABLE
- POST/TUBE ALIGNMENT IS EFFECTIVE - NO BINDING
- J-HOOK MECHANICAL FASTENERS - EASY TO OPERATE AND PROVIDE TEMPORARY RESTRAINT
- HAND TOOL DRIVEN ELECTRICAL AND FLUID CONNECTOR MATE/DEMATE MECHANISMS ARE EFFECTIVE
- TETHER APPROACH FOR PARKING IS FEASIBLE -
- ALL OPERATIONS ARE COMPATIBLE WITH A7L TEST SUIT - SHUTTLE PRESSURE SUIT WOULD ENHANCE OPERATIONS
- FOOT RESTRAINTS ARE MORE EFFECTIVE AND SAFER THAN HANDHOLDS-ONLY, FOR LARGE MODULE HANDLING - ONE CREWMAN IN FOOT RESTRAINT IS ADEQUATE
- TORQUE (25 FT/LBS) AND NUMBER OF TURNS (3-5) ON FASTENERS AND HEX DRIVES COMPATIBLE WITH RATCHET WRENCH/HANDHOLD APPROACH
- ONE INCH HEX HEIGHT PREFERRED OVER "DOUBLE-HEIGHT" (1/2 IN.) - BETTER TOOL STABILITY

## NEUTRAL BUOYANCY TEST RESULTS (CONT)

---

- ONE-MAN OPERATIONS ARE FEASIBLE FOR ALL THREE MODES BUT TWO-MAN OPERATIONS ARE PREFERRED FOR MODULE CONTROL IN PFR MODE
- MMU/ORU/PRESSURE SUIT INTERFACES CAN BE DEVELOPED IN NBF - FREE FLYING DYNAMICS NEED COMPUTER AND 6 DOF SIMULATION
- ANALYTICAL AND MOCKUP DETERMINATION OF FOOT RESTRAINT LOCATIONS IS EFFECTIVE
- SOME DIFFICULTY IN MATING ALTERNATE FLUID CONNECTOR BOLTS - LEARNING CURVE
- TASK TIMES
- UTILIZATION OF FOAM-CORE MOCKUPS ARE VERY EFFECTIVE IN DEVELOPING HARDWARE AND PROCEDURES
- SIMPLE COUNTERBALANCE PENDULUM (1-G) TESTS ARE EFFECTIVE IN PRELIMINARY TESTING OF ALIGNMENT AND ATTACHMENT HARDWARE FOR LARGE MODULES
- NEUTRAL BUOYANCY TESTS SHOULD INCLUDE SAFETY TETHERS, MINI WORK STATION (MWS) AND WORK TETHERS TO ENHANCE FIDELITY
- SIGNIFICANT AMOUNT OF GENERIC DATA ON EVA, RMS, MFR, AND MMU OPERATIONS OBTAINED


C-9  
5-85

---

## **Solar Array Subsystem**

5-86

SOLAR ARRAY MOCKUP  
ELECTRICAL CONNECTOR MATING




5-87

ORIGINAL PAGE IS  
OF POOR QUALITY


## BOX TO WING MECHANICAL INTERFACE

---






S/A BOX REMOVAL  
CREWMEN AT BOTH ENDS



ORIGINAL PAGE IS  
OF POOR QUALITY

NEUTRAL BUOYANCY TEST  
BLANKET BOX CHANGOUT USING MANIPULATOR  
FOOT RESTRAINT

---



ORIGINAL PAGE IS  
OF POOR QUALITY

1. Report No. NASA TM 86673		2. Government Accession No.		3. Recipient's Catalog No.	
4. Title and Subtitle PROCEEDINGS OF THE SEMINAR ON SPACE STATION HUMAN PRODUCTIVITY				5. Report Date April 1985	
				6. Performing Organization Code	
7. Author(s) Compiled by Marc M. Cohen and Erika Rosenberg*				8. Performing Organization Report No. 85011	
9. Performing Organization Name and Address Ames Research Center, Moffett Field, California 94035 *San Jose State University, San Jose, California				10. Work Unit No.	
				11. Contract or Grant No.	
12. Sponsoring Agency Name and Address National Aeronautics and Space Administration Washington DC, 20546				13. Type of Report and Period Covered Technical Memorandum	
				14. Sponsoring Agency Code	
15. Supplementary Notes Point of contact: Marc M. Cohen, Ames Research Center, MS 239-C, Moffett Field, CA 94035, (415) 694-5385 or FTS 464-5385					
16. Abstract  As NASA prepares plans to develop a space station, one of the major human factors study tasks is to develop an approach to crew safety. NASA has always been a leader in the field of safety consciousness and recognizes that safety will be the key to reliability and human productivity in the space station.  In evaluating safety strategies, it is also necessary to recognize both qualitatively and quantitatively how this space station will be different from all other spacecraft. It is recognized that the major difference between a space station and previous spacecraft is the role of human factors and extra-vehicular activity (EVA). In the project, a model of the various human factors issues and interactions that might affect crew safety is developed.					
17. Key Words (Suggested by Author(s)) Space station Crew safety Internal contamination Space architecture				18. Distribution Statement  Unlimited  Star category* 54	
19. Security Classif. (of this report) Uncl		20. Security Classif. (of this page) Uncl		21. No. of Pages 741	
				22. Price* A99	